


History of original corner establishment:

Corner originally established by Frank W. Campbell on July 23, 1883, under contract No. 468, as follows:

Set a basalt stone 12"x 8"x 7", 8" into the ground marked "1/4" on the north face, from which:

- A 10" Pine bears S24°W, 20 links (13.2 feet).
- A 10" Pine bears N23°E, 27 links (17.82 feet).



Description of corner evidence found:

The original corner stone is solidly set in the ground 3 inches. The stone measures 12"x 8"x 7" and is marked "1/4" on the north face and "X" on the top. From which:

- A root hole and decayed pine log with no remaining marks bears N23°E, 17.82 feet.
- A root hole bears S24°W, 13.2 feet. Nothing left of this tree.
- The channel of a small creek which flows southerly bears west 33.0 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, set a 2 1/2" by 30" aluminum pipe, 30" into the ground surrounded by a small mound of stones. Bury the corner stone along the north side of the pipe. A 3 1/4" aluminum cap attached is marked as shown in the diagram above. From which:

- A 8" Western Larch scribed "1/4 S23 BT" bears N71°E, 73.5 feet.
- A 14" Douglas-fir scribed "1/4 S26 BT" bears S22°E, 52.6 feet.
- A 11" Lodgepole Pine scribed "1/4 S23 BT" bears N22°W, 56.8 feet. This bearing tree is west of the creek.
- A 27" Douglas-fir scribed "1/4 S26 BT" bears S74°W, 32.9 feet. This bearing tree is in the creek west of the corner.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze and a 54-3, Bearing Tree sign nailed above the blazes and a 54-9, Land Survey Monument sign nailed to the back.

Magnetic Declination: 22° E

NAD1983 Geographic Position (+ or - 2 to 6 meters)
Latitude 45-01-33.730 N
Longitude 118-35-08.470 W

Witnessed by: Troy Allen



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

(COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

☆ U.S. GOVERNMENT PRINTING OFFICE • 1983-793-276

Date 10-93
Rec'd By KR
No. 93-76-R

R-19