


History of original corner establishment:

Corner originally established by Frank W. Campbell on July 26, 1883, under contract No. 468, as follows:

Set a post for the section corner from which:

- A 10" Pine bears N68° E, 37 links (24.42 feet).
  - A 10" Pine bears S39° E, 34 links (22.44 feet).
  - A 27" Tamarack bears S59° W, 132 links (87.12 feet).
  - A 13" Tamarack bears N50° W, 52 links (34.32 feet).
- Each tree was scribed per the surveying instructions.



Description of corner evidence found:

The decayed remains of the corner post were found to a depth of 12".  
 A 13" Western Larch snag with scribes visible on a charred and mostly healed face bears N50° W, 34.32 feet.  
 A 26" Western Larch with double healed blazes bears S59° W, 87.12 feet.  
 The original SE and NE bearing trees are gone.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by the remains of the original corner post, set a 2 1/2 inch by 30 inch aluminum pipe 28 inches into the ground with a 3 1/4 inch aluminum cap attached which is marked as shown in the diagram above. From which:

- A 22" Western Larch bears N9° 30' E, 45.5 feet scribed "T6SR34ES21 BT".
- A 8" Lodgepole Pine bears S79° E, 7.5 feet scribed "T6SR34ES28 BT".
- A 7" Lodgepole Pine bears N43° W, 26.8 feet scribed "T6SR34ES20 BT".

Each new bearing tree is scribed on double blazes, has a 3/4" brass washer, marked "1636", nailed flush to the lower scribed face and has a 54-3, Bearing Tree sign nailed above the blaze and a 54-9, Land Survey Monument sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on June 23, 1993. Magnetic declination: 20° E.

NAD1983 Geographic Position (+ or - 2 to 6 meters):  
 Latitude 45-01-34.624 N  
 Longitude 118-38-12.006 W

Witnessed by: Shane Sills and Trina Alden

REGISTERED PROFESSIONAL LAND SURVEYOR  
*Dennis L. Gaylord*  
 OREGON JULY 14, 1978  
 DENNIS L. GAYLORD  
 1636  
 EXPIRES 12/31/93

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 7-93  
 Rec'd By KK  
 No. 93-61-R