

USDA-FOREST SERVICE  
Index  
File No. V-11  
T. 6 S.  
Merid. Willamette

R. 34 E.

**CORNER RECORD (SEARCH)**  
(Ref. FSM 5151.4)


R.D. North Fork John Day  
N.F. Umatilla

County Umatilla  
State Oregon

Tract or  
Survey No.

Cor.  
No.

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

NONE

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By  
Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the junction of roads 52 and 5200-527 walk up 5200-527 approximately 350 feet. The corner is located on the northwest side of the road approximately 40 feet near the top of the cut bank.

**PLANE COORDINATE POSITION DATA**

State:                      Zone:  
X:  
Y:  
Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 22" in the ground.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 19" in the ground, N. 32-02 E., 38.42 feet.  
5" Lodgepole Pine, S. 48 1/4 E., 17.4 feet, scribed "1/4 S33" "BT" on double blaze.  
9" Lodgepole Pine, S. 10 1/4 W., 33.8 feet, scribed "1/4 S33" "BT" on double blaze.  
RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 18" in the ground, N. 48-57 W., 35.45 feet.

Work Done By D. Schlaich Title Land Surveyor Date 09/1997 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_  
Certified Corner Record Prepared?  Yes No Filed At: Umatilla County Surveyor's Office Date 11/1997

REMARKS