

USDA-FOREST SERVICE

Index

File No. C19

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 7S R. 31E

R.D. N.F. John Day County Grant

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T7S R31E

C $\frac{1}{4}$

S 2

1993

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is approximately 600 feet Northwest up drainage behind Dale Store.

Signature

William R. Wells

Title

PLS

Division

Headquarters

Pendleton, OR

Date

1/19/94

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

A 2 1/2" aluminum cap on 2 1/2" X 30" aluminum pipe, 24" in ground with mound of stone to cap, marked as shown in corner diagram.
Set steel fence post with sign 54-9 and 54-2 attached 4.4 feet South of monument.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 13" ponderosa pine bears North - 40.5 feet, scribed: C 1/4 S2 BT.
A 11" ponderosa pine bears S51°E-98.1 feet, scribed: C 1/4 S2 BT.
A 9 1/2" ponderosa pine bears S19°W-60.3 feet, scribed: C 1/4 S2 BT.
A 17" ponderosa pine bears N33°W-43.6 feet, scribed: C 1/4 S2 BT.
New bearing trees have a brass washer stamped "PLS 1106" nailed to face of blaze. Attached sign 54-3 and 54-9, painted face of blaze and a 6" red band around each bearing tree.

Work Done By. WR Wells Title PLS Date 8/26/93 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: GRANT CO. SURVEYOR'S OFFICE Date: 1/94

REMARKS

This corner was established as part of a USFS contract.

Index File No. C19 T. 7S R. 31E M. Willamette Tract or Surv. No. Cor.