

Index

File No.

T. 7 S. R. 33 E.

Merid. WILLAMETTE

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:  
 Filed At.:  
 Object Ident.:  
 Ident. By:

*Signature*

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North  
 X: 2,464,494.10'  
 Y: 467,913.33'  
 Datum: NAD1927

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NORTH FORK JOHN DAY

N.F. UMATILLA

County GRANT

State OREGON

Tract or

Survey No. NFJD UNIT

Cor.

No. AP-3399

DESCRIBE CORNER MONUMENT FOUND

NONE:

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE:

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct of roads 1010 and 5505, travel northerly on road 5505 approx. 2.10 miles. Then walk East approx. 1700 feet to the corner which is located in a slight draw at an elevation of 5360 feet.

*Signature*

D. Schlaich

*Title*

Land Surveyor

*Division*

*Headquarters*

S.O.

*Date*

07/16/92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 42" aluminum rod, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFJD WILDERNESS ELEV 5360 AP-3399 RLS 2308 1992".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

9" Lodgepole Pine, N. 64° E., 15.1 ft., mkd. "WB/3399""BT".

12" Douglas Fir, S. 38° E., 56.6 ft., mkd. "WB/3399""BT".

Both BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich

Title Land Surveyor

Date 07/16/92

State Registration No.  
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No.

T.

7 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD UNIT

Cor.

AP-3399