

USDA-FOREST SERVICE

Index  
File No.

T. 7 S. R. 33 E.  
Merid. WILLAMETTE

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:  
Filed At.:  
Object Ident.:  
Ident. By:

*Signature*

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North  
X: 2,470,022.71'  
Y: 462,826.70'  
Datum: NAD1927

CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)

R.D. NORTH FORK JOHN DAY County GRANT  
N.F. UMATILLA State OREGON

Tract or  
Survey No. NFJD UNIT

Cor.  
No. AP-3304

DESCRIBE CORNER MONUMENT FOUND

NONE:

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE:

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct of road 5505 and trail 3007 travel easterly on the trail approx. 8300 feet to AP-3303 which is set on the trail. From AP-3303 the corner is located N. 12° W., 118.5 feet.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/11/92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 23" in the ground, mkd. "NFJD WILDERNESS AP-3304 RLS 2308 1992".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

9" Lodgepole Pine, N. 68° E., 14.9 ft., mkd. "WB/3304""BT".

6" Lodgepole Pine, N. 51° W., 12.7 ft., mkd. "WB/3304""BT".

Both BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **06/11/92**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

**7 S.**

R.

**33 E.**

M.

**W.M.**

Tract or Survey No.

**NFJD UNIT**

Cor.

**AP-3304**