

USDA-FOREST SERVICE

Index

File No.

T. 7 S. R. 33 E.
Merid. WILLAMETTE


CORNER RECORD (SEARCH) v.
(Ref. FSM 7151.4)

R.D. NOTH FORK JOHN DAY County GRANT
N.F. UMATILLA State OREGON

Tract or
Survey No. NFJD UNIT

Cor.
No. AP-3330

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:
Filed At:
Object Ident.:
Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct of road 5505 and trail 3007 travel easterly on the trail approx. 5600 feet.
The corner is located 100 feet northerly of the trail.

PLANE COORDINATE POSITION

State: Oregon Zone: North
X: 2,467,650.92'
Y: 462,510.82'
Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

08/28/92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, 35" in the ground, mkd. "NFJD WILDERNESS AP-3330 RLS 2308 1992".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

5" Western Larch, S. 31° W., 48.9 ft., mkd. "WB/3330""BT".

7" Western Larch, S. 19 3/4° E., 42.6 ft., mkd. "WB/3330""BT".

Both BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich

Title Land Surveyor

Date 08/28/92

State Registration No.
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No.

T.

7 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD UNIT

Cor.

AP-3330