

Index

File No. X-01

T. 7 S. R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. North Fork John Day

N.F. UMATILLA

County GRANT

State OREGON

Tract or

Survey No. NFJD UNIT

Cor.

No. AP-3302

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,472,644.07'

Y: 461,377.34'

Datum: NAD1927

DESCRIBE CORNER MONUMENT FOUND

Found a stone 18" by 12" by 6" in a loose mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

24" Douglas Fir, N. 48° E., 36.0 ft., with healed face.

Root hole, with windthrown 24" Douglas fir, S. 82° W., 52.6 feet.

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 5505 and 5505-170, travel southeasterly on 5505-170 approx. 2.28 miles to the end of the road. From the end of the road walk easterly approx. 800 feet to the corner which is located on the top of Kelsay Butte.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/02/92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set in place of the stone a 2 1/2" by 30" aluminum pipe, with 3 1/4" aluminum cap, 24" in the ground and surrounded it with a mound of stone (corner stone was placed in the mound of stone on the north side of the monument), mkd. "T7S R33E

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

7" Douglas Fir, S. 76° E., 37.5 ft., mkd. "1/4 S31""BT".

9" Lodgepole Pine, S. 55° W., 69.4 ft., mkd. "1/4 S36""BT".

6" Lodgepole Pine, S 89° W., 31.5 ft., mkd. "1/4 S36""BT".

New BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **06/02/92**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **YES**

Filed At: **Grant Co.**

Date **08/31/92**

REMARKS

Index File No.

X-01

T.

7 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD UNIT

Cor.

AP-3302