

Cont. No. 95

110
110B

Township No. N. R. 30 E.

Rec'd Dec 6 1860

18.30

Washington Transcript made

D. N. Murphy

xx

Rec'd

Field Notes ^{of the survey} of the subdivision
 lines of Township No 1 North
 of the Base Line of Range No
 30 East of the Willamette
 Meridian, in the State of
 Oregon, by Wm B Campbell
 deputy surveyor, under his
 contract No 95, bearing date
 the 19th day of September
 1860,

Commenced Oct 30/60
 Completed November 26th 1860

Index Diagram.

6	5	4	3	2	1
49	48	35	26	17	9
47	8	34	9	10	11
46	45	33	24	15	7
18	17	32	16	15	14
43	42	32	22	14	6
19	20	31	21	22	23
41	39	30	20	12	4
31	29	28	27	26	25
38	37	38	19	11	3
31	32	33	34	35	36

Township 1 N. Range 30 E. Tarrant Co. Texas
chain

West On a true line between sec 29 & 32
40.14 1/2 ^{draw chain & stake} Set a post for quarter sec. corner, level
& raised ~~44~~ mound of earth with trench
spits, as per instructions

80.29 The corners sec 29 30 31 & 32 - 50
Land rolling prairie. Soil
good 2 in state

West On Random line between sec 30 & 31,
Variation 20° SE

~~100~~ Indian Trail corner N.E. & S.W.
and commenced ascent.

~~15.00~~ To top of ascent. +50

~~23.00~~ Commenced descent.

40.00 ^{40.00} Temporary quarter sec post. - 50

~~52.50~~ To foot of descent - 100

~~54.00~~ Cross station to second

87.67 Intersect West boundary of Township +80

87.67 at post. corners sec 30 & 31

150

Township 1 Range 30 E. Tiltamott Precinct
chains

West, On a random line between Sec 19 & 20,
Variation $19^{\circ}45' E$,

~~28.00~~ Big trail before noted corner

40.00 Set a temporary quarter sec post,

87.00 Intersect West boundary of Township

1000s. South of post corner to sec 19 & 20,

$89^{\circ}36' E$. On a true line between Sec - 19 & 20

~~Variation $20^{\circ} E$~~

draw chain & stake,

47.00 Set a post, for quarter sec corner, & corner
in corner of north, as per instructions.

59.00 To Trail above noted NW.

87.00 They corner to sec 19, 20 & 29 & 30

Land gently rolling prairie

Soil good 2nd rate

Township 1 N Range 30 E Willamette Meridian,
chains

North, Between Sec 19 & 20

Variation 19° 13' E

Commence descending at post

40.00 Set a post for quarter sec corner, ^{draw char'd stake,} 100

^{9 raised} ~~in~~ Mound of earth as per instructions

50.00 Cross hollow & ascend - 50

70.00 To top of ascent & descend to post, + 50

80.00 Set a post on a ridge 150 ft from
a ravine. Draw char'd stake
& raised mound of earth as per
instructions. Land rolling prairie
Soil good 2nd rate

East On a random line between

Sec 19 & 20 ³/₄ Variation 19° 53' E

~~2.00 To top of slight ascent & descend~~

~~10.75 Single Indian tract, N & S.~~

~~12.50 To foot of decent & ascend~~

40.00 Set temp quarter sec post on a hill + 150

~~45.00 To top of ascent & descend + 25~~

80.32 Intersect ^{N & S line} corner to sec 16 N 7 21 & 22,

240 ft north of post ^{Cor. to 16, 17, 21 & 20}

Township 1 N. Range 30 E. Willamette Meridian
Chs.

- As 930' N. On true line between Secs. 17 & 20
 45.32 To top of ascent & descent + 25
 40.16 Set a post for quarter sec corner
 in Stone Mound as per instructions - 15 0
 67.82 To foot of descent & ascent gently
 69.57 To single Indian Trail corner 108
 78.32 To top of gentle ascent & descent
 80.32 The post corners sec 17. 18. 19 & 20

-
- West On a random line between Sec 18 & 19,
~~commenced ascending near post~~
 40.00 Set temporary quarter sec post + 100
 57.00 To top of ascent + 50
 66.50 Large Trail before noted c. N. W. Sec.
 87.10 Intersect N boundary of Township lead
 6 lks South of post, cor to sec 18 & 19

Township 1 N. Range 3 E. Willamette Meric.
chains

West. On a random line between Sec 7 & 8
Variation 21 E.

Commence descent from post

7.00 To hollow & ascend -25

14.00 To top of ascent & commence descent +30

40.00 Set temporary quarter sec post

50.50 To foot of hill & ascend

85.00 To Large Trail before noted N.S.

86.42 Intersect West boundary of
Township 38 N. South of post
corner to Sec 7 & 8.

89.42 E. On a true line between Sec 7 & 8 18.

1.42 To large Indian trail corner N.S.

35.92 Commence to ascend

46.42 Set a post for quarter section corner, raised.
^{above char & stake,}
in mound of earth as per instructions.

76.42 To top of hill & commence descent. +50

79.42 To hollow & ascend -25

86.42 The post corner to sec 7, 8, 17, 18.

Land rolling prairie Soil
good 2nd rate

Township 1 N Range 30 E Willamette Mer. chains

North, Between Secs. 7 & 8.

Variation 24 E.

Descend gradually from post

27.50 To foot of decent & ascend -100

40.00 Set a post for quarter sec corner ^{Draw chain & stake,} raised mound _{with trench & pile as per instructions,}

45.00 To top of ascent +50

^{50.00} 50.00 Commence to descend

^{70.00} 70.00 To foot of decent -100

^{71.75} 71.75 To Indian trail corner NW & SE

^{79.00} 79.00 Cross Big Hollow & ascend rocky bluff

^{80.00} 80.00 Set a post for corner to sec 5 & 6 by 8, +25

Draw chain & stake to ^{raised} mound of stone, as per instructions.

Land rolling prairie, except last chain. Soil 2nd rate

Township 1 N. Range 3 E. Tullamette Mer. chains

East, On a random line between Sec 5 & 8.

Variation 18° E

~~Ascend Bluff over bed of old road~~

12.50 To top of do & descend + 25

18.00 To foot of decent & ascend - 50

35.00 To top of ascent & descend + 150

40.00 Set temporary gr sec post. - 25

49.75 To foot of decent & ascend - 25

78.00 To top of ascent + 100

80.32 Intersect ^{N. V. D. line} corner to sec 4, 5, 8 & 9.

48 lbs north of post corner to Sec 4 & 5, 8 & 9

78939' N, On a true line between Sec 5 & 8.

2.32 commence to descend

30.57 To foot of decent & ascend - 100
drown char of state

40.16 Set a post for quarter sec corner, + 50
& raised
~~in~~ mound forth, as per instructions.

45.32 To top of ascent & descend + 100

62.32 To foot of decent & ascend - 50

67.82 To top of ascent & descend + 25

81.32 The post corner to sec 5 & 6 & 7 & 8.

Long broken in places balance rolling,
Soil 2nd & 3rd rate

Township / Range 30 E. T11 S. Meridian
chains

Test. On a random line between Sec 8 & 7
~~Variation 1800~~

~~Down bluff~~

- 2.50 To foot of do & cross bottom -25
- 16.50 To a trail corner E & N.
- 34.50 Ascend eastern slope of ridge
- 41.00 Set temporary granite sec. post +25
- 86.50 Intersect West boundary of Township level
at post corner to sec. 6 & 7.

East On a true line between Sec 6 & 7

- 46.50 Set a post for quarter sec corner, ^{drove a char of stakes,}
& raised ^{up} mound of earth, as per instructions.
- 53.00 To foot of descent -25
- 70.00 To a trail corner E & N.
- 84.50 Commence to ascend
- 86.50 The corner to sec. 5, 6, & 8.
Land gently rolling. Soil
good ^{and} Rate

List of Names,

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No 1 North of the base line of Range No 30 East of the Willamette Meridian showing the respective capacities in which they acted,

Samuel S. Campbell chairman
 Josephus Tompkins chairman
 Robert H. Crawford Axman

We hereby certify that we assisted Wm. S. Campbell deputy Surveyor, in surveying the subdivisional lines of Township No 1 North of the base line, of Range No 30 East of the Willamette Meridian, and that said Township has been.

in all respects, to the best of our
knowledge and belief well and
faithfully surveyed, and the
boundary Monuments planted
according to the instructions,
furnished by the Surveyor General

Samuel S. Campbell, Chairman
Josephus Tompkins, Chairman
Robert F. Caufield, Assessor

Subscribed and Sworn
to before me at Oregon
City this 3rd day of December
AD 1860 Jas. W. Winstone
Clerk of the Circuit
Court for the County
of Clatsop, State
of Oregon

I, Wm. Campbell, deputy surveyor
 do solemnly swear that, in pursuance
 of a contract with W. H. Chapman
 Surveyor of the public lands of the
 United States, ~~of the State of Oregon,~~
 bearing date the 19th day of September,
 1860, and in strict conformity to
 the laws of the United States, and
 the instructions furnished by the
 said Surveyor General, I have faithfully
 surveyed the subdivisions of Town-
 ship N^o 1 North of the base line of
 Range N^o 30 East of the Willamette
 Meridian, in the State of Oregon, aforesaid,
 and do further solemnly swear
 that the foregoing are the true and ori-
 ginal field notes of such survey,

Wm. Campbell,

Deputy Surveyor.

Subscribed and sworn to before
 me at Oregon City this 3rd day of Dec
 A.D. 1860

Jas. W. W. W. W.
 Clerk of the Circuit Court
 for the County of Clatsop
 State of Oregon

Surveyor General's Office
Eugene City, Jan'y 29th 1861
The foregoing field notes of
the survey of the subdivisions
of Township No. 1 North, of
Range No. 30 East of the
Willamette Meridian, execu-
ted by Wm B. Campbell, deputy
surveyor, under his contract of
the 19th day of September 1860,
having been critically exam-
ined, the necessary corrections
and explanations made, the
said field notes and the sur-
veys they describe are here-
by approved.

A. W. Chapman
Sur. Genl. of Oregon