

Plotted -

167

Ex

Field notes of the subdivision
of lines in Township No 1 north
of range 29 East of the Willamette
Meridian, in the State of
Oregon, by L. J. Carter, deputy sur.
under his contract - dated 11th
day of May 1860

Commenced May 12th 1860

Completed May 26th 1860

Index diagram

6	3	3	22	4	17	3	11	2	6	1
30	+	29	+	21	+	16	+	11	+	5
7	29	8	21	9	16	10	10	11	5	12
28	+	28	+	21	+	15	+	10	+	4
18	27	17	20	16	15	13	9	14	4	13
27	+	26	+	20	+	14	+	9	+	3
19	26	20	19	21	14	22	8	23	3	24
25	+	25	+	19	+	13	+	8	+	2
30	24	29	18	28	13	27	7	26	2	23
24	+	23	+	18	+	12	+	17	+	1
31	23	32	17	33	12	34	6	33	1	36

J. A. M. Thompson & J. P. W. Bell
do solemnly swear that I will
faithfully execute the duties of
of chairman; that I will level
the chain upon uneven ground,
and plumb the tall pins, whether
sticking or scraping the same;
that I will report the true
distance to all notable objects,
and the true lengths of all lines
that I assist in measuring, to
the best of my skill and ability

Allen M. Thompson
J. P. W. Bell

Subscribed and sworn to before me on J. 1. 1860

at 29 East. This 12th day of May 1860

L. J. Carter

Not. Pub.

I G. C. Litchfield do solemnly
swear that I will well and
truly perform the duties of
Clerk, according to instructions
given me, and to the best of my
skill and ability.

G. C. Litchfield

Subscribed and sworn to before me in

Town of E. This 12th day of May 1860

A. J. Carter

Not. Pub.

Township 1 N R 29 East

172²

North between sections 25 & 26

40.00 Set post for gr. section corner and
built mound of earth as per instructions

80.00 Set post for corner to sections 23 & 24
25 & 26 and built mound of
earth as per instructions - - 30

Land partly rolling, slope north
soil 2nd rate.

East on random line between secs. 24 & 23

Dir. 18 1/2° East -

40.00 Set limb of sec. post -

79.10 intersect at sec. corner Level

West on true line between secs. 24 & 23

39.55 Set post for gr. sec. cor. and built
mound of earth as per instructions

79.10 to section corner

Soil 2nd rate, land partly rolling

3 173

Township 1 N R 29 East

North between sections 23 & 24

40.00 Set post for q. section corner
and built-mound of earth as per
instructions

80.00 Set post for corner to sections 13, 14
23 & 24 & built-mound of earth as per
instructions

Land partly rolling
soil 2nd rate.

East on random line between secs. 13 & 24

On 19° 30 East

40.00 Set temp q. sec. post

72.44 Intersect line 25 lks North of sec cor.

N 89° 49' W on true line between secs 13 & 24

32.72 Set post for q. sec. cor. & built-
mound of earth as per instructions

79.44 to section corner

Land rolling soil 2nd rate

Township 1N R 29 East

4
174

North between sections 13 & 14

40.00 Set post for q. sec. corner and built mound of earth as per instructions

80.00 Set post for corner to sections 11, 12

13 & 14 & built mound of earth as per instructions

Land rolling, soil 2nd rate

East on random line between sections 12 & 13

Dir. 19° 45' East

40.00 Set temp. q. sec. post

79.30 Intersect-line 23-cks North of corner

N 89° 49' W on true line between sec. 12 & 13

39.65 Set post for q. section corner
And built mound of earth as per instructions

79.30 to section corner

Land rolling soil 2nd rate

175 Township 1 N R 29 East

North between sections 11 & 12

40.00 set post for gr. sec. corner and
built mound of stone as per instructions

80.00 set post for com to sections 1, 2, 11 & 12
& built mound of stone as per instructions

Low rolling soil 3^d & 2^d sets

East on random line between secs. 1 & 12

Dir. 20° 30' East

40.00 set temp gr. sec. post

78.33 Intersect line 25 lks N of corner

N. 89° 48' W on true line between secs. 1 & 12

39.17 set post for gr. sec. corner & built
mound of earth as per instructions

78.35 to section corner

Land ripen soil & rot and
stony

May 14th 1860

North between sections 1 & 2 on random
40.00 set temp. gr. sec. post-

79.40 Intersect. line 86 lks East of post

S 37' E on true line between sections 1 & 2

39.40 set post for gr. sec. corner, & built

mound of earth as per instructions

79.40 to section corner.

Land gently sloping north side
2nd rate

North on line between sections 34 & 35

40.00 set gr. section corner and built mound
of stone as per instructions & 100

80.00 set post for corner to secs. 26, 27

34 & 35 & built mound of earth as per
instructions

Land on first 1/2 mile broken and
stony, 2nd steps north, side 3' & 2' etc

7 177 Township 1 N R 29 East

East on random line between Secs. 26 & 35

Run 19° 45' East

40.00 Set temp. gr. section post

79.70 intersect line 40 lbs south of corner

S 89° 43' W on true line between Secs 26 & 35

39.85 Set post for gr. sec. corner & built-
mounds of earth as per instructions

79.70 to section corner

Land rolling soil 2^d rate

North between sections 26 & 27

40.00 Set post for gr. sec. cor. & built-
mounds of earth as per instructions

80.00 Set post for corner to sections 22, 23

26 & 27 & built-mounds of earth as
per instructions

Land gently rolling soil 2^d rate

Township 1 N. R. 29 East

178

East on random line between secs. 23 & 26

Dir. $19^{\circ}45'$ East

40.00 Set temp. gr. section post

79.10 intersect-line 44 links S of post-

$S 89^{\circ}41' W$ on true line between secs 23 & 26

39.55 Set post for gr. sec. corner & built mound of earth as per instructions

79.10 to section corner

Land selling, soil 2nd rate

North between sections 22 & 23

40.00 Set post & deposited 2 stones 4 in square

for gr. sec. corner and built mound of earth as per instructions

41.60 true course E & W

80.00 Set post for corner to sections 22. 23

14 & 13 & built mound of earth as per instructions.

Land selling Hesper with soil 2nd rate

9 179 Township 1 N R 29 East

East on random line between secs. 14 & 23

On $20^{\circ}15'$ East

40.00 Set temp. gr. section corner

79.10 intersect line 24 lks N of post

$N89^{\circ}30'W$ on true line between secs. 14 & 23

39.35 Set post for gr. sec. cor. & built mound
of earth as per instructions

79.10 to section corner

Low rolling soil in site

North between sections 14 & 15

40.00 Set post for gr. sec. cor. & built mound
of earth as per instructions

80.00 Set post for corner to sections 10, 11

14 & 15 and built mound of earth
as per instructions

Land gently rolling, general
slope north. Soil 2nd rate

Township 1 N R 29 East

10

180

East on random line between sections 11 & 14

40.00 set temp. gr. sec. post -

79.54 intersect - line 10 lks south of corner

S 89° 36' W on true line between sec. 12 & 14

39.77 set post for gr. sec. cor. & built

mound of earth as per instructions

79.54 to section corner

Land rolling soil 2nd rate

North on line between sections 10 & 11

40.00 set post for gr. section corner and

built mound of earth as per instructions

80.00 set post for corner to sections 2, 3

10 & 11, & built mound of earth as

per instructions

Land rolling, slopes north
soil 2nd rate

May 13th 1860

11 181

Township 1 N R 29 East

East on random line between Secs. 2 & 11

Bur 19° 45' East

40.00 set temp gr. sec. post

79.20 intersect at Sec. corner

West on true line between sections 2 & 11

39.60 set post for gr. sec. corner & built mound of earth as per instructions

79.20 to section corner

Land rolling soil 2nd rate

North on random line between Secs 2 & 3

40.00 set temp gr. sec. post

78.40 intersect line 108 lks east of corner

S 46° E on true line between sections 2 & 3

38.40 set post for gr. section cor. & built mound of earth as per instructions

78.40 to section corner

Land slopes gently to the north
soil 2nd rate

Township 1 N R 29 East 1892

North between sections 33 & 34
 000 ascend hill slopes South
 40.00 set post for gr. sec. cor. & built mound
 of earth as per instructions
 80.00 set post for corner to sections 27, 28, 33
 & 34 & built mound of earth as per instructions

Land broken soil 2nd & 5 rate

East on random line between secs. 27 & 34
 run. 19° East

40.00 set temp. gr. sec. corner
 80.00 intersect line & lbs S of post

† S 89° 55' W on true line between secs. 27 & 34
 40.00 set post for gr. sec. cor. & built mound
 of earth as per instructions
 80.00 to section corner

6 3/4
7 1/2

Land gently descending to the
North soil 2nd rate

Township 1 N R 29 East

North between sections 27 & 28

40.00 Set post for gr. sec. cor. & built mound
of earth as per instructions80.00 Set post for corner to sections 21, 22, 27 & 28
& built mound of stone as per instructionsLand sloping to the north soil 2nd rate

East on random line between secs 22 & 27

Run 2nd East

40.00 Set temp gr. sec. post.

80.70 intersect line 10 lks S of post

S 89° 36' W on true line between secs. 22 & 27

40.35 Set post for gr. sec. cor. & built mound
of earth as per instructions

80.70 to section corner

Land rolling, slopes north
soil 2nd rate

Township 1 N R 29 East

14
184

North between sections 21 & 22

40.00 set post for gr. sec. cor. & built mound
of earth as per instructions

46.30 true C & W

80.00 set post for cor. to Sect. 13, 16, 21 & 22

and built mound of earth as per instructions

Land rolling slopes north soil 2nd rate

East on random line between Secs 15 & 22

Run, 20° 30' East

40.00 set temp. gr. sec. post

80.82 intersect line 22 lbs S of post

89° 31' W on true line between Secs. 15 & 22

40.41 set post for gr. sec. cor. & built

mound of earth as per instructions

80.82 to section corner

Land rolling slopes north
soil 2nd rate

13- 185

Township 1 N R 29 East

North between sections 13 & 14

40.00 set post for gr. sec. cor. & built mound
of earth as per instructions

80.00 set post for corner to sections 9, 10, 13 & 14
& built mound of earth as per instructions

Land gently rolling soil 2nd rate
steeper north

East on random line between secs. 10 & 13

On 19° 30' East

40.00 set temp gr. sec. cor

80.70 intersect line 38 lbs south of sec cor.

89° 44' W on true line between secs. 10 & 13

40.33 set post for gr. sec. cor. & built mound
of earth as per instructions

80.70 to section corner

Land rolling soil good 2nd rate
May 17th 1860

Township 1 N R 29 East

15
186

North between sections 9 & 10

40.00 let post for q. sec. cor. & built mound
of earth as per instructions

80.00 let post for cor. to secs. 9, 10, 3 & 4 and
built mound of earth as per instructions

Land gently rolling soil 2^d rate

East on random line between secs 3 & 10

run 21° 30' East

40.00 let temp q. sec. post

80.80 intersect line 24 lbs S of post

88° 45' W on true line between secs 3 & 10

40.40 let post for q. sec. cor. & built
mound of earth as per instructions

80.80 to section corner

Land rolling slopes north
soil 2^d rate

1877

Township 1 N R 29 East

North on random line between secs. 3 & 4

40.00 set temp. gr. sec. post.

77.81 intersect line 3-4 this east of post

S 28° E on true line between secs. 3 & 4

37.81 set post for gr. sec. cor. & built mound
of earth as per instructions

77.81 to sustain corner

Land pretty rolling sloping north soil 2' etc

North between sections 32 & 33

0.00 ascend hill course N 85° W

2.73 trace E & W

40.00 set post for gr. sec. cor. & built + 400

mound of earth as per instructions

80.00 set post for corner to sections 28, 29

- 200

32 & 33 in mound of earth as per instructions

Land broken soil 2' & 3' etc

60
37
20

Township 1 N R 29 East

18
188

East on random line between Secs. 28 & 33
on 20° East

40.00 set temp. gr. sec. post

80.14 intersect line 14 lks N of cor. X

N 89° 54' W on true line between Secs. 28 & 33

40.07 set post for gr. sec. cor. & built mound
of earth as per instructions

80.14 to section corner

Land broken and stony
soil 2nd and 3rd rate

North between sections 28 & 29

0.00 ascend hill steps S W

40.00 set post for gr. sec. cor. & built ^{mound} + 300
of stone as per instructions

35.00 top of hill E & W + 200

80.00 set post for corner to Secs. 20, 21

28 & 29 & built mound of earth
as per instructions

Land rough soil 2nd & 3rd rate

19 189

Township 1 N R 29 E

East on random line between secs. 21 & 28
Due 23° East

40.00 set temp. g. sec. cor.

79.74 intersect line 45 lbs S of post

S 89° 41' W on true line between secs 21 & 28

39.87 set post for g. sec. cor. & built
mound of earth as per instructions

79.74 to section corner

North between sections 20 & 21

40.00 set post for g. sec. cor. & built mound
of earth as per instructions

60.00 true E & W

80.00 set post for corner to secs. 16, 17

20 & 21 & built mound of stone
as per instructions

Land taken from NW
sec 2nd lot and stop

Township 1 N R 29 E

20

190

East on random line between sections ^{16 & 21}

~~Sec. 22 & 23 E~~

40.00 Set ~~boundary~~ gr. sec. cor.

80.10 intersected line 62 lbs S of corner

S 89° 33' W on true line between Secs. 16 & 21

40.03 Set post for gr. sec. cor. & built

mound of earth as per instructions

80.10 to section corner

Land selling. Slopes S W said 2nd rate
North between sections 16 & 17 Township 21 S E

40.00 Set post for gr. sec. corner & built

mound of earth as per instructions

80.00 Set post for corner to Secs. 8 & 9

16 & 17 & built mound of earth

as per instructions

Land gently descending to
the North side road & rate

May 18th 1860

21 1911

Township 1 N R 29 E

East on random line between sec. 9 & 16

Var. 13° East

40.00 set post for gr. sec. cor. & built mound

79.34 intermediate in 90° the S of cor.

S 89° 21' W on true line between sec. 9 & 16

39.77 set gr. sec. post & built mound

of south as per instructions

79.54 to section corner

Land rough & stony soil Sect

North between sections 8 & 9

40.00 set post for gr. sec. cor. & built

mound of south as per instructions

80.00 set post for cor. to sec. 4, 5, 8 & 9

& built mound of south

as per instructions

Land pretty rolling soil 2nd sect

Township 1 N R 29 E

22

192

East on random line between secs 4 & 9

Dir. $20^{\circ}15'$ East

40.00 set temp. q. sec. cor.

80.00 intersect at corner

West on true line between secs. 4 & 9

40.00 set post for q. sec. cor. & built

mound of earth as per instructions

80.00 to section corner

And broken line $2^{\circ}30'$ rate

North on random line between secs. 4 & 5

40.00 set temp. q. sec. corner

77.40 intersect town line 93 lbs east

of post -

S 40° E on true line between sec. 4 & 5 -

37.40 set q. sec. cor. & built mound

earth as per instructions

77.40 intersect line at corner

Land partly descending to
the north said post 12° rate

23 1913 of Township 1 N R 29 E

North between sections 31 & 32

40.00 set q. sec. cor. & built mound
of stone as per instructions
and descend hill E & W

80.00 set post for cor. to secs. 29 & 30
31 & 32 & built mound of earth as
per instructions - 300

Land rough, size 0th rate

East on sundom line bet. secs. 29 & 32

Bur. 19° 30' East

40.00 set temp q. sec. cor.

80.94 intersect at sec. cor.

~~Set~~ on line between secs 29 & 32

40.47 set post for q. sec. cor. & built
mound of earth as per instructions

54.00 trail nearly E & W

59.94 Creek 25th mile corner N 80° W

80.94 to section corner

Land rolling slopes S. W.

Size 1st & 2nd rate

50
100
150

Township 1 N B 29 East

24

194

West on random line between secs. 30 & 31

40.00 set temp. gr. sec. cor.

87.14 intersected line 8 lks N of sec. cor.

N 89° 37' E on line between secs 30 & 31

47.14 set post for gr. sec. cor. built

mound of stone as per instructions

87.14 to section corner

Land broken slopes N side 2nd rate

North between sections 29 & 30

17.30 creek 25 lks wide corner N 60° W

22.30 line corner E & W & ascen

40.00 set post for gr. sec. cor. & built mound
of stone (on hill side) as per
instructions. + 200

60.00 top of hill E & W + 300

80.00 set post for cor. to secs. 19, 20, 29 & 30

& built mound as per instructions

Land rough, side 1st & 2nd rate

25 195 Township 1 N R 29 E

East on random line between Secs. 20 & 29

Dir. 20° East

40.00 set temp. gr. sec. cor.

80.30 intersect - line 12 lks N of sec. cor.

N $89^{\circ} 35'$ W on true line between Secs 20 & 29

40.23 set post for gr. sec. cor. & built

mound of earth as per instructions

80.30 to section corner

Land rolling slopes to the NW

Soil 2nd rate

West on random line between Secs. 19 & 30

40.00 set temp. gr. sec. cor.

86.68 intersect - 86 lks N of sec. cor.

N $89^{\circ} 25'$ E on true line between Secs. 19 & 30

27.30 true N & S

46.68 set post for gr. sec. cor. & built

mound of earth as per instructions

86.68 to section corner

Land rough slopes S. Soil 2nd rate

Township 1N R29E

26

196

North between sections 19 & 20

330 line E & W

4000 set post for q. sec. cor. & built-

mound of earth as per instructions

8000 set post for corner to sections 17 & 18

19 & 20 & built-mound of earth as

per instructions

Land selling soil 2^d rate

East on random line between secs 17 & 20

Dir. 20° 30' East

40.00 set temp q. sec. post

80.38 intersect 20 lks N of sec. cor.

S 89° 31' W on true line between secs 17 & 20

40.29 set post for q. sec. cor. & built-

mound of earth as per instructions

80.38 to section corner

Land partly selling slips of
soil good 2^d rate

27 197 Township 1N R 29E

West on random line between Secs. 18 & 19

40.00 Set temp. gr. sec. post

87.62 Interest line 27 lbs N of sec cor.

N 89° 44' E on true line between Secs. 18 & 19

47.62 Set post for gr. sec. cor. & built mound
of earth as per instructions

39.11 true cons N & S

87.62 to section corner

Land partly rolling soil 2nd rate

North between sections 17 & 18

40.00 Set post for gr. sec. cor. & built
mound of earth as per instructions

80.00 Set post for corner to sections

7, 8, 17 & 18 and built mound

of earth as per instructions

Land partly rolling. Slopes North
soil 2nd rate

Township 18 R 29 E

28
198

East on sundown line between secs. 8 & 17

Dir. $18^{\circ} 15'$ East

40.00 set temp. q. sec. post

80.28 intersect line 10 lbs south of sec. cor.

$S 89^{\circ} 36'$ on true line between secs. 8 & 17

40.13 set post for q. sec. cor. & built mound
of earth as per instructions

80.26 to section corner

Land partly rolling good route

West on sundown line between secs. 7 & 18

40.00 set temp. q. sec. cor. & built

88.60 intersect line 67 lbs N of corner

$N 89^{\circ} 81'$ on true line between secs 7 & 18

48.60 set post for q. sec. cor. & built
mound of earth as per instructions

88.60 to section corner

Land partly rolling good route

199 Township 1 N R 29 E

North between sections 7 & 8

40.00 set post for gr. sec. cor. & built

mound of earth as per instructions

80.00 set post for corner to sections

3-6, 7 & 8 & built mound of earth

as per instructions.

Land selling, steps N, 2nd date

East on random line between secs 3 & 8

on 21° East

40.00 set temp gr. sec post

79.70 returned - line 18 ths N of sec cor.

N 89° 52' W on true line between secs. 3 & 8

40.00 set post for gr. sec. cor. & built

mound earth as per instructions

79.70 to section corner

Land selling, post 2nd date

Township 1 N R 29 E

30
200

West on random line between secs 6 & 7

40.00 set temp gr. sec. post.

88.06 intersect-line 66 lbs N of sec. cor.

N 89° 32' E on true line between sec. 6 & 7

48.06 set post for gr. sec. cor. & built mound of earth as per instructions

3866 true course A & S

88.06 to section corner

Land rolling soil 2nd & 3rd rate

North on random line between secs. 3 & 6

40.00 set temp gr. sec. post.

73.90 intersect-line 133 lbs east of cor.

S 37° E on true line between secs. 3 & 6

35.90 set post for gr. sec. cor. & built

mound of stone & earth, with posts as per instructions.

73.90 to section corner

Land rolling, 2nd rate

May 29th 1860

General description

The quality of the land in this township is 2^d rate, except along the Bottom Fording on Butte creek, a small stream entering the township in sec 32, and leaving it in the west boundary in sec 30. There is no timber except along this stream, consisting, ^{of} cotton wood, birch, willow and alder. It is well adapted to grazing purposes, the upland being covered with grass.

List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines & corners described in the foregoing field notes of township 1 N of R 29 E of the Willamette meridian, showing the respective capacities in which they acted

A. M. Thompson	Chairman
P. W. Bell	do
J. C. Atchafule	Assessor

We hereby certify that we assisted J. F. Carter, deputy surveyor, in surveying the subdivisional lines of township No 1 N of R 29 East of the Willamette meridian, and that said Township has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Gen. General.

Allen M. Thompson

A. W. Bell

J. C. Litchfield

Subscribed and sworn to before me at

Oregon city this 12th day of June 1860

L. F. Carter

Not. Pub.

J. J. Hartie, deputy surveyor, do solemnly swear that in pursuance of a contract with W. W. Chapman Surveyor of the public lands of the United States in the state of Oregon, bearing date the 11th day of May 1860, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivisional lines of Township 1 North of Range 29 East of the Willamette meridian, in the State aforesaid, and do further swear that the foregoing are the true and original field notes of such survey.

J. J. Hartie dep. sur.

Subscribed and sworn to before me at Eugene City this 26th day of June 1860

W. W. Chapman
 Secy Genl
 Oregon

Surveyor General's Office
Eugene City, July 13th 1860.

The foregoing field notes of the
Survey of the Subdivisions
of Township No 1 North of
Range No. 29 East of the
Willamette Meridian, State
of Oregon, executed by S. G.
Cartee, under his contract
of the 11th day of May 1860.
having been critically examined
the necessary corrections and
explanations made the said
field notes and the surveys
they describe are hereby ap-
proved

W. W. Chapman
Sur. Gen. of Oregon