

Washington transcript made - ²⁰⁶⁸⁸ D. H. Murphy

Field notes of the resurvey of the
exterior line of the East boundary
of Township 1 N of Range 28 East

Commenced May 23^d 1860
Completed do do

Index diagram

| | |
|----|---|
| 1 | 3 |
| 12 | 3 |
| 13 | 2 |
| 24 | 2 |
| 25 | 1 |
| 36 | 1 |

Comp'd

©

12 207

East boundary of T1 N R 28 E

Having detected an error of five chs. in the length of the East boundary of sec. 36 I commence at the established cor. on the base line an run as follows.

North on line between sections 31 & 36

0.00 descend hill E & W - 200

12.00 ascend hill slopes S

40.00 set post for q. sec. cor. and built mound of earth as per instructions.

65.00 top of ridge c. N.W. & S.E.

80.00 set post for corner to sections 23, 30, 31 & 36 -100

built mound of earth as per instructions hill slopes N.E.

Land rough and string 2nd set 5

North on the east boundary of section 23

Run 20.00 E

0.00 descend hill faces N.E.

40.00 set post for q. sec. cor. and built mound of earth as per instructions, ^{hill} slopes N - 300

32.30 trail course E & W

60.50 creek 20 chs and course N 70° W

East boundary of T1N22E

2
208

62.23 - Hill E & W

62.50 Ascend hill E & W

80.00 set post for corner to sections 19, 24

23 & 20. Built mound of earth & stone
as per instructions + 200

Land taken 2nd 1/2 on site

North on east boundary of sec 24

Over 19° 30' East

50 Ascend hill slopes South

40.00 set post for q. sec. cor. & built mound
of stone as per instructions on top of hill + 200

80.00 set post for corner to sections 13, 18, 19 & 24

and built mound of earth as per instructions

Just half mile. partly rolling 2nd 1/2 on site

North on east boundary of sec 13

Over 19° 15' East

40.00 set post for q. sec. cor. built mound
of earth as per instructions

80.00 set post for corner to secs. 7, 12, 13 & 18

built mound of earth as per instructions

Land partly slopes N. side 2nd 1/2 on site

8
208 A

North on east boundary of sec 12

Cor. $19^{\circ}45'$ East

40.00 set post for q. sec. cor. & built mound of
earth as per instructions

80.00 set post for corner to sec. 6, 7, 1 & 12

built mound of earth as per instructions

Trust partly selling, deposes N. 2° rate

North on east boundary of sec. 1

Cor. $20^{\circ}45'$ East

40.00 set post for q. sec. cor. built mound of
earth as per instructions

74.99 to the corner established for the N.E.
corner of T. 1 N R. 28 E.

This error of 5 chains went through the
township, and I destroyed the old
corners and made new ones, 5 chs
north of the place where previous set
May 23 1860

List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of the resurvey of the east boundary of Township 1 N of range 28 east of the Willamette Meridian showing the respective capacities in which they acted.

- A. M. Thompson Chairman
- P. W. Bell do
- J. C. Litchfield Assessor

We hereby certify that we assisted J. F. Carter
deputy surveyor, in surveying, or correcting,
the section line of the eastern boundary
of Township 1 North of Range 28 east of the
Willamette Meridian, and that said
line has been in all respects to the
best of our knowledge and belief, well &
faithfully surveyed, and the boundary
monuments planted according to the
instructions furnished by the
Surveyor General.

Allen M. Thompson

A. W. Bell

G. C. Litchfield

Subscribed and sworn to before me at
Oregon city. This 10th day of June 1860

J. F. Carter

Not. Pub.

J. J. Hattie, deputy Surveyor, do solemnly swear that in prosecuting my contract with W. W. Chapman Surveyor of the public lands of the United States in the State of Oregon, bearing date the 11th day of May 1860, I found an error of five chains (about) in the east boundary of Sec. 36 T 1 N R 28 E, and in strict conformity to the laws of the United States and the instructions furnished by the Chief Surveyor Genl. I have faithfully corrected a resurvey the east boundary of said township, and do further swear that the foregoing are the true and original field notes of such survey

J. J. Hattie, Dep. Sur.

Subscribed and sworn to before me at Eugene City this 26th day of June 1860

W. W. Chapman
Secy. Genl.
Oregon

Surveyor General's Office
Sedgwick City July 13th 1860.

The foregoing field notes
of the correction of the East-
ern boundary of Township
1 North of Range 28 East
of the Willamette Merid-
ian, Oregon, executed by
S. G. Carter, in the prose-
cution of his contract of the
11th day of May 1860; hav-
ing been critically exam-
ined, the necessary correc-
tions and explanations
made, the said field notes
and the surveys they des-
cribe are hereby approved.

H. W. Chapman
Sur. Genl of Oregon.