

Washington transcript, made L.A.M.

Field Notes of the Exterior  
Lines of Townships No. 1 & 2 N.  
Range No. 31. East of the Will-  
amette Meridian, Oregon - ex-  
ecuted by Josiah A. Burnett  
deputy Surveyor, under his con-  
tract No. 92, dated September  
12<sup>th</sup> 1860.

Commenced October 16<sup>th</sup> 1860

Completed Nov. 20<sup>th</sup> 1860.

Rec<sup>d</sup> Nov-19<sup>th</sup> 1860

Copia

+







We Walter Poulding, Thomas H

Bell, Davis Divers & Patrick Callihuan, do solemnly swear that we will faithfully execute the duties of chain carriers, that we will level the chain upon uneven ground and plumb the tally pins, whether by sticking or dropping the same, that we will report the true distance to all notable objects, and the true length, of all lines that we assist in measuring to the best of our skill and ability.

Walter Poulding chainman  
Thomas H Bell chainman

Daves, Divers chainman

Patrick <sup>pin</sup> Callihan chainman  
mark

Subscribed & sworn to before me by  
the above named persons this  
22<sup>d</sup> day of September 1860  
J. B. Hodgdon J. P.  
of Masco Co Oregon



We Wm Smith & Thomas White do  
 solemnly swear that we will  
 well and truly perform the duties  
 of Axemen according to instri-  
 ctions given, ~~us~~ and to the  
 best of ~~our~~ skill and ability  
 William L. Smith Axeman  
 Thomas White Axeman  
 Subscribed & sworn to before me  
 by the above named persons  
 this 22<sup>d</sup> day of September 1860  
 J. B. Hodgdon, J. P.,  
 of the Co of Marsoo Arizon



Between Ranges 31 & 32 E T. N

North on East boundary of Sec 1  
Variation  $19^{\circ}45' E$

40.00 Set a post for  $\frac{1}{4}$  sec. cor. drove  
chance stake & raised mound  
with trench as per instructions

80.00 A point for corner to Townships  
142 North. Ranges 31 & 32 East

Set post and drove chance  
stake, <sup>Raised</sup> mound & trench as per  
instructions

Land for the last 6 miles has  
been Rolling grass hills light  
2<sup>d</sup> rate soil

Oct. 17<sup>th</sup> 1860

Beginning at the established corner  
to Townships 142 North Ranges  
31 & 32 East. at a post in mound.

West on random line along  
the North boundary of Sec's <sup>1, 2</sup> ~~3, 4, 5, 6~~  
~~3, 4, 5, 6~~

Variation  $21^{\circ}15' E$

I set temporary half mile and



South (9)  
North  
~~South~~ boundary T2 N R31 E

249

mile posts at every 40.00 chas 80.00 chas  
and at 6 miles 9 chains and 25 lks  
to a point 3 chains and 84 lks. South  
of the corner to Townships 14 2 Nor  
-th Ranges 30 + 31 East.

Therefore the correction will be 64.00  
links South per mile.

I find the corner post standing  
with mound & trench.

From the corner to Townships 14 2  
North Ranges 30 + 31 East. I Run  
589.33' E on true line along the  
~~North~~ boundary of Sec. 6

49.25  
49.35 Set post for 1/4 Sec. Cor, drove chain  
-rod stake & raised mound with  
trench as per instructions

64.00 Top of Ridge bears N 4 S

89.35 Set post for corner to Sec's. 5, 6, 31

89.25  
and 32, drove chain & stake & raised mound with  
-ch as per instructions. Land 2d rate Soil



South  
North

South boundary Sec 31 E

- 589<sup>33</sup>' E on a true line along  
the ~~South~~ <sup>North</sup> boundary of Sec. ~~32~~  
40.00 Set post for 1/4 Sec. Cor. drove charred  
stake & raised mound with trench  
as per instructions
- 80.00 Set post for corner to Secs. 4.5.  
32 & 33. drove charred stake and  
raised mound with trench  
as per instructions
- Land selling 2<sup>d</sup> rate soil

- 589<sup>33</sup>' E on a true line along  
the ~~South~~ <sup>North</sup> boundary of Sec. ~~34~~  
4.00 to head of a dry Run course N.E.  
40.00 Set a post for 1/4 Sec. cor. drove charred  
stake and raised mound with  
trench as per instructions
- 75.30 Head of a dry Run course  
N.E.
- 80.00 Set post for corner to Secs. 3.4.  
33 & 34. drove charred stake and  
raised mound with trench



251

South (11)  
North  
~~South~~ boundary T2N R31E

as per instructions.  
Land Broken hills poor stony  
soil.

S 89° 33' E. on a true line along the  
North  
~~South~~ boundary of Sec. ~~2~~ 3.  
Variation 20.00° E

40.00 Set post for  $\frac{1}{4}$  Sec. cor. drove char-  
-ed stake and raised mound with  
trunk as per instructions

80.00 Set a post for corner to Sec's. 2,  
3, 34 and 35. Drove charred stake and  
raised mound with trunk as  
per instructions.

Land Grass hills. 3<sup>d</sup> rate sandy soil

S 89° 33' E on true line along the ~~South~~ North  
boundary of Sec. ~~2~~ 2.  
Variation 20.00° E

33.00 To a dry Ravine course N.E.

40.00 Set a post for  $\frac{1}{4}$  Sec. cor. drove charred  
stake and raised mound with trunk  
as per instructions

80.00 Set a post for  $\frac{1}{4}$  corner to Sec's



## South boundary T2 N R31 E

1. 2, 35 and 36 drove chain stake  
and raised mound with truck  
as per instructions.

Land rolling grass hills 2<sup>d</sup> rate soil

S89°33' E on a true line along the  
North ~~South~~ boundary of Sec. #1. Var. 19°30' E

13,00 To the Bed of a Dry Ravine course  
North. There is a beautiful  
spring in this ravine, about  
60,000 chs. south of this point,  
and also one about 40,00 chs  
North, with good tillable land  
surrounding.

40,00 Set a Post for 1/4 Sec. cor drive  
chain stake and raised mound  
with truck as per instructions

80,00 The corner to Township 10 and 2 North  
Range 31 & 32 East.  
Land Rolling 2<sup>d</sup> rate sandy soil  
covered with rich grass-

Oct 18<sup>th</sup> 1860.



South boundary L2N R31E

General Description

This Township contains a large amount of 1<sup>st</sup> and 2<sup>d</sup> rate land and is well adapted to grazing purposes, as it is covered with rich grass.

The Township will admit of settlements and should therefore be subdivided

---



A list of the names of the individuals employed to assist in running measuring or marking the lines and corners described in the foregoing field notes of Townships T<sub>10</sub>N and 2 North of the Base line of Range T<sub>31</sub>E east of the Willamette meridian showing the respective capacities in which they acted,

Patrick Callahan, Chairman

Walter Paulding " "

Thomas Whit's Eyeman

M. C. C. Murphy, Compassman



We hereby certify that we assisted Josiah, A. Burnett <sup>267</sup>  
deputy surveyor in surveying the exterior lines  
of Township No 142 North of the base line of  
Range No 31 East of the Willamette meridian

and the survey of the Base line along the  
south boundary of Township No 1 North of  
Range No 31 East of the Willamette meridian  
and that said exterior and survey of the base  
line has been in all respects to the best of our  
knowledge and belief, well and faithfully sur-  
veyed and the boundary monuments planted  
according to the instructions furnished by  
the surveyor General,

M. O. Murphy

Patrick <sup>his</sup> Ballahan

Walter Pudding

Thomas White Osaman

Subscribed & sworn to by the above persons before  
me a Justice of the Peace, of the County of  
Wasco, State of Oregon, this 30 day of October  
1860—

G. B. Hodgdon  
Justice of the Peace



I Josiah, A. Burnett deputy  
 Surveyor do solemnly swear  
 that in pursuance of a contract  
 with W. W. Chapman Surveyor  
 of the public lands of the  
 United States, in the State of Oregon  
 bearing date the 12<sup>th</sup> day of Septem-  
 -ber 1860, and in strict conformity  
 to the laws of the United States,  
 and the instructions furnished  
 by the said Surveyor General, I have fai-  
 -thfully surveyed the exterior boundaries  
 of Townships No 1 and 2 North, of the base  
 line of Range No 31 East of the Willamette  
 Meridian in the State aforesaid and do further, sol-  
 -emly swear that the foregoing are the true and  
 original field notes of such survey

J. A. Burnett

Asst. Surveyor

Subscribed and sworn to before  
 me at Eugene City Nov 21. 1860

W. W. Chapman Surveyor



270

Surveyor General's Office

Eugene City, Dec 5<sup>th</sup> 1860.

The foregoing field notes of the survey of the remeasurement of the Base Line through Range No 31 East and the Exterior Lines of Townships No. 1 & 2 North of Range No. 31 East of the Willamette Meridian, Oregon, executed by J. A. Barnett under his contract of the 12<sup>th</sup> day of September 1860. having been critically examined the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

A. W. Chapman  
Sur. Gen. of Oregon.