

Washington Transcript made 287

A. H. Murphy

(2) Copy

Field notes of the Subdivisions of Townships No 1 North of the base line of Range 31 East of the Willamette Meridian, in the State of Oregon, by Josiah A. Burnett deputy Surveyor, under his contract No 92 bearing date the 12<sup>th</sup> day of September 1860.

Commenced October 17<sup>th</sup> 1860.

Completed October 24<sup>th</sup> 1860

Index Diagram

|    |    |    |    |    |    |    |    |    |   |    |
|----|----|----|----|----|----|----|----|----|---|----|
| 6  | 37 | 5  | 28 | 4  | 21 | 3  | 14 | 2  | 8 | 1  |
| 37 |    | 36 |    | 27 |    | 20 |    | 14 |   | 7  |
| 7  | 35 | 8  | 26 | 9  | 20 | 10 | 13 | 11 | 6 | 12 |
| 35 |    | 34 |    | 26 |    | 19 |    | 12 |   | 5  |
| 18 | 34 | 17 | 25 | 16 | 19 | 15 | 12 | 14 | 5 | 13 |
| 33 |    | 32 |    | 25 |    | 18 |    | 11 |   | 4  |
| 19 | 32 | 20 | 24 | 21 | 17 | 22 | 11 | 23 | 3 | 24 |
| 31 |    | 31 |    | 23 |    | 17 |    | 10 |   | 3  |
| 34 | 30 | 29 | 23 | 28 | 16 | 27 | 9  | 26 | 2 | 25 |
| 29 |    | 29 |    | 22 |    | 16 |    | 9  |   | 2  |
| 31 | 28 | 32 | 22 | 33 | 15 | 34 | 8  | 35 | 1 | 36 |



## T. N. R. 31 E

Field notes of the subdivision lines  
in Township 1 North R. 31 E. Mecumite  
Meridian

Subdivisions commenced October 17<sup>th</sup>  
1860.

Under the direction of the Surveyor  
The following is a list of the work done  
4 days

North between Sec's 35 & 36

<sup>40.00</sup>  
40.00 Set a post for  $\frac{1}{4}$  Sec. cor. drove charred  
stake and raised mound with trench  
as per instructions.

<sup>50.00</sup>  
50.00 To a Dry Ravine course N E

<sup>80.00</sup>  
80.00 Set post for corner to Sec's. 25. 26. 35 &  
36. drove charred stake and raised  
mound with trench as per instructions  
Land rolling grass hills 2<sup>d</sup> rate soil

East on Random line between Sec's  
25 & 36.

<sup>40.00</sup>  
40.00 Set Temporary  $\frac{1}{4}$  sec. cor  
Variation 2000' E.



## I. N. R. 31 E

79.68 Intersected East boundary of Township. 63 links South of corner to Sec's. 25 and 36, <sup>30 & 31</sup> from which corner I Run.

589.33 W on true line between Sec's 25 & 36

39.84 Set a post for 1/4 Sec. cor. drove charred stake and raised mound as per instructions

79.68 The corner to Sec's. 25. 26. 35 & 36  
Land level 2<sup>d</sup> rate soil

North between Sec's 25 and 26

40.00 Set a post for 1/4 Sec. cor. drove charred stake and raised mound as per instructions

80.00 Set a post for corner to Sec's 23. 24. 25 and 26 drove charred stake. and raised mound as per instructions

Land rolling grass hills 2<sup>d</sup> rate soil.



T. N. B. 16

Easton Random line between  
Sec's 24 and 25

Variation 20°30'E

40.00 Set Temporary 1/4 Sec. cor.  
79.50 Intersected East boundary of Town  
ship 33 1/2 miles South of the corner  
to Sec's 24 & 25, from which corner  
I Run

S 89°46' W on a true line between  
Sec's 24 & 25.

39.75 Set a post for 1/4 Sec. cor. drove  
charred stake and raised mound  
with truck as per instructions

79.50 The corner to Sec's 23, 24, 25 and 26  
Land level 2", date soil

North between Sec's 23 and 24

40.00 Set a post for 1/4 Sec. cor. drove  
charred stake and raised mound  
with truck as per instructions

70.00 To bed of Dry Ravine course N 30° E

80.00 Set a post for corner to Sec's 13, 14,  
23 and 24, drove charred stake



4 194

LIN R31E

and raised mound with trench  
after instructions  
Land rolling grass hills & rate  
soil.

Cast on a Random line between  
Sec's 13 & 24,

Variation 18'00"E

40.00 Set a Temporary 1/4 sec, cor.  
79.65 Intersected East boundary of Town-  
=ship, at the post corner of  
Sec's 13 & 14, from which I Run  
West on true line between Sec's 13 &  
24.

39.82 Set post for 1/4 sec, cor. drove  
churned stake and raised  
mound, with trench after  
instructions.

79.65 The corner to Sec's, 13, 14, 23 and  
24.

Land rolling grass hills & rate  
soil.



S, N R 31 E

North between Sec's. 13 & 14

<sup>40.00</sup> 40.00 Set a post for 1/4 Sec. cor. drove charred stake and raised mound with trench as per instructions.

<sup>80.00</sup> 80.00 Set a post for corner to Sec's. 11, 12, 13 and 14. drove charred stake and raised mound with trench as per instructions.

Land rolling grass hills 2% rate soil.

East on Random line between Sec's 12 and 13.

Variation 2000' E

<sup>40.00</sup> 40.00 Set a post for 1/4 Sec. cor.

<sup>79.84</sup> 79.84 Intersect a line East boundary of Township 20 N, South of Post corner to Sec's 12 and 13. from which corner I Run.

S 89.51' W on true line between Sec's 12 & 13.

<sup>39.92</sup> 39.92 Set post for 1/4 Sec. cor. drove charred stake and raised mound with



6 296

S. N. R. 31 E

trench as per instructions  
7984 The corner to Sec's 11, 12, 13 and 14  
Land rolling grass hills  $2\frac{1}{2}$  rate  
soil

---

- North between Sec's 11 and 12  
4000 Set a Post for  $\frac{1}{4}$  sec, cor, drove  
sharred stake and raised mound  
with trench as per instructions  
6500 Entered small Valley bearing N. E. &  
S. W.  
7800 Leave Valley bearing N. E. & S. W.  
8000 Set a post for corner to Sec's 1, 2,  
11 and 12. raised stone mound  
as per instructions
- 

~~East on Random line between  
Sec's 1 & 12~~

~~Variation 2000 E~~

~~700 Entered Valley bearing N. & S. W.  
from this point a beautiful spring  
of fresh water bears N. 40 E about  
2000 feet dist.~~



297

T. N. R. 31 E

East on Random line between  
Sec's 1 & 12

Var 20.00' E

<sup>40.00</sup>  
40.00 Set Temporary 1/4 Sec cor  
<sup>79.18</sup>  
79.18 Intersected East boundary of  
Township 30 Ws South of the cor-  
ner to Sec's 1 and 12 from which  
corner I Run

S 89 1/2 W on true line between  
Sec's 1 & 12.

<sup>39.59</sup>  
~~39.59~~ Set post for 1/4 Sec cor. Above  
charrid stake and raised moun-  
nd with much aspen instru-  
-tion

<sup>68.00</sup>  
68.00 Enter small Valley bearing N 45 W  
from which point a beautiful  
fresh water Spring issues North  
about 2000 chs dist.

<sup>78.00</sup>  
78.00 Leave Valley bearing N 45 W

79.18 The corner to Sec's 1, 2, 11 and 12

<sup>79.18</sup>  
79.18 Land Valley 1<sup>st</sup> rate soil East of  
Valley gently rolling 2<sup>d</sup> rate soil  
Oct 17<sup>th</sup> 1860,



8 298

T. N. R. 37 E

North on Random line between  
Sec's 1 and 2

40.00 Set a Temporary  $\frac{1}{4}$  Sec. cor.

80.90 Intersect North boundary of Township  
70 miles East of the corner to Sec's 1 and 2  
from which corner I Run

500.30' E on true line between Sec's 1 & 2

40.90 Set apart for  $\frac{1}{4}$  Sec. cor. drove charred  
stake and raised mound with trench  
as per instructions.

44.90 To a Dry Ravine corner East

80.90 The corner to Sec's 1, 2, 11 and 12,  
Land rolling grass hills light 2<sup>d</sup> rate  
soil.

North between Sec's 34 and 35.

32.00 To a Dry Ravine corner N. E.

40.00 Set post for  $\frac{1}{4}$  Sec. cor. drove charred  
stake and raised mound with trench  
as per instructions.

80.00 Set post for corner to Sec's 26, 27, 34  
and 35 drove charred stake and raised  
mound with trench as per instructions.



T. N. R. 31 E

Land rolling grass hills, light  
2<sup>d</sup> rate soil.

East on Random line between Sec's.  
26 & 35

Variation 1845' E

40.00  
40.00 Set Temporary 1/4 Sec. cor.  
80.09 Intersect N & S line 50 Yds South of  
the corner to Sec's. 25, 26, 35 and 36  
from which corner Run  
S 89° 39' W on true line between Sec's. 26  
and 35.

40.04  
40.04 Set Post for 1/4 Sec. cor. drove chain  
stake and raised mound with truck  
as per instructions.

80.09  
80.09 The corner to Sec's. 36, 27, 34 and 35.  
Land rolling grass hills, light 2<sup>d</sup>  
rate soil

40.00  
40.00 North between Sec's 26 and 27  
Set Post for 1/4 Sec. cor. drove chain  
stake and raised mound with truck  
as per instructions



## T. N. R. 31 E

46.00 To a Dry ravine course N E  
 80.00 Set Post for corner to Sec's. 22, 23,  
 26 and 27 drove charred stake and  
 raised mound with trench as  
 per instruction  
 Land rolling 2<sup>d</sup> rate soil

East on Random line between Sec's  
 23 and 26

Variation 20.00' E

40.00 Set Temporary 1/4 Sec. cor.  
 79.85 Intersected N & S line 23 lks South  
 of the ~~Post~~ corner to Sec's. 23, 24, 25  
 and 26, from which corner I Run  
 589' 30" W on true line between Sec's  
 23 and 26.  
 39.92 Set a post for corner to 1/4 Sec drove  
 charred stake and raised mound  
 with trench as per instructions  
 40.50 To a Dry ravine. Course N. E.  
 79.85 The cor to Sec's. 22, 23, 26 and 27  
 Land rolling grass hills 2<sup>d</sup> rate soil



S. N. B. 318

North bottom Sec's 22 and 23.

<sup>40.00</sup>  
40.00 Set post for 1/4 Sec. cor. drove ch  
= wood stake and raised mound  
with trench as per instructions

<sup>80.00</sup>  
80.00 Set Post for corner to Sec's. 14, 15,  
22 and 23, drove chard stake and  
raised mound with trench as per  
instructions,

Land rolling grass hills 2<sup>d</sup> rate  
soil.

East on Random line between Sec's  
14 and 23

Variation 2,000 E

<sup>40.00</sup>  
40.00 Set Temporary 1/4 Sec. Cor.  
<sup>79.75</sup>  
79.75 Intersected N and S line 12 Mts South  
of the Post corner to Sec's. 13, 14,  
23 and 24. From which corner  
down

89.53' W on the line between Sec's  
14 and 23.

<sup>39.87</sup>  
39.87 Set Post for 1/4 Sec. cor. drove chard  
stake and raised mound with trench



12

302

T. N. R31E

as per instructions

79.75 The corner to Sec's. 14, 15 22 and  
23.

Land rolling grass hills light 2<sup>d</sup>  
rate soil

North between Sec's 14 and 15  
40.00 Set a Post for 1/4 Sec. cor. above  
chain stake and raise monument  
with trench as per instructions

80.00 Set Post for corner to Sec's. 10, 11, 14,  
and 15 - above chain stake and  
raise monument with trench as  
per instructions

Land rolling grass hills 2<sup>d</sup> rate  
soil

East on Random line between Sec's  
11 and 14

Per 20.00 E

40.00 Set Line for any 1/4 Sec. cor.

79.92 Intersect N & S line 7/16<sup>s</sup> North of  
the Post cor to Sec's. 11, 12, 13 and 14



T. N. R 31 E

From which corner I Run  
N 89° 37' W. on true line bottom  
Sec's. 11 and 14.

- 39.96
- 39.96 Set Post for 1/4 sec, cor, drove  
charred stake and raised mound  
with truck as per instructions
- 44.40
- 44.40 To a Dry Ravine course North
- 79.92
- 79.92 In corner to Sec's 10, 11, 14 and 15  
Land, rolling grass hills 2<sup>nd</sup> rate  
soil.

- 32.00
- 32.00 North bottom Sec's 10 and 11.
- 40.00
- 40.00 To a Dry Ravine course, N E
- 41.00
- 41.00 Set Post for 1/4 Sec, cor, drove Charred  
stake and raised mound with truck  
as per instructions
- 50.00
- 50.00 Foot of hill bearing N E. and S W
- 80.00
- 80.00 Summit of hill bearing N E & S W
- 80.00
- 80.00 Set post. for corner to Secs. 2, 3, 10 and  
11. Drove charred stake and raised mound  
with truck as per instructions  
Land, rolling grass hills 2<sup>nd</sup> and 3<sup>rd</sup> rate  
soil



4 304

T. N. R. 318

East on Random line between  
Secs. 2 and 11.

Variation 19,00' E

4,000 Set Temporary 1/4 Sec. cor.  
80,00 Intersected N + S line 16 Mts North  
of the corner to Sec's. 1. 2. 11 and 12  
from which corner I run  
N 89° 33' W. On true line between Sec's  
2 and 11.

8,50 Top of Ridge bearing N. 48  
40,00 Set a Post for 1/4 Sec. cor. above  
churned Stake and revised monument  
with trench as per instructions  
8000 The corner to Sec's. 2. 3. 10 and 11  
Land rolling 3<sup>d</sup> rate soil.

North on Random line between Sec's  
2 and 3:

~~4,000~~ ~~Set~~ ~~Temporary~~ ~~1/4~~ ~~Sec.~~ ~~cor.~~  
40,00 Set Temporary 1/4 Sec. cor.  
81,84 Intersected North boundary of Town  
= ship 48 Mts East of the corner to Sec's  
2 and 3. from which corner I Run



S. N. R. 31 E.

50.20' On Iron line between Sec's  
2 and 3.

<sup>41.84</sup>  
41.84 Set a post for 1/4 Sec. cor. drove char-  
-ed stake and raised mound with  
trench, as per instructions.

<sup>70.34</sup>  
70.34 To a Dry Ravine course N 70° E

81.84 The corner to Sec's. 2, 3, 10 and 11.

<sup>81.84</sup>  
Land rolling grass hills 3<sup>d</sup> rate soil  
Oct 19<sup>th</sup> 1860.

North between Sec's 33 and 34

<sup>40.00</sup>  
40.00 Set post for 1/4 Sec. cor. drove char-  
-ed stake and raised mound with  
trench as per instructions

<sup>80.00</sup>  
80.00 Set post for corner to Sec's. 27, 28, 33  
and 34. drove charred stake and  
raised mound with trench as per  
instructions.

Land rolling grass hills 2<sup>d</sup> rate  
soil.

East on a Random line between Sec's  
27 and 34



16 396

T. V. B. 31 E

Variation  $14^{\circ}00' E$

- 40.00 Set Temporary  $\frac{1}{4}$  Sec. cor.  
80.08 Intersection N + S line 58 Yds North  
th of the corner to Sec's. 26, 27, 34  
and 35 from which corner I Run  
 $N 89^{\circ}35' W$  on a true line between  
Sec's. 27 and 34  
36.00 To a Dry Ravine. course N. E.  
40.04 Set post for  $\frac{1}{4}$  Sec. cor. drove charred  
stake and raised mound with trench  
as per instructions  
80.08 The corner to Sec's. 27, 28, 33 + 34  
Land rolling grass hills light  $2^d$   
into soil.

- North between Secs 27 and 28  
25.00 Top of Ridge course N. E. + S. W  
40.00 Set apart for  $\frac{1}{4}$  Sec. cor. drove char-  
red stake and raised mound with  
trench as per instructions  
43.00 Head of a Dry Ravine course N. E.  
80.00 Set Post for corner to Sec's. 21, 22,  
27 and 28, drove charred stake and



G. N. R. 318

raised mound with trench as per instructions,

Land rolling Grass hills 2<sup>d</sup> rate soil

East on Random line between Sec's 22 and 27,

Variation 1936 E

40.00  
40.00 Set a Temporary 1/4 Sec. cor.  
80.39  
80.39 Intersect N and S. line 21/4 Sec North of the corner to Sec's. 22, 23, 26 and 27 from which corner I Run, N 89.51' W on a true line between Sec's 22 and 27.

40.19  
40.19 Set a post for 1/4 Sec. cor. drove char-  
=ed Stake and raised mound with trench as per instructions

61.80  
61.80 To a Dry Ravine. Course N 10 E  
80.39  
80.39 The corner to Sec's. 21, 22, 27 and 28  
Land grass uplands 2<sup>d</sup> rate soil

North between Sec's 21 and 22

40.00  
40.00 Set a post for 1/4 Sec cor drove char-  
=ed Stake, raised mound with trench



## T. N. R. 31 E

as per instructions

80,00 Set apart for cor. to Secs. 15, 16  
21 and 22, drove chain stake and  
raised mound with trench as  
per instructions  
Land rolling grass hills & rich  
soil.

East on Random line between  
15 and 22

Variation  $18^{\circ}45' E$

40,00 Set a Temporary  $\frac{1}{4}$  Sec. cor.  
80,43 Intersected North & South line  
2000s South of the corner to Secs. 4,  
15, 22 & 23, from which corner I Ran  
38937 W on a true line between  
Secs. 15 and 22,

36,00 To a Dry Ravine corner N. E.

40,31 Set apart for  $\frac{1}{4}$  Sec. cor, drove  
chain stake and raised mound  
with trench as per instructions

7,43 To a dry Ravine corner N. W.

80,43 The corner to Secs. 15, 16, 21 and 22



T. N. R 31 E

Land selling grass hills light 2<sup>d</sup> rate soil

North between Sec's 15 and 16  
 4,000 Set apart for  $\frac{1}{4}$  Sec. cor, drove ch-  
 =urned Stake and raised mound  
 with trench as per instructions  
 8,000 Set a part for corner to Sec's 9,  
 10, 15 and 16, drove churned stake  
 and raised mound with trench  
 as per instructions  
 Land Soil good 2<sup>d</sup> rate soil

East on Random line between Sec's  
10 & 15

(Variation 20°30' E)

4,000 Set Temporary  $\frac{1}{4}$  Sec. cor,  
 8,003 Intersected T & S line 31/2 m. south  
 of the corner to Sec's 10, 11, 14 and 15  
 From which corner Run  
 S 89°51' W on a true line between  
 Sec's 10 & 15  
 4,001 Set apart for  $\frac{1}{4}$  Sec cor drove churned



20 310

T. A. R. B. E.

Stake and raised mound  
with trench as per instructions  
8003 The corner to Sec's, 9, 10, 15 & 16  
Land gently rolling  $2\frac{1}{2}$  rate soil  
October 20<sup>th</sup> 1860

North between Sec's 9 and 10  
19.00 To a Dry Ravine course N. E.  
40.00 Set Post for  $\frac{1}{4}$  Sec. cor. drove cham  
stake and raised mound with  
trench, as per instructions,  
80.00 Set post for corner to Sec's, 3, 4, 9  
and 10. drove cham stake and raised  
mound, with trench as per instructions  
Land rolling grass hills  $2\frac{1}{2}$  rate soil

East on Random line between Secs.  
3 and 10.

Variation  $20^{\circ} 15'$  E

40.00 Set Temporary  $\frac{1}{4}$  Sec. cor.  
80.14 Intersected N & S line 33<sup>th</sup> N. of the  
corner to Sec's, 3, 3, 10 & 11, from which cor  
nered Run.



S. N. R. & E

N 89 49' W on true line between Sec's.  
3 and 10

40.07 Set a post for 1/4 Sec, Cor, drove charred  
stake and raised mound with trench  
as per instructions.

80.14 The corner to Sec's. 3, 4, 9 and 10,  
Land. rolling grass hills 2<sup>d</sup> rate soil

North between Sec's. 3 and 4, on Random  
line.

40.00 Set Temporary 1/4 Sec, Cor,

81.78 Intersected North boundary of Towns  
-ship 47<sup>th</sup> East of the corner to Sec's  
3 and 4, from which corner Run  
50.20' On true line between Sec's 3 and  
4.

41.78 Set a post for 1/4 Sec, Cor, drove charred  
stake, and raised mound with trench  
as per instructions.

81.78 The corner to Sec's. 3, 4, 9 and 10,  
Land. Rolling grass hills. Stony soil



## T. N. R 31 E

North bottom Sec's 32 and 33.

40.00 Set post for  $\frac{1}{4}$  Sec. cor. drove charred stake and raised mound with truck as per instructions

80.00 Set post for corner to Sec's. 28. 29. 32 and 33. drove charred stake and raised mound with truck as per instructions.

Land Rolling 2<sup>d</sup> Rate soil

East on Random line between Sec's 28 and 33.

Variation 18.00' E

40.00 Set Temporary  $\frac{1}{4}$  Sec cor  
79.75 Intersected N & S line 50 Mts South of the corner to Sec's. 27. 28. 33 and 34 from which corner & Run.

589.34' W on true line between Sec's 28 and 33.

39.87 Set a post for  $\frac{1}{4}$  Sec. cor. drove charred stake and raised mound with truck as per instructions

79.75 The corner to Sec's. 28, 29. 32 and 33



## T. N. R 31 E

Land rolling 3<sup>d</sup> rate soil

North between Sec's 28 and 29  
4000 Set post for 1/4 Sec, cor, drove  
chamda stake and raised mound  
with trench as per instruction,

8000 Set apart for corner to Sec's 20, 21  
28 and 29. Drove chamda stake and  
raised mound with trench as  
per instructions.

Land Rolling 2<sup>d</sup> and 3<sup>d</sup> rate soil

East on Random line between Secs  
21 and 28.

## T. N. R 31 E

4000 Set Temporary 1/4 Sec, cor,  
8017 Intersected N and S line 4000 North  
of the corner to Sec's 21, 22, 27 & 28  
from which corner I Run  
N 89° 43' W on a true line between  
Sec's 21 and 28

4008 Set post for 1/4 Sec, cor, drove chamda  
stake and raised mound with



## T. N. R. 31 E

Truck as per instructions

8017 The corner to Sec's. 20, 21, 28 and 29  
 Land high rolling grass hills  
 3<sup>rd</sup> rate soil.

North between Sec's. 20 and 21

30.50 So bed of a Dry Ravine bears N 20  
 W.

32.50 Foot of steep hill bearing S E + N 20 W

40.00 Set a post for 1<sup>st</sup> S. cor. and raise  
 stone mound—as per instructions

50.00 Summit of hill bearing N W + S E

80.00 Set a post for corner to Sec's. 16, 17  
 20 and 21 drove chain stake and  
 raised mound with truck as per  
 instructions.

Land. 3<sup>rd</sup> and 4<sup>th</sup> rate soil

East on Random line between  
 Sec's 16 and 21.

Variation 14° 30' E

40.00 Set a Temporary 1<sup>st</sup> S. cor.

8031 Intersected N + E line. 17 lbs North



## T. N. R. 31 E

of the corner to Sec's, 15, 16, 21 & 22  
From which corner Run,

N 89° 53' W on true line between Sec's  
16 and 21,

4015 Set post for 1/4 Sec, cor, drove  
charred stake, and raised mound  
with trench, as per instructions

8031 The corner to Sec's, 16, 17, 20 & 21,  
Land West half Stony. East half  
2<sup>d</sup> rate soil

North between Sec's 16 and 17

4000 Set a post for 1/4 Sec, cor, drove  
charred stake and raised mound  
and with trench, as per instructions

5000 To a Dry Ravine course N. E.

8000 Set Post for corner to Sec's, 8, 9,  
16 and 17 drove charred stake  
and raised mound as per in-  
structions,

Land rolling grass hills 2<sup>d</sup> rate  
soil,



26

316

T. N. R. 316

East on Random line between  
Sec's. 9 & 16

Variation 20° 05' E

4000 Set Temporary 1/4 Sec. cor.  
8016 Intersected ~~line~~ N & S line 10 Ws  
South. of the corner to Sec's 9  
10, 15 & 16. from which corner  
Run.

58936 Won true line between Sec's  
9 & 16

4008 Set apart for 1/4 Sec. cor. drove  
chance stake and raised mound  
with trench as per instructions

5200 To a dry Ravine course N.E.

8016 The corner to Sec's. 8, 9, 16 and 17  
Land rolling grass hills 2, rat soil

North between Sec's 8 and 9

2000 To a Dry Ravine course East

4000 Set apart for 1/4 Sec. cor. drove chance  
stake and raised mound with  
trench as per instructions

8000 Set apart for corner to Sec's



T. N. R. 31 E

4, 5, 8 and 9. drove charred stake  
and raised mound with trench  
as per instructions  
Land Broken + Stony,

East on Random line between Sec's  
4 and 9

Variation 20° 15' E

40.00 Set Temporary 1/4 Sec. cor.  
80.02 Intusect N + S line 30 lbs South of  
the corner to Sec's. 3, 4, 9 and 10  
from which corner I Run  
S 89° 47' W on true line between Sec's  
4 and 9

40.01 Set post for 1/4 Sec. cor. drove charred  
stake and raised mound with trench  
- as per instructions,

80.02 The corner to Secs. 4, 5, 8 and 9  
Land mostly rolling table land 2<sup>d</sup> rate  
soil

North on Random line between Sec's  
4 and 5.



## T. N. B. 31 E

- 40.00 Set Temporary  $\frac{1}{4}$  Sec. cor.  
 82.82 Intersect North boundary of the  
 Township 18<sup>ths</sup> East of the corner  
 to Sec's 4 and 5, from which  
 corner run  
 50.08' E on true line between Sec's  
 4 and 5.
- 42.82 Set a Post for  $\frac{1}{4}$  Sec. cor. drove char-  
 red stake & made mound trench as per instructions  
 82.82 The corner to Sec's 4, 5, 8 and 9  
 Land broken 3<sup>d</sup> & into soil,  
 Oct. 22<sup>d</sup> 1800

- North between Sec's 31 and 32
- 40.00 Set post for  $\frac{1}{4}$  Sec. cor. drove char-  
 red stake and raised mound  
 with trench as per instructions
- 80.00 Set a post for corner to Sec's  
 29, 30, 31 and 32 drove charred stake  
 and raised mound with trench  
 as per instructions
- Land gently rolling grass plains  
 2<sup>d</sup> & into soil



T. N. R. 31 E

29  
319

East on Random line between  
Sec's. 29 and 32,

Variation 20° 00' E

40.00 Set Temporary 1/4 Sec. cor.  
79.91 Intersected N and S line 19 Mts North  
of the corner to Sec's. 28, 29, 32  
and 33, from which corner I Run  
N 89° 53' W on true line between Sec's  
29 and 32,

39.95 Set post for 1/4 Sec. cor. drove  
charred Stake and raised mound  
and with trench as per instruc-  
tions.

79.91 The corner to Sec's. 29, 30, 31 & 32  
Land, rolling 2<sup>nd</sup> rate Soil

West on Random line between Sec's  
30 and 31,

40.00 Set Temporary 1/4 Sec. cor.  
89.36 Intersect West boundary of Town-  
ship. 50 Mts South of the corner to  
Sec's. 30 & 31 from which corner I  
Run,



## T. N. R. E.

589<sup>39</sup> Center line between  
Sec's. 30 and 31.

49<sup>36</sup> Set a post for  $\frac{1}{4}$  Sec. cor. above  
Chumma Stake, and raised mound  
and with trench as per instructions  
= on

89<sup>36</sup> The corner to Sec's. 29, 30, 31 & 32  
Land, rolling 2<sup>d</sup> Rate Soil

North between Sec's. 29 and 30.

40<sup>00</sup> Set a post for  $\frac{1}{4}$  Sec. cor. and  
raised Stone Mound as per  
instructions.

80<sup>00</sup> Set a post for Cor. to Secs  
19, 20, 29 and 30, and raised Stone  
Mound as per instructions  
Land gently rolling 2<sup>d</sup> rate Soil

East on Random line between Sec's  
20 and 29

Variation 2000' E

40<sup>00</sup> Set Temporary  $\frac{1}{4}$  Sec cor  
79<sup>70</sup> Intersect N & E line. at post cor.



## T. N. R. 31 E

to Secs. 20, 21, 29 & 30, from which  
Corner & Run

West on true line between Sec's  
20 and 29

39.85 Set post for  $\frac{1}{4}$  Sec. cor, drove  
chama Stake and raised mound  
with trench as per instructions

79.70 The Corner to Sec's, 19, 20, 29 & 30  
Land gradually rolling 2<sup>d</sup> rate  
Soil,

West on Random line between Sec's  
19 and 30

40.00 Set Temporary  $\frac{1}{4}$  Sec. cor,

89.40 Intersect West boundary of Township  
95 Ws South of the Corner to Sec's 19 & 30  
from which Corner & Run.

589' 19' On true line between Sec's  
19 and 30.

49.40 Set post for  $\frac{1}{4}$  Sec. cor, drove  
chama Stake and raised mound  
with trench as per instructions

50.00 To a Dry Ravine course N & SW



## T. A. R. 31. E

8940 The Corner to Sec's. 19, 20, 29  
and 30.  
Land Storey.

North between Sec's. 19 and 20  
40.00 Set post for 1/4 Sec. Cor. and drive  
or Chama Stake and raised  
Stone mound with trench as per  
instructions.

80.00 Set post for corner to Sec's 17.  
18, 19, and 20. Drive Chama Stake  
and raised mound with trench  
as per instructions  
Land rolling 2<sup>d</sup> rate soil

East on Random line between Sec's  
17 and 20.

## Variation 2000' E

40.00 Set Temporary 1/4 Sec. Cor.  
79.80 Intersected N & S line 3000' North  
of the corner to Sec's. 16, 17, 20 & 21 from  
which corner I Run  
N 89° 47' W on true line between



## T, N R 31 E

Sec's 17 and 20

3990 Set post for  $\frac{1}{4}$  Sec, cor, above  
 Diana Stake and raised mound  
 with trench as per instructions

7980 The corner to Sec's, 17, 18, 19 & 20  
 Land Broken 2<sup>d</sup> & 3<sup>d</sup> rate Soil  
 Oct 23<sup>d</sup> 1860

West on a Random line between Sec's  
 18 and 19

4000 Set Temporary  $\frac{1}{4}$  Sec, cor,

8948 Intusseta West boundary of Town-  
 -ship 48 lbs South of the corner  
 to Sec's, 18 and 19, from which  
 corner I Run,

388.5' On a true line between Secs  
 18 and 19

4948 Set a post for  $\frac{1}{4}$  Sec, cor, above Diana  
 Stake and raised mound with trench  
 as per instructions

5500 To a Dry Ravine Course N 78

8948 The corner to Sec's, 17, 18, 19 and 20  
 Land, rolling 2<sup>d</sup> and 3<sup>d</sup> rate Soil



## T, N R 31 E

North bottom Sec's 17 and 18

40.00 Set a post for  $\frac{1}{4}$  Sec. cor, drove char-  
-ed stake and raised mound with  
trench as per instructions

80.00 Set a post for corner to Sec's. 7, 8,  
17 and 18, drove charred stake  
and raised mound with trench  
as per instructions

Same. Level good 2<sup>d</sup> rate soil

Custom Random line between Sec's  
8 and 17

Variation 2000' E

40.00 Set a temporary  $\frac{1}{4}$  Sec. cor,  
7970 Intersecting N & S line 4000' North  
of the corner to Sec's. 8, 9, 16 & 17  
from which I Run.

N 89 $\frac{1}{2}$  W on a true line between  
Sec's 8 and 17.

39.85 Set post for  $\frac{1}{4}$  Sec. cor, drove  
charred stake and raised mound  
with trench as per instructions

75.00 To a Long Ravine Course North



## T. N. R. 31 E

7970 The corner to Sec's. 7, 8, 17 and 18  
Land rolling 2<sup>d</sup> + 3<sup>d</sup> rate Soil

West on a Random line between Sec's  
7 and 18

4000 Set temporary 1/4 Sec. cor.

8950 Intersecting West boundary of Township  
2.00 lbs South of the corner to Sec's  
7 and 18, from which corner I Run  
S 88.34 E on a true line between  
Sec's 7 and 18.

4950 Set post for 1/4 Sec. cor. drove  
chain stake and raised mound  
with trench as per instructions

8950 The corner to Sec's. 7, 8, 17 and 18  
Land rolling 2<sup>d</sup> rate Soil

North between Sec's 7 and 8

2000 A Dry Ravine. Course East,

4000 Set post for 1/4 Sec. cor. drove chain  
stake and raised mound with trench  
as per instructions

8000 Set apart for corner to Sec's. 5, 6, 7 & 8



T. N. R. 31 E

drove diamna Stake and raised mound with trench as per instructions  
Land Broken & Stony.

Easton Random line between Sec's  
5 and 8

Variation 2100' E

4000 Set Temporary 1/4 Sec. cor,  
7922, Intersected N & S line 44 Ms North  
of the corner to Sec's 4, 5, 8 & 9 from  
which corner I Run

N 89° 41' W on a true line between  
Sec's 5 & 8

3961 Set post for 1/4 Sec. cor, and drove char-  
-ed Stake, and raised mound with  
trench as per instructions.

7922, The corner to Sec's 5, 6, 7 and 8,  
Land Broken & Stony.

Weston a Random line between  
Sec's 6 and 7.

4000, Set Temporary 1/4 Sec. cor,  
89,75, Intersected West boundary of the



T. A. R. 31 E

37  
327

Township, 268 lks South of the  
Corner, to Sec's. 6 and 7 from which  
Corner I Run.

588.57' E On a true line between Sec's  
6 and 7

49.75 Set post for  $\frac{1}{4}$  Sec, cor, drove charred  
Stake and raised mound with  
89.75 ~~much~~ <sup>much</sup> as per instructions  
The corner to Sec's. 5, 6, 7 and 8  
Land, rolling 2" and 3" rate soil

North on Random line between  
Sec's. 5 & 6

40.00 Set Temporary  $\frac{1}{4}$  Sec, cor,  
83.00 Intersecting North boundary of the  
Township 52 lks East of the corner  
to Sec's 5 and 6, from which  
Corner I Run.

50.23' E On a true line between Sec's  
5 and 6,

43.00 Set a post for  $\frac{1}{4}$  Sec, cor, drove char-  
red stake and raised mound with  
much as per instructions

83.00 The corner to Sec's 5, 6, 7 and 8,



## T. N. R. 31 E

Land, South half low 2<sup>d</sup> rate  
soil. North half Broken & Stony  
Oct 24<sup>th</sup> 1860,

The quality of the land in this Township, is about an average. There is a fair proportion of 1<sup>st</sup> rate land, and well adapted for cultivation.

The greater portion of the Township is rolling grass upland, and is well adapted for grazing purposes. The uplands are good 2<sup>d</sup> rate soil, covered with rich bunch grass. There are several fine, fresh water Springs - which afford an abundance of water, the year round.

### List of Names

A list of the names of the individuals employed to assist in forming measuring or marking



T. N. R. 31 E

the lines and corners described  
in the foregoing field notes of  
Township No. 1 North of the base  
line of Range No. 31 East of the  
Willamette Meridian. Showing  
the respective capacities in which  
they acted

Dave Diers Chairman

J. H. Bell. " "

Mr. H. Smith Assessor



We hereby certify that we assisted  
 Joseph A. Burnetts deputy surveyor  
 in surveying the subdivision lines  
 in Township No 1 North of the  
 base line of Range No 31 East of  
 the Willamette Meridian, and that  
 said Township has been in all res-  
 pects to the best of our knowledge  
 and belief, well and faithfully sur-  
 veyed, and the boundary monuments  
 planted according to the instructions  
 furnished by the surveyor General,

Darius Diners Chairman  
 Thomas A Bell Chairman  
 William H Smith Assessor

Subscribed & sworn to by the above named persons  
 before me a Justice of the Peace, in the County of Wasco  
 in the State of Oregon  
 this 30 day of Oct: 1860. J B Hodge, J. P.



I Josiah, A. Burnett, deputy Surveyor, do solemnly swear that, in pursuance of a contract with W. W. Chapman Surveyor of the lands of the United States in the State of Oregon, bearing date the 12<sup>th</sup> day of September, 1860, and in strict conformity to the laws of the United States, and the instructions furnished by the said Surveyor General, I have faithfully surveyed, the subdivisions lines of Township 1 North, of the base line, of Range 31 East of the Willamette Meridian in the State of Oregon, aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such Survey

J. A. Burnett, Depty. Swr.

Subscribed by said Josiah A. Burnett depty. Swr., and sworn to before me.

Apr. 21. 1860

W. W. Chapman  
Sur. Genl.



Surv. Genls Office

Eugene City, Dec: 5<sup>th</sup>, 1860.

The foregoing field notes of the survey of the subdivisions of Township No. 1 North, Range No. 31 East of the Willamette Meridian, Oregon executed by Josiah A. Burnett, under his Contract of the 12<sup>th</sup> day of September 1860, having been critically examined, the necessary corrections and explanations made the said field notes and the surveys they describe are hereby approved.

A. W. Chapman  
Surv. Genl. of Oregon