

FIELD NOTES

Of the survey of the

*Exteriors*Lines of *Tps. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100**R's 31, 33, 34 & 35, E. Tps. 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35* Willamette Meridian, Oregon,as surveyed by *James P. Currier and James E. Poland*
their special

U. S. Deputy Surveyor, under his Contract No. _____

dated *May 4th*, 1887Survey commenced, *June 14th*, 1887Survey completed, *Aug 30th*, 1887

NAMES AND DUTIES OF ASSISTANTS.

L. J. Wooley , Compassman.
J. Medley , Chainman.
W. H. Medley , Chainman.
Guy Davis , Chainman.
Frank Selshard , Chainman.
J. P. Crowner , Axman.
J. A. Hadley , Axman.
..... , Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

36 We, J. S. Medley, W. H. Medley, Frank Behshaw
and Guy Davis

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the Exterior lines of Twp. 10, R. 32, 33 & 34 E. Twp. 21, R. 33 & 35 E. Twp. 1 lines of A. R. 32, 33, 34 & 35 E. Twp. 21, R. 32, 34 & 35 E. Willamette Meridian, Oregon.

J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Behshaw, Chainman.
Guy Davis, Chainman.

Subscribed and sworn to before me this 14th day of June, 1887

[SEAL.] James P. Currier
U.S. Deputy Surveyor

We, B. B. Crowner and J. R. Haddley, do solemnly swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Exterior lines Twp. 10, R. 32, 33 & 34 E. Twp. 21, R. 33 & 35 E. Twp. 1 R. 32, 33, 34 & 35 E. Twp. 21, R. 32, 34 & 35 E. Willamette Meridian, Oregon.

B. B. Crowner, Axman.
J. R. Haddley, Axman.

Subscribed and sworn to before me this 14th day of June, 1887

[SEAL.] James P. Currier
U.S. Deputy Surveyor

72
442

(4)

Extentions of T. 1 North R. 32 East -
Willamette Meridian, Oregon.

(8003-10 M.)

Beginning on the Base Line at
The Cor. To Tps. 10 N. R. 32 + 33 E.
I run North an E. by Sec 36,
Var. 20° E

Descending Gradually
39.50 To old 1/4 Sec. Cor. Found pits
& earth mound. Set a basalt-
stone 10x8x6 ins 7 ins in old md.
mkd. 1/4 on N. face. Dug pits 18x
15x12 ins at + S. of Cor. ^{5 1/2 ft dist} Raised
earth mound, 1/2 ft high 3/2 ft
long along side +

43.00 Hollow Course N - 25

69.95 Trail Course N.E. + S.W.

79.00 Found old Cor. To Secs. 25, 30,
31 + 36 Found pits + md. Set
a basalt-stone 10x12x8 ins 11 ins
in old md. mkd. 1 Notch on S
& 5 on N. Edges. Dug pits 18x18
x12 ins in Cor. of each sec. 5 1/2 ft
dist; Raised earth mound 2 ft

Extremes of T. 1 North R. 2 East -
Willamette Meridian, Oregon.

high 4 1/2 ft. base along side
Land rolling
Soil 2nd rate
No timber Grass short -

North an E. by Sec. 20
Var. 20° 30' E

- 860 Spring branch, 2 hrs. wide C. N.
- 3985 Found pit + mound of old 1/4 Sec.
Cor. Sec-a basalt-stone 12x10x10
ins 8 ins in the ground in old
mnd. mnd 1/4 on W face for 1/4 Sec.
Cor. Dug pit 18x18x12 ins N. + S.
of Cor 8 1/2 ft. dist. raised earth
mnd. 1/2 ft. high 8 1/2 ft. base along side
- 7970 To old Cor. to Secs. 19, 24, 25 + 30.
Found pit + mnd of earth, Sec-a
basalt-stone 14x10x8 ins 10 ins in
the ground for Cor. to Secs 19, 24, 25
+ 30. mnd 2 notches on S + 4 on N.

Exteriors of T. 1 North R. 32 East -
Willamette Meridian, Oregon.

(8093-10 M.)

Edges. Dug pits 18x18x12 ins in Cor.
of each Sec. 5 1/2 ft - dist - & Raised ear-
th mound 2 ft - high 4 1/2 ft - base
along side

Land rolling Soil, 1st - rain
no timber & Buck Grass & rabbit - sage.

North on East - by Sec. 24
Var 20° E

- 1870 - Dry branch Course N - 50
- 2400 Top of Hill + 75
- 3963 Found old 1/4 Sec. Cor. pits & md.
Set a Lasall - stone 14x12x8 ins 9 ins
in the ground for 1/4 Sec. Cor. Mtd
1/4 ~~mi~~ N face, redug pits 18x18x
12 ins N & S. of cor. 5 1/2 ft - dist. &
Raised earth md. 1 1/2 ft - high 3 1/2 ft -
base along side
- 4725 dry Gulch Course N - 50
- 5000 Summit of Hill + 50

Extremities of T. / North R. 32 East-
Willamette Meridian, Oregon.

7615 Trail Course N. N.

7925 Found old mud & pits to cor to Secs.
13, 18, 19 & 24 Set a Lasall-stone
9x8x7 ins 6 ins in the ground
for Cor. to Secs. 13, 18, 19, & 24 used 3
notches on N. & S. edges. dug pits
18x18x12 ins in each sec. 5-1/2 ft.
dist raised earth mound 2 ft.
high 4-1/2 ft. base along side
Land rolling soil white
sandy 3rd rate
Bunch grass, Sage Bush no timber

North on East-side Sec. 13
Var 19° E

2625 dry gulch Course N -100

3100 Top of hill +50

3980 To old 1/4 sec. Cor. found pits & mud.

Set a Lasall-stone 10x10x8 ins 7 ins
in the ground, for 1/4 Sec. Cor.

446

Extensions of T. 1 North R. 32 East -

Willamette Meridian, Oregon.

(8093-10 M.)

marked $\frac{1}{4}$ on N Face. Redding pits
 $18 \times 18 \times 12$ ins N. & S of Cor & $5\frac{1}{2}$ ft-
 dist: & Raised Earth mound $1\frac{1}{2}$
 ft. high & $3\frac{1}{2}$ ft. base along side
 Descend gradually.

54.00 dry mulch course Fr. -100

59.00 Top of Hill + 50

79.60 Turned old mound & pits for Cor.
 To Secs 7, 12, 13 & 18. Set a basalt-
 stone $12 \times 8 \times 8$ ins in the
 ground. for Cor. To Secs. 7, 12,
 13, & 18 marked 4 notches on S &
 2 on N Edges. Redding pits $18 \times$
 18×12 ins in each Sec. $5\frac{1}{2}$ ft-
 dist: & Raised earth mound
 2 ft. high $4\frac{1}{2}$ ft. base along side
 Land rolling
 Soil sandy 3rd Rate
 Sage brush & poor grass.

Extents of T. 1 South R. 32 East-
Willamette Meridian, Oregon.

North on E. Day, of Sec. 12
Jan. 21st E

- 700 dry ditch
- 3987 Found pis + md. for old $\frac{1}{4}$ Sec.
Cor. Set-a has all-stone $14 \times 12 \times 12$
ins 9 ins in the ground for $\frac{1}{4}$
Sec. Cor. mtd. $\frac{1}{4}$ on N face
Reaug pis $18 \times 18 \times 12$ ins N + S of Cor.
 $5\frac{1}{2}$ ft. dia. + Raised earth mound
 $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base along side
- 7957 Found old md. + pis for Cor to
Secs. 1, 6, 7 + 12. Set-a has all-stone
 $12 \times 9 \times 8$ ins 8 ins in the ground for
new Cor. mtd 5 notches on S +
1 on N. Edges. Reaug pis 18×18
 $\times 12$ ins in each Sec. Raised earth
mound 2 ft high $4\frac{1}{2}$ ft base along side
Land level soil whi. sandy ends
rare + scattering sage brush
+ bunch grass

Extensions of T. 1 North R. 32 East -
Willamette Meridian, Oregon.

(8093-10 M.)

North on E. Bay of Sec 1
Var 20°45'E

4,000 Wagon road Course N.E.

37,500 very ditch Course w

38,977 Found pits & md for old 1/4 Sec.

Cor. Set a basalt-stone 14x12x10
ins 9 ins in the ground for new

Cor. mtd. 1/4 on N. face. Redug.
^{18x18x12 N.E. of cor 5 1/2 ft. dist.}
Pits & Raised earth mound 1 1/2 ft.
high 3 1/2 ft. base along side

41,500 Trail Course N.E.

66,600 " " " "

77,974 Found old Cor. to Tps. 1 & 2 of
R. 32 + 33 East: Pits & earth md -
very plain. Set a basalt-stone
10x8x7 ins 6 ins in the ground
Dug pits 24x18x12 ins lengthwise
on each line N.E. & N. of Cor 6 ft.
dist. Raised earth md 2 1/2 ft. high
5 ft. base along side

Extensior of T. 1 North R. 32 East-

Willamette Meridian, Oregon.

Land level

Soil 1st-rate

Scattering Sage brush & bunch grass

July 25th 1887

This Township is mostly rolling land. Soil suitable for farming. Water scarce.

There is no timber except some scattering Cotton wood on McKey creek which runs through through Twp from S. To N. at an average of 1 1/2 miles from East Bay. The bottom land is gravelly.

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by James P. Currier
and James E. Holland, U. S. Deputy Surveyors, to assist in
 running, measuring, and marking the lines and corners described in the
 foregoing field notes of the survey of the Exterior lines of Tps. 1, 2,
Rs. 32, 33, 34 & 35, Tps. 2, 1, Rs. lines of 33, 34 & 35 E, Tps. 1, 4, Rs. 32, 33, 34 & 35 E
Tps. 2, 1, Rs. 32, 34 & 35 E Willamette Meridian, Oregon,
 showing the respective capacities in which they acted:

- L. A. Wooley , Compassman.
- J. J. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Crowner , Axman.
- J. R. Hadley , Axman.
- , Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted James P. Currier and James
E. Holland, U. S. Deputy Surveyors, in surveying
 all those parts or portions of the Exterior lines of Tps. 1, 2, Rs. 32, 33, 34 & 35
Tps. 2, 1, Rs. 33, 34 & 35 E, Tps. 1, 4, Rs. 32, 33, of 34 & 35 E, Tps. 2, 1, Rs.
3, 2, 34, & 35 E Willamette Meridian, Oregon,
 as represented in the foregoing field notes as having been surveyed by
 him and under his direction; and that said survey has been in all respects,
 to the best of our knowledge and belief, well and faithfully surveyed,
 and the corner monuments established, according to the instructions
 furnished by the U. S. Surveyor General of Oregon.

- L. A. Wooley , Compassman.
- J. J. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Crowner , Axman.
- J. R. Hadley , Axman.
- , Flagman.

Subscribed and sworn to before me this 30th day of
September, 1887.

[SEAL.]

James P. Currier
 U. S. Deputy Surveyor.

FINAL OATH OF DEPUTY SURVEYOR.

We, James P. Currier and James E. Poland, United States
Deputy Surveyor, do solemnly swear that in pursuance of instructions
received from Douglas H. Taylor, U. S.

Surveyor General for Oregon, bearing date of the 13th

day of May, 1887, I have well, faithfully,
and truly, in my own proper person, and in strict conformity with the
instructions furnished by the U. S. Surveyor General for Oregon, the
Surveying Manual, and the laws of the United States, surveying all

those parts or portions of Exterior lines of Twp. 1 N., R. 32, 33 & 34 E., Twp. 1

2 N., R. 33 & 35 E., Twp. 1 N., R. 32, 33, 34 & 35 E., Twp. 2 N., R. 32, 34 & 35 E.

Willamette Meridian, in the State of Oregon, as are represented in the
foregoing field notes as having been surveyed by me and under my
directions; and I do further solemnly swear that all the corners of said
survey have been established and perpetuated in strict accordance with
the Surveying Manual, printed instructions, the special written instruc-
tions of the U. S. Surveyor General for Oregon, and in the specific man-
ner described in the field notes, and that the foregoing are the *true* field
notes of such survey, and should any fraud be detected I will suffer the
penalty of perjury under the provisions of an act of Congress approved
August 8, 1846.

James P. Currier James E. Poland
U. S. Deputy Surveyors

Subscribed and sworn to before me this Fifteenth
day of February, 1888

W. Woodcock
Notary Public
for Oregon

Office of U. S. Surveyor General,

Portland, Oregon, June - 11th/₄, 1888.*foregoing*

The following Field Notes of the Survey of the

Eastern lines of T. 1 S. Rgs 32.

34. E. T. 2 S. Rgs 33 and 35

T. 1 N. Rgs 32-33-34 and 35 East

T. 2 N. Rgs 32-34 and 35 East

Will. Mel. Or.

executed by James J. Currier and James E. Noel

Special Joint U.S. Dept. Surveyors

under his Contract No. —, dated May

4th, 1887, having been critically examined,

the necessary corrections and explanations made, the

said Field Notes and the survey they describe, are

hereby approved.

Douglas W. Taylor

Surveyor General.