

We hereby certify that we assisted

Daniel Chaplin, deputy Surveyor in

subdividing Township No 1 South of

the Base Line of Range No 33 East of

the Willamette Meridian and that

said Township has been in all respects

the best of our knowledge and

belief well and faithfully surveyed

and the boundary monuments

planted according to the instructions

furnished by the Surveyor General

David P. Thompson Comptroller

of S. G. T. or Chairman

of W. P. Newman "

of H. M. Dean Assessor

of the same Subscribed before me

this 8th day of November 1864

J. S. Gilliland

Justice of the Peace
in Multnomah Co Oregon

237

37

Ironship 1 North Range

North between Secs 35 & 36

again

4000 Set Stone 17x10x8 for 1/4 Sec corner

8000 Set post for corner to Secs 25, 26, 35 & 36

in corner of Earth with Hanna stake
pits & as per instructions

Hanna Level Soil 1 1/2' late

Easton a re-run on line between Secs 25 & 36

4000 Set temporary 1/4 Sec cor.

8000 Intersect East boundary at corner

to Secs 25 & 36 from which corner from

Weston a true line between Secs 35 & 36

4000 Set Stone 18x10x10 for 1/4 Sec corner

8000 The corner to Secs 25, 26, 35 & 36

Hanna Level

Soil 1 1/2' late

32 East Willamette Meridian

North between Secs 25 & 26

chains bearing 21° E.

4000 Set post for $\frac{1}{4}$ Sec cor. in corner of East
with Charcoal Stake pits & copper
instructions

8000 Set Stone 18x10x8 for corner to Secs 23, 24,
25 & 26

Level Soil 1 $\frac{1}{2}$ rate

Easton & Meridian line between Secs 24 & 25

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8000 Intersect East boundary at corner to
Secs 24 & 25 - ~~in corner~~ ~~of Secs~~

West on a true line between Secs 24 & 25

4000 Set post for $\frac{1}{4}$ Sec cor. in corner of East
with Charcoal Stake pits & copper
instructions

8000 The corner to Secs 23, 24, 25 & 26
Level Soil 1 $\frac{1}{2}$ rate

Township 1 North Range
North between Secs 23824

chains (va. 210 E.)

4000 Set post for $\frac{1}{4}$ Sec. corner in mound
of earth with charred stake pits &
asper instructions

8000 Set post for corner to secs 13, 14, 238
& 24 in mound of earth with charred
stake pits & asper instructions
Luna Level Soil 1st rate

East on a common line between Secs 13824

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

79.71 Intersect East boundary 70 ft
North of corner to secs 13824

from which corner I run

N 89° 30' W. on a true line between Secs 13824

39.85 Set post for $\frac{1}{4}$ Sec. corner in mound of
earth with charred stake pits & asper
instructions

79.71 The corner to secs 13, 14, 23824
Luna Level Soil 1st rate

32 East Willamette Meridian

North between Secs 13 & 14

Chains

on 20th E.

4000 Set Stone 18x8x6 for $\frac{1}{4}$ sec. cor.

74.75 Road bears N E & S W

8000 Set post for corner to sec 11, 12, 13 & 14
in Monna of Earth with charna stake
pits & as per instructions
Level Level Soil $\frac{1}{4}$ sec.

Easton a random line between Secs 12 & 13

4000 Set temporary $\frac{1}{4}$ sec. cor.

8000 Intersect East boundary at corner
to Secs 12 & 13 from which run

West on a true line between Secs 12 & 13

4000 Set post for $\frac{1}{4}$ sec. cor. in Monna of Earth
with charna stake pits & as per instructions

72.75 Road bears N E & S W

8000 The corner to sec 11, 12, 13 & 14

Level Level Soil $\frac{1}{4}$ sec.

241

47

Township 1 North Range
North between Secs 11 & 12

chains

ca. 21° E.

4000 Set post for $\frac{1}{4}$ Sec cor. in corner of East
with charred stake pits & as per instructions

8000 Set post for corner to Secs 1, 2, 11 & 12
in corner of East with charred stake
pits & as per instructions
Level Level. Soil 1st sect.

East on a range on line between Secs 1 & 12

4000 Set post for temporary $\frac{1}{4}$ Sec cor.

8042 Intersect East boundary 68th South
of corner to Secs 1 & 12 from which I run

8931¹ on a true line between Secs 1 & 12

430 Road bench E & S W

4021 Set post for $\frac{1}{4}$ Sec corner in corner
East with charred stake pits &
as per instructions.

8042 The corner to Secs 1, 2, 11 & 12

Level Level. Soil 1st sect.

32 East Willamette Meridian

North on a corner between Secs 18 & 2
chains be 19 1/2° E.

4000 Set post for temporary 1/4 sec. cor.

8075 Intersect North boundary at corner
to Secs 18 & 2 from which corner I run

South on a true line between Secs 18 & 2

4075 Set post for 1/4 sec cor. in corner of
Earth with chains stake pits & as per
instructions

8075 True corner to Secs 18, 19, 20 & 21
Level. Soil 1/2" late

North between Secs 34 & 35

4000 Set post for 1/4 sec corner in corner of Earth
with chains stake pits & as per instructions

8000 Set post for corner to Secs 34, 35, 26 & 27
in corner of Earth with chains stake
pits & as per instructions

Level. Soil 1/2" late

243

713

Township 1 North Range
 chains East on a true line between Secs 26 & 35
 4000 Set temporary $\frac{1}{4}$ sec cor.
 8000 Intersect N & S Line at corner to Secs
 25, 26, 35 & 36 from which I run
 West on a true line between Secs 26 & 35 -
 2288 Brook & Mes wire runs N 20° W
 4000 Set post for $\frac{1}{4}$ sec cor. in mound
 Earth with charred stake pits &c
 as per instructions
 8000 The corner to Secs 26, 27, 34 & 35 -
 Land gently rolling Soil $\frac{1}{11}$ rate

North between Secs 26 & 27

(Dec. 19 $\frac{1}{4}$ E.

3650 Road runs N E. & S W
 4000 Set post for $\frac{1}{4}$ sec cor. in mound of Earth
 with charred stake pits &c as per instructions
 8000 Set post for corner to Secs 22, 23, 26 & 27
 in mound of Earth with charred stake
 pits &c as per instructions
 Land Level Soil $\frac{1}{11}$ rate
 October 20th 1864

32 East Willamette Meridian

Easton & Dawson line between Secs 23 & 26

4000

Set temporary 1/4 Sec. cor.

8000 Intersect N & S Line at corner to Secs

23, 24, 25 & 26 from which I run

Westward true line between Secs 23 & 26

2800 Dry bed of Creek bears N W

4000 Set post for 1/4 Sec corner in mound of Earth

with Charney stake pits & as per instructions

4650 Road bears N E & S W

8000 The corner to Secs 22, 23, 26 & 27

Land gently rolling. Soil 1/4 rate

North between Secs 22 & 23

Dec 1934 E

3550 Road bears N E & S W

4000 Set post for 1/4 Sec. cor. in mound of Earth

with Charney stake pits & as per instructions

8000 Set post for corner to Secs 14, 15, 22 & 23

in mound of Earth with Charney stake

pits & as per instructions

Level Soil 1/4 rate

245

45-

Township 1 North Range

Eastern boundary line between Secs 14 & 23 ²³
chains

4000 Set temporary 1/4 sec corner

8000 Intersect N & S Line at corner

traces 13, 14, 23 & 24 from which I run

Western true line between Secs 14 & 23

32.75 Dry bed of creek course N & W

34.40 Road bears N & S

40.00 Set post for 1/4 sec corner in mound of earth
with Charred Stake pits & Casp instructions

73.60 Road bears N E & S W

8000 The corner traces 14, 15, 22 & 23

Some gently rolling. Soil 1st rate

North between Secs 14 & 15

on 20° E.

13.00 Road bears N E & S W

4000 Set post for 1/4 sec corner in mound of earth
with Charred Stake pits & Casp instructions

8000 Set post for corner traces 10, 11, 14 & 15

in mound of earth with Charred Stake
pits & Casp instructions

Some Level. Soil 1st rate

32 East Willamette Meridian

chain

East on a random line between Secs 10 & 14

4000 Set post for temporary 1/4 Sec corner

8000 Intuse at N & S line at corner to Secs

11, 12, 13 & 14 from which I run

West on a true line between Secs 11 & 14

3650 by line of creek runs N 10° W

4000 Set post for 1/4 Sec cor. from which

(A) Balm 18 in diam bears S 75° E 95 Rod dist

(A) " 18 " " " N 57° E 100 " "

8000 The corner to Secs 10, 11, 14 & 15 -

Level rolling Soil good 20% water

Some Balm timber on dry creek

North between Secs 10 & 11

by 19 1/2 E

4000 Set post for 1/4 Sec cor. in corner of East

with charred stake pits & as per instructions

8000 Set stone 20x16x8 for corner to Secs 2, 3, 10 &

"

Level Soil 1/2 water

~~247~~

Township 1 North Range

Eastern a true line between Secs 2 & 11
chains

- 4000 Set post for temporary 1/4 sec cor.
- 8000 Intersect h & J line at corner to sec 1, 2, 11 & 12 from which I run West on a true line between Secs 2 & 11
- 4000 Set post for 1/4 sec corner in mound of Earth with marked stake pits &c as per instructions
- 7030 Brook & Ws in Sec 11 North
- 8000 The corner to Secs 2, 3, 10 & 11
Level rolling Soil 2nd rate

North on a true line between Secs 2 & 3 be. 19 1/2° East

- 4000 Set post for temporary 1/4 sec cor.
- 8040 Intersect North boundary at corner to Secs 2 & 3 from which corner I run South on true line between Secs 2 & 3
- 1750 Dry bed of creek runs N W
- 2400 Same creek " N E
- 3000 " " " N W
- 4040 Set post for 1/4 sec corner from which
 @ Cottonwood 10 in diam bears N 75° W 34 1/2 dist
 @ " 18 " " " N 15° E 96 " "
- 8040 The corner to Secs 2, 3, 10 & 11
Level level creek bottom
Soil 1st rate Timber bottomwood

32 East Willamette Meridian

North between Secs 33 & 34

chains

1250 Spring Brook 3 Monarimus N E

2250 Birch Creek by line Course N E

2480 Level field bears N E & S W

4000 Set post for $\frac{1}{4}$ Sec corner in corner of East
with charred stake pits & as per instructions8000 Set post for corner to Secs 33, 34, 27 & 28
in corner of East with charred stake pits
& as per instructionsLevel Soil $\frac{1}{4}$ rate

Timber Cottonwood & Birch

Eastern range on line between Secs 27 & 34

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.8030 Intersect N & S Line at corner to Secs
26, 27, 34 & 35 - from which I run

Western true line between Secs 27 & 34

2656 Road bears N & S

3300 Birch Creek 6 Monarimus N E

4015 Set Stone 15 X 8 X 8 for $\frac{1}{4}$ Sec corner

8030 The corner to Secs 27, 28, 33 & 34

Level rolling

Soil $\frac{1}{4}$ rateSome Cottonwood and Birch Timber
on the creek

249

49

Township 1 North Range

North between Secs 27 & 28

chains per. 20° E.

4000 Set stone 15x8x5 for 1/4 sec. cor.

8000 8000 Set post for corner trees 21, 22, 27 & 28 in mound of Earth with cleared stake pits & as per instructions
Lance rolling. Soil 1/2 rate

Eastern apanaom line between Secs 27 & 27

4000 Set post for temporary 1/4 sec. cor.

8030 Enter at N & S Line 70 Ws north of corner trees 22, 23, 26 & 27 from which corner Run

N 89° 30' W. on a true line between Secs 22 & 27

2280 Road bears N & S

2610 Enter field bears N & S

3825 Birch Creek 10 Ws near runs north

4075 Set post for 1/4 sec corner from which
@ Birch 10 in diam bears S 60° E 7 Ws dist dist
@ yellow wood 4 in diam bears N 45° W 8 " " "

8030 The corner trees 21, 22, 27 & 28

Lance gently rolling

Soil 1/2 rate

Timber on crest Cottonwood &

Birch

32 East Willamette Meridian
North between Secs 21 & 22

chains (ba. 22° E.

4000 Set post for $\frac{1}{4}$ sec cor. in corner of East
with charred stake pits & copper instructions

8000 Set post for corner traces 15:16, 21 & 22
in corner of East with charred stake
pits & copper instructions

Land gently rolling Soil 1st rate

East on a meridian line between Secs 15 & 22

4000 Set temporary $\frac{1}{4}$ sec corner

8000 Intense at N & S line at corner traces

14, 15; 22 & 23 from which comes Iron

Western true line between Secs 15 & 22

2010 Enter field bears N. & S.

3710 Dry bed of Birch Creek course North

4000 Set post for $\frac{1}{4}$ sec corner in corner of East

with charred stake with pits & copper instructions

4225 Leave field bears N & S

8000 The corner traces 15:16, 21 & 22

+
200

Land rolling

Soil 1st rate

& Cottonwood Linch on the creek
banks

October 21st 1864

251

57

Township 1 North Range
North between Secs 15 & 16

chains Va. 20° E.

4000 Set post for 1/4 Sec corner in Monna of East
with Charney state pits & Casper instructions

8000 Set post for corner trees 9, 10, 15 & 16 in
Monna of East with Charney state pits
& Casper instructions

Ground gently rolling
Soil 2nd rate

Easterna remon line between Secs 10 & 15-

4000 Set post for temporary 1/4 Sec corner

7976 Intersect N & S Line 6 & N & W

corner trees 10, 11, 14 & 15 from which I run

N 89° 31' W on a true line between Secs 10 & 15-

1890 Road bears N & S

3988 Set Stone 16 x 10 x 8 for 1/4 Sec corner
Sec corner hill

3500 Foot of hill

5700 Birch Creek 10 1/2 miles runs N W

7725 Road bears N W & S E

7976 The corner trees 9, 10, 15 & 16

Ground rolling

Soil 1st rate

Cottonwood timber on land

- 32 East Willamette Meridian
North between Secs 9 & 10
chains $\text{true } 19\frac{1}{2}^{\circ} \text{ E.}$
- 8000 Run bears N W & S E
- 4000 Set post for $\frac{1}{4}$ sec. cor. from which
 @ Balm 14 in diam bears S 70° E 25 - Modist
 @ " 14 " " " S 40° W 115 " "
- 4500 Bush creek & Meridian runs N W
- 8000 Set post for corner to Secs 3, 4, 9 & 10 in
 Monney of Earth with charred stake pits &c
 as per instructions
 Same level. Soil $1\frac{1}{2}$ rate
-

- East on a rancon line between Secs 3 & 10
- 4000 Set post for temporary $\frac{1}{4}$ sec. corner
- 7980 Intersect N & S Line 70 Ws North of corner
 to Secs 2, 3, 10 & 11 from which I run
 N $89^{\circ}30'$ W. on a true line between Secs 3 & 10
- 3990 Set post for $\frac{1}{4}$ sec corner in Monney of
 Earth with charred stake pits &c
 as per instructions
- 4500 Run bears N E & S W across hill
- 7980 The corner to Secs 3, 4, 9 & 10 300
 Same hill
 Soil good 2 $\frac{1}{2}$ rate

Township 1 North Range

North on a bearing line between Secs 3 & 4
chains Va. 1930 E.

4000 Set post for temporary $\frac{1}{4}$ Sec corner
8000 Enter at North boundary at corner
Tasies 3 & 4 from which I run
South between Secs 3 & 4 on true line

75 Road bears N W & S E

3250 Road bears E & W

4000 Set stone 14 x 12 x 6 for $\frac{1}{4}$ Sec cor.
descend hill

6000 Foot of hill

300

300

7750 Enter bush bears N W & S E

7850 Go on Birch creek

8000 The corner to Secs 3, 4, 9 & 10

Same hill

Soil 1 $\frac{1}{2}$ feet

32 East Willamette Meridian

North between Secs 32 & 33

chains

4000 Set post for $\frac{1}{4}$ Sec cor. in Monna of Earth
with Charred Stake pits & as per instructions

8000 Set Stone 18 X 15 X 5 for corner to Secs 28, 29,
32 & 33.

Level Level Soil 1 $\frac{1}{2}$ rate

Eastern a parallel line between Secs 28 & 33

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8000 Intersect N & S Line at corner to Secs
27, 28, 33 & 34 from which corner from

Western true line between Secs 28 & 33

4000 Set post for $\frac{1}{4}$ Sec corner in Monna of Earth
with Charred Stake pits & as per instructions

8000 The corner to Secs 28, 29, 32 & 33

Level gently rolling
Soil 2 $\frac{1}{2}$ rate

Township 1 North Range
North between Secs 28 & 29

chains $\text{Bearing } 19\frac{1}{2}^{\circ}\text{E.}$

4000 Set stone 16 X 10 X 10 for $\frac{1}{4}$ Sec corner

8000 Set post for corner traces 20, 21, 28 & 29
in manner of Eutter with chains & stake
pits & as per instructions
Gena rolling. Soil 2⁰⁰⁰ sets

25

Easton line between Secs 21 & 28

4000 Set temporary $\frac{1}{4}$ Sec corner

18000 The corner traces 21, 22, 27 & 28 from
which I run

West on a true line between Secs 21 & 28

4000 Set stone 18 X 12 X 6 in for $\frac{1}{4}$ Sec. cor.

5800 Spring 650 W of South

8000 The corner traces 20, 21, 28 & 29

Gena rolling
Soil 1⁰⁰⁰ sets

32 East Willamette Meridian
North between Secs 20 & 21

Chains per 19 $\frac{1}{2}$ E.

4000 Set stone 20x15x6 for $\frac{1}{4}$ sec corner

8000 Set post for corner traces 16, 17, 20 & 21 in corner
of East with chains stake pits & Casper instructions
Genea Kelly. Soil good 30% rate

East on a random line between Secs 21 & 16

4000 Set post for temporary $\frac{1}{4}$ sec. cor.

8000 Intersect N & S Line at corner traces
16, 16, 21 & 22 from which corner I run

West on a true line between Secs 16 & 21

4000 Set post for $\frac{1}{4}$ sec. cor. in corner of
East with chains stake pits & Casper
instructions.

7825 Spring 25th N of Line

8000 ~~Set~~ corner traces 16, 17, 30 & 21

Genea gently polling

Soil 20% rate

October 22nd 1864

257

57

Township 1 North Range
North between Secs 16 & 17

chains (ve. 19 1/2 E.

4000 Set post for 1/4 Sec corner in Monney
Earth with charred stake pits & Casper instructions

8000 Set post for corner traces 8, 9, 16 & 17
in Monney of Earth with charred stake
pits & Casper instructions
Luna gently rolling
Soil good 2 ~~over~~ ^{over} feet

East on a permanent line between Secs 9 & 16

4000 Set temporary 1/4 Sec corner

8000 Intersect N & S Line at corner traces

9, 10, 15 & 16 from which I run

West on a true line between Secs 9 & 16

4000 Set post for 1/4 Sec corner in Monney

Earth with charred stake pits

& Casper instructions

8000 The corner traces 8, 9, 16 & 17

Luna rolling

Soil good 2 ~~over~~ ^{over} feet

32 East Willamette Meridian

North between Secs 8 & 9

chains via 19 1/2 E

4000 Set stone 15x8x6 for 1/4 Sec corner

8000 Set stone 22x15x4 for corner to sec

4, 5, 8, 9

Levee rolling Soil 2nd rate

East on a survey line between Secs 4 & 9

4000 Set post for temporary 1/4 Sec corner

8000 Intersect N & S Line at corner to sec

3, 4, 9 & 10 from which corner is run

West on a true line between Secs 4 & 9

1000 Birch creek 1000 ft wide runs NE

1400 Run across N & S

4000 Set post for 1/4 Sec cor. in corner

of Earth with charred stake pits & iron

& copper instructions

8000 The corner to sec 4, 5, 8 & 9

Levee rolling

Soil 1st rate

259

3-9

Township 1 North Range
North on a resection line between Secs 485-
va 19 1/2 E

4000 Set post for temporary 1/4 Sec corner

8054 Intersect North boundary 31 Ws West
of corner to Secs 485 from which I run
S 0° 13' W. on a true line between Secs 485-

4054 Set stone 20 x 8 x 8 for 1/4 Sec. cor.

6406 Road bears E & W

8054 The corner to Secs 451-889

Land rolling

Soil 2nd rate

Fine Grass hills

32 East Willamette Meridian

line North between Secs 31 & 32

4000 Set post for $\frac{1}{4}$ Sec cor. in Monong Earth
with Charred Stake pits & as per instructions

8000 Set Stone 20x12x8 for corner to Secs 29, 30,

31 & 32

Land gently rolling
Soil 2nd rate

East on a true line between Secs 29 & 32

4000 Set post for temporary $\frac{1}{4}$ Sec cor.

8000 Intersect N & S Line at corner to Secs
28, 29, 32 & 33 from which corner I run

West on a true line between Secs 29 & 32

4000 Set post for $\frac{1}{4}$ Sec corner in Monong Earth
with Charred Stake pits & as per
80.00 instructions

8000 The corner to Secs 29, 30, 31 & 32

Land rolling
Soil 1st rate

Township 1 North Range 31
 West on a corner line between Secs 30 & 31
 4000 Set post for temporary 1/4 Sec. cor.
 88.26 Intersect West boundary 84160
 South of corner to Secs 30 & 31
 from which corner I run
 S 89° 24' E. on a true line between Secs 30 & 31
 48.26 Set stone 18x12x10 for 1/4 Sec. cor.
 88.26 (The corner to Secs 29, 30, 31 & 32)
 Land gently rolling
 Soil good 2nd rate

North between Secs 29 & 30
 Sec. 19.30' E.
 4000 Set post for 1/4 Sec. cor. in mound of earth
 with charred stake pit as per
 instructions
 8000 Set stone 18x8x8 for corner to Secs
 19, 20, 29 & 30
 Land rolling
 Soil good 2nd rate
 October 23rd 1864

32 East Willamette Meridian
 East on a random line between Secs 20 & 29
 chains 4000 Set post for temporary $\frac{1}{4}$ Sec. cor.
 7990 Intersect N. & S Line at corner Secs
 20, 21, 28 & 29 from which corner I run
 West on a true line between Secs 20 & 29
 3995 Set Stone 16x8x6 for $\frac{1}{4}$ Sec. cor.
 7990 The corner to Secs 19, 20, 29 & 30
 Land rolling.
 Soil 2 ^{or} 4 rate. Thin. Grap

West on a random line between Secs 19 & 30
 4000 Set post for temporary $\frac{1}{4}$ Sec corner
 8830 Intersect West boundary 5000 S South
 of corner to Secs 19 & 30 from which I run
 S 89° 39' E. on a true line between Secs 19 & 30
 4830 Set Stone 24x14x12 for $\frac{1}{4}$ Sec corner
 8830 The corner to Secs 19, 20, 29 & 30
 Land rolling
 Soil 2 ^{or} 4 rate

263

63

Township 1 North Range
North between Secs 19 & 20

Chains per. 20° E.

4000 Set post for $\frac{1}{4}$ Sec. cor. in Monong
Earth with Charney Stake pits & as per instructions

8000 Set stone 18x12x8 for corner to Secs 17, 18,
19 & 20

Land gently rolling
Soil 2 or 3 feet

Eastern a common line between Secs 17 & 20

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8000 Intersets N & S Line 7000s north corner
to Secs 16, 17, 20 & 21 from which I run

N 89° 30' W. on a true line between Secs 17 & 20

4000 Set post for $\frac{1}{4}$ Sec cor. in Monong North
with Charney Stake pits & as per
instructions

8000 The corner to Secs 17, 18, 19 & 20

Land rolling
Soil 2 or 3 feet

32 East Willamette Meridian

West on a true line between Secs 18 & 19

4000

Set post for temporary $\frac{1}{4}$ sec corner

88.34 Intersect West boundary 8000 South of
corner to Secs 18 & 19 from which corner run
S $89^{\circ}26'$ E. on a true line between Secs 18 & 19

48.34 Set post for $\frac{1}{4}$ sec corner in manner of East
with Charney Stake pits & as per instructions

88.34 The corner to Secs 17, 18, 19 & 20
Ground hilly. Soil 2nd rate

North between Secs 17 & 18

on 20th East

4000 Set post for $\frac{1}{4}$ sec. cor. in manner of East
with Charney Stake pits & as per
instructions

8000 Set post for corner to Secs 7, 8, 17 & 18
in manner of East with Charney Stake
pits & as per instructions
Large gently rolling
Soil 2nd rate

Township 1 North Range
 eastern boundary line between Secs 8 & 17

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.
 7980 Intersect N & S Line at corner to Secs
 8, 9, 16 & 17 from which corner from
 West on a true line between Secs 8 & 17

3990 Set stone 18x8x8 for $\frac{1}{4}$ Sec. cor.
 7980 The corner to Secs 7, 8, 17 & 18
 Land gently rolling
 Soil 2 ~~over~~ rate

West on a random line between Secs 7 & 18
 4000 Set post for temporary $\frac{1}{4}$ Sec corner
 8840 Intersect West boundary 75-100 South of corner
 to Secs 7 & 18 from which corner from
 S 89° 28' E on a true line between Secs 7 & 18
 4840 Set stone 18x7x9 for $\frac{1}{4}$ Sec. cor.
 8840 The corner to Secs 7, 8, 17 & 18
 Land rolling
 Soil 2 ~~over~~ rate

32 East Willamette Meridian
 North between Secs 7 & 8
 chains (N. 20° E.)

4000 Set post for 1/4 Sec corner in Monna of Earth
 with Charms Stake pits & as per instructions

8000 Set post for corner to Secs 3:6:7 & 8 in Monna
 of Earth with Charms Stake pits & as per
 instructions

Land gently rolling
 Soil good 2nd rate

East on a previous line between Secs 5 & 8

4000 Set post for temporary 1/4 Sec. cor.

7978 Intersect N & S Line at corner to Secs
 4:5:8 & 9 from which comes True

Monna true line between Secs 5 & 8

3989 Set post for 1/4 Sec corner in Monna of Earth
 with Charms Stake pits & as per
 instructions

4978 The corner to Secs 3:6:7 & 8

Land gently rolling
 Soil 2nd rate

267

67

Township 1 North Range

Western boundary line between Secs 6 & 7

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8850 Intersect West boundary 70 W South
of corner to sec 6 & 7 from which I run

S 89° 30' East on a true line between Secs 6 & 7

4850 Set post for $\frac{1}{4}$ Sec. cor. in Monongia
with charred stake pits & as per instructions

8850 The corner to sec 5, 6, 7 & 8.

Land rolling

Soil 2 $\frac{1}{4}$ rate

North on a remainder line between Secs 5 & 6

wa. 19 $\frac{1}{2}$ E

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8040 Intersect North boundary at corner
to sec 5 & 6 from which corner I run

South on a true line between Secs 5 & 6

4040 Set post for $\frac{1}{4}$ Sec. cor. in Monongia
with charred stake pits & as per instructions

4380 ^{Road} Bears E & W

8040 The corner to sec 5, 6, 7 & 8

Land rolling

Soil 2 $\frac{1}{4}$ rate

October 24th 1864

32 East Willamette Meriemer

General Description

The Lema in this Township is either
 flat or good ~~low~~ level level or gently
 rolling and has a large amount of
 good farming land and is also
 well watered by numerous Springs and
 by Birch Creek which flows north
 through the Township it is
 however dry in many places at this
 season of the year but this is an
 unusually dry season in many
 seasons there is plenty of water in
 it

There is generally a heavy layer of
 bottom wood and Birch Yunk on the
 creek bottoms

There are at least 30 settlers
 in this Township

269

69

List of Names

A List of the names of the individuals employed by me to assist in running measuring and marking the lines and corners described in the foregoing field notes of Township No. 1 North of the base line of Range 32 East of the Willamette Meridian showing the respective Capacities in which they acted

David P. Thompson Carpenter
H. S. Dotson Chairman
George W. Newman "
A. McBlain Stenographer

270

We hereby certify⁷⁰ that we assisted
Daniel Chaplin deputy Surveyor in
subdividing Township No 1 North of the
base line of Range No 32 East of the Willamette
Meridian and that said Township has
been in all respects to the best of our
knowledge and belief well and faithfully
surveyed and the boundary monuments
planted according to the instructions
furnished by the Survey General

David P. Thompson Comptroller
J. S. Gotsom Chairman
G. W. Newman "
A. M. Cleon Assessor

Done and subscribed to before me
this 8th day of November 1864

J. P. Gilliland
Justice of the Peace
in Matilla County
Oregon

I, Daniel Chaplin Deputy
Surveyor do solemnly swear
that in pursuance of a
Contract with B. J. Pengra
Surveyor of the Public Lands
of the United States in Oregon
bearing date the 2nd day of
September 1864 I have well
faithfully and truly and in
my own proper person and
in strict conformity with
the instructions furnished
by the said Surveyor Gene-
ral the Surveying Manual
and the Laws of the United
States, surveyed all those
parts or portions of Township
No. 1 North Range No. 32 East
of the Willamett Meridian as
are represented in the foregoing

273
- my field notes as having
- been surveyed under my
- directions and I do further
- solemnly swear that all of
- the corners of said surveys
- have been established and
- perpetuated in strict accor-
- - ance with the surveying man-
- - ual and printed instructions
- and that the foregoing are
- the true and original field
- notes of such survey.

Daniel Choplin, Deputy Surveyor
- Sworn and subscribed to
- before me this 6 day of Decem-
- ber 1864

B D Reinhart
justice of the peace

Surveyor General's Office
Eugene City. Jan. 11th 1865

The foregoing field notes of the survey of
subdivisional lines in Tp. 1 North Range
32 E. Will. Mer. Ore. executed by
Daniel Chaplin, Deputy Surveyor, under
his contract No. 107 dated September
21st 1864, having been critically
examined, the necessary corrections and
explanations made, the said field
notes and the surveys they describe
are hereby approved.

J. J. Pennington
Sur. Gen. of Ore.