

Between Ranges 34 and 35, E T 1 N.

chs. North on East boundary of Sec. 12.
Var. 21° E.

1050 Mc Kay creek 20 lks flows S W 250 250

4000 Set post and raised stone mound
for 1/4 Sec. corner. 210 + 270

5550 Brook 8 lks wide, flows S E 400 400

8000 Set post and raised stone mound
for cor to Secs 1, 12, 6, 7. 50 + 50

Land mountainous, Soil 1st
rate, good grass, Pine & Fir
timber.

North on East boundary Sec. 1.
Var. 21° E.

4000 Set post and raised stone
mound for 1/4 Sec. cor.

5550 La Grande & Pundleton wagon
road, course N W + S E

8000 Set post for corner to Townships 1 & 2
North, Ranges 34 & 35, East, from which
Afr 10 in diam bears N 80° E - 10 lks
do do 8 " " " N 70° W - 12 do

Land mountainous, Soil 2d
rate, good grass, Pine & Fir timber

North Boundary T. 11. N R 34 East.

84

chs. West on random line on North
Boundaries of Secs 1, 2, 3, 4, 5, 6, 7.

Var. 20° E.

I set temporary half mile and
mile posts at every 40 and 80
chains, and at 5 miles 78 chains
and 5 olivets to a point 2
chains north of the corner of
Townships 1. 42 N R 33 & 34 East.

N $89^{\circ}46'$ East on true line on
North boundary of Sec. 6.

~~Var. $20^{\circ}30'$ East~~

38.50
Set Bassalt Stone 14 + 12 + 8 for $\frac{1}{4}$ Sec.

corner.

78.50
Set Bassalt Stone 18 + 14 + 12
for corner to Secs 5, 6, 31, 32.

Land Hilly. Soil 1st rate,
Good grass.

85 North Boundary, Twp. 1 N. R. 34. East.

cho. North 89°46' East on North
boundary of Sec. 5,
Var. 21° E.

4000 Set Bassalt Stone 14 + 12 + 8 for 1/4
Section Corner.

54,000 Brook, 4 lks wide, flows N. 70°

8000 Set Bassalt Stone, 16 + 14 + 10 for

Corner to Secs 4, 5, 32, 33

Land Hilly, Soil 1st rate, good
grass.

North 89°46' East on North
boundary Sec. 4,
Var. 21° East.

4000 Set Bassalt Stone 14 + 12 + 10 for
1/4 Sec. Corner.

76,000 Brook, 5 lks, flows N. 170°

8000 Set Bassalt Stone 14 + 14 + 14 for
corner to Secs 3, 4, 33, 34

Land Hilly, Soil 1st rate
good grass.

North Boundary, T/S. R. 34. East.

North 89°46' East on true line on
North boundary of Sec. 3.

Var. 21° East.

40.00

Set Basalt Stone 15 + 12 + 4 for 14

Sec. Corner

+
75

Set post and raised stone mound
for corner to Secs 2, 3, 34, 35

Land Heilly, Soil 1st rate, good
grass.

North 89°46' East on true line on
North boundary of Sec. 2.

Var. 21°30' E.

1.25

Brook 3 lbs, flows N,

40.00

Set post at 1/4 Sec corner
from which:-

A Fir 15 in diam bears N 38° W 138 lbs

do do 12 do do do S 50° E 100 lbs

80.00

Set post and raised stone mound
for cor. to Secs. 1, 2, 35, 36

Land Stony, some pine timber

87 North Boundary, T1N R 34, East,

chs. North $89^{\circ}46'$ East on true line
on North boundary of Sec. 1.

Var. $21^{\circ}30'$ East.

38.00 La Grande and Pendleton Wagon
road - corner N.W. & S.E.

40.00 Set post and raised stone mound
for $\frac{1}{4}$ Sec. corner.

80.00 To corner by Townships 1 & 2
North, Ranges 34 and 35
East, Willamette meridian.

Land Hilly, Soil 2^d rate,
some grass, Pine & Fir timber.

May, 8th 1871.

Platten

4
100

I, James F. Moody, deputy surveyor do solemnly swear that in pursuance of a Contract with W. H. Odell, Surveyor General of the public lands of the United States in the State of Oregon, bearing date 23 day of April 1871, and in strict conformity to the laws of the United States, and the instructions furnished by the said Surveyor General, I have faithfully surveyed the Eastern boundaries of Township 1 North of the Base line Range No. 34 East of the Willamette meridian, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

J. F. Moody
Deputy Surveyor.

Sworn and Subscribed before me

This 30th day of June 1871

M. Davenport

Commr of the U.S. Circuit Court

for the District of Oregon

I Genas F. Moody, having
 been appointed Deputy Surveyor, of the
 lands of the United States in Oregon,
 do solemnly swear that I will well
 and faithfully, and to the best of my
 skill and ability, execute the duties
 confided to me, pursuant to a con-
 tract with W. H. Odell, Surveyor
 General, of the public lands in Oregon,
 bearing date 23 day of April 1871,
 according to the laws of the United
 States and the instructions received
 from the said Surveyor General.

J. G. Moody

Sworn and Subscribed before me
 This 29th day of April 1871
 W. Davenport
 Coroner of the U.S. Circuit Court
 for the District of Oregon

I, M. A. Moody, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the pins upon uneven ground, and plumb the lally pins, whether by sticking or dropping the same; that I will report the true distance to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

M. A. Moody

Sworn and Subscribed before me }
 this 29th day of April 1871 }
 Wm. Davenport }
 Counselor of the U.S. Circuit Court }
 for the District of Oregon }

A. E. G. Condon, do solemnly swear
that I will well and truly perform the
duties of a seaman, according to
instructions given me, and to the
best of my skill and ability.

E. G. Condon

Sworn and Subscribed before me
This 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon

J. E. H. Henderson do solemnly ²⁹⁸
swear that I will faithfully execute
the duties of chain carrier; that I
will level the chain upon uneven
ground, and plumb the lally
pins, whether by striking or dropping
the same; that I will report the
true distance to all notable
objects, and the true length of all
lines that I assist in measuring,
to the best of my skill and
ability.

C. H. Henderson

Sworn and Subscribed before me
this 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon