

1270
Platte

Township 1 N R. 34 E

6	145	5	138	4	136	3	134	2	134	1
144		144		137		135		132		133
7	143	8	136	9	135	10	132	11		12
143		142		131		131				
18	142	17	130	16		15		14		13
141		141								
19	140	20	130	21		22		23		24
140		139								
30	139	29	129	28		27		26		25
128		129								
31		32		33		34		35		36

Pa
Coup Creek

6
128

See page 7 Van among on
North Random twice

Side

Moody
145

East on two lines on South
boundary of Sec. 30.

Var. 22° East

40.00

Set Bassalt Stone 14 + 14 + 12
for 1/4 Sec. corner

80.00

Set Bassalt Stone 18 + 18 + 10
for corner to Secs 29, 30, 31 + 32. 600

Land mountainous. Soil
2^d rate. Some grass. Pine timber
scattering.

T 1 N. R 34 East, Will. Mer.

129
chs.

East on true line on South
boundary of Section 29

Var. 21°30' East

4000

Set Bassalt Stone 14 + 10 + 10 for
1/4 Sec. corner

8000

Set Bassalt Stone 16 + 14 + 10 for
corner to Secs 28, 29, 32 + 33. c
stands in creek bottom

Land Mountainous, soil 2
rate, some grass, scattering
Pine and Fir timber.

North between Secs. 28 + 29

Var. 22° East

4000

Set Bassalt Stone 12 + 12 + 12
for 1/4 Sec. corner

8000

Set Bassalt Stone 17 + 14 + 9 for
corner to Secs 28, 29, 20 + 21

Land Mountainous, soil 2d
Good grass, some Pine and
Fir timber.

T. N. R. 34. East, Hill mer.

North between Secs 20 + 21
Var. 21°30' East

40.00 Set Bassalt stone, 14 + 14 + 7 for
1/4 Sec. corner.

80.00 Set post for corner to Secs 20, 21
+ 16 + 17 - from which:-

A Pine 30 in diam bears N 45° E 55 lbs
do do 36 do do do S 25° W. 40 "
Land Mountainous, soil 2^d
rate, Pine timber scattering,
Good grass.

North between Secs 16 + 17.
Var. 20° East.

40.00 Set Bassalt Stone 16 + 12 + 12 for
1/4 Sec. corner.

80.00 Set Bassalt stone 18 + 18 + 9 for corner
to Secs 16, 17, 8 + 9.

Land Mountainous, Soil 2^d
rate, Excellent grass.

T 1 N. R 34 E. Mill. Mer.

chs

East on true line on
South boundary of Sec. 9,
Var. 20° East.

10,000

Brook, 7 links wide, flows N. 75

4,000

Set Bassalt Stone 15 + 14 + 10 for

1/4 Sec. corner.

+100

+7
100

8,000

Set Bassalt Stone 18 + 12 + 10 for
corner to Secs 9, 10, 15, 16

Land Mountainous. Soil
2^d rate, Good grass, Pine and
Fir timber.

East on true line on South
boundary of Sec 10.

Var. 21° East.

5,100

Brook 10 links wide flows S.E. 75

4,000

Set Bassalt Stone 14 + 14 + 9

for 1/4 Sec corner

+240

+
240

8,000

Set Bassalt stone 18 + 18 + 7 for
corner to Secs 10, 11, 14, 15

Land Mountainous. Soil 2^d
rate, Good grass.

T. 1. N. R. 34. East. Hill mer.

132

North between Secs 10 + 11.

Var. 20°30' East.

4.00 Set Bassalt-stone 16+15+14 for 1/4
Sec corner.

8.00 Set post and skinned stone mound
for corner to Secs 2, 3, 10 + 11.

Land Mountainous. Soil 2^d rate

Good Grass. Some Pine and Fir.

May 9. 1871.

East on true line on South
boundary of Sec. 2.

Var. 21° East

4.00 Brook 4 lks, flows S. 70

4.00 Set post and made mound of
stone for 1/4 Sec. corner +
75

4.00 Brook 4 lks, flows S. 100

8.00 Set post and raised stone mound
for corner to Secs 1, 2, 11, 12. +
100

Land Mountainous. Soil 2^d

rate. Good grass. Some

Good Pine and Fir timber.

1193
T 1 N. R 34 E. Will Mrs.

chs.

East on random between
Secs 1+12.

Var 20° East.

4000 Set temporary 1/4 Sec. corner

7960 Intersect N+S line 35 lks S
of corner.

South 89°25' West on true line

3980 Set post and made mound
of stone for 1/4 Sec. corner.

7960 To Corner.

Land Mountainous. Soil
2^d rate. Excellent grass.

T 1 N R 34 E. Will. Mer.

184

chs

North on random bet Secs 1 + 2

Var. ~~19°30' East~~*

4000

Set temporary $\frac{1}{4}$ Sec. corner

8057

Intersected north boundary at cor.

South on true line.

4057

Set post and made stone mound for $\frac{1}{4}$ Sec. corner

8057

To corner.

Table land. Soil 2^d rate
good grass. Some pine timber

North on random between Secs 2 + 3

Var. ~~20° East~~*

4000

Set temporary $\frac{1}{4}$ Sec. corner

8050

Intersected north boundary 47 lks

East of corner.

S 00° 20' East on true

4050

Set Bassalt Stone 18 + 14 + 10 for $\frac{1}{4}$ Sec. corner.

8056

To corner

Land Hilly. Soil 2^d rate. Good grass some pine timber.

chs. North between Secs 9+10.
 550 Brook 14 lks flows E. 74
 4000 Set-Bassalt-Stone 18+14+4 for 1/4
 Sec. corner. +80 +80
 8000 Set-Bassalt-stone 20+16+10 for
 corner to Secs 9, 10, 3, 4
 Land Hilly, Soil 2^d rate
 Good grass. Pine timber.

East on random between
 Secs 3+10.

Var. 22° East,

4000 Set-temporary 1/4 Sec corner
 8000 Intersected E+5 line 10 lks
 South of cor.
 S 89° 56' N. on true line
 4000 Set-post and made Stone mound
 for 1/4 Sec. corner.
 8000 To corner.
 Land Hilly, Soil 2^d rate
 Good grass Pine timber.

T1N.R. 34 E. Mill. Meridian

136

chs North on random between Secs 3 & 4.
4000 Set temporary $\frac{1}{4}$ Sec. corner.

8048 Intersected North boundary 24 lks
East of corner

S $00^{\circ} 10'$ East on true line

4048 Set Basalt Stone $14 + 10 + 10$ for $\frac{1}{4}$
Sec. corner.

8048 To corner.

Land Heilly, Soil 2^d rate
Fine grass, some good timber.

North between Secs 8 & 9.

4000 Set Basalt Stone $14 + 14 + 8$ for
 $\frac{1}{4}$ Sec. corner

8000 Set Basalt Stone $18 + 14 + 8$ for
corner to Secs 8, 9, 4, 5

Land Heilly, Soil good 2^d
rate. Excellent quality of grass.
Some fine Pine & Fir timber.

T 1 N. R. 34. E. Mill. Meridian.

cho page East on random between Secs
4 + 9,

Variation, 20° East,

4000 Set temporary 14 Sec. corner

8004 Intersected N + S. line 14th to S.
of corner

S $89^{\circ}54'$ West on true line

4002 Sit Bassalt Stone 16 + 14 + 8 for
14 Sec. corner

8004 To corner

Land Heilly, Soil good
2^d rate. First rate

quality of grass. There
is no timber on this line.

T. N. R. 34. E. Will. Meridian

138

chs

North on random between
Sections 4 + 5.

40 50
2,000

Set temporary 1/4 Sec. corner

80 50
50

Intersected North Boundary

15 lbs East of corner

S 00° 6' E. on true line

40 50
50

Set Bassalt Stone 14 + 14 + 9 for

1/4 Sec corner

80 50
50

To corner.

Land Hilly. Soil good
2 d rate. Fine grass.

May 10th 1871.

T. 1 N. R. 34. E. Mill. Meridian.

189

chs. North, between Secs 29 & 30.

40.00 Set Bassalt Stone 18+14+8 for $\frac{1}{4}$

Section corner.

+350 +
350

80.00 Set Bassalt Stone 16+12+12 for corner
to sections 29, 30, 19 & 20.

+200 +
200

Land mountainous, soil 2^d rate
good grass.

East on random between
Secs 20 & 29.

Var. 20° E.

40.00 Set temporary $\frac{1}{4}$ Section corner

80.00 Intersected N+S. line 12 lks S. of
corner.

S. 89° 55' N. on true line

40.04 Set Bassalt Stone 18+10+10
for $\frac{1}{4}$ Section corner

80.08 To corner

Land mountainous, soil
2^d rate, Good grass.

T. N. R. 34. E. Mill. Meridian

140

chs

West on random between Sections
19 + 20.

40.00

Set temporary $\frac{1}{4}$ Section post

80.14

Intersected N. + S. line at corner

East on true line

40.14

Set Bassalt Stone 14 + 14 + 10 for
 $\frac{1}{4}$ Section post.

80.14

To corner

Land Kelly, Soil 2^d rate
Some good grass.

40.00

40.00

North between Secs 19 + 20.

Set Bassalt Stone 16 + 14 + 10 for
 $\frac{1}{4}$ Sec corner

80.00

Set post and made Stone
mound for corner to sections
17. 18. 19 + 20

Land Kelly, Soil 2^d rate
Good grass.

chs.

East on random between Secs 17 &
Var. 20°30'E.

4000 Set temporary 1/4 Sec. corner

8010 Intersected N+S line 12 S. of corner

4005 Set Bassalt stone 16+14+10 for 1/4 Sec. c

8010 To corner.

Land Hilly, Soil 2^d rate
Good grass. Some fine timber.

West on random between Secs 18 & 19

4000 Set temporary 1/4 Section corner

8020 Intersected N+S. line 15 lbs S of cor

S 89°54'E. on true line

4020 Set Bassalt-stone 16+12+10 for

1/4 Section corner.

8020 To corner

Land Hilly, Soil 2^d rate
Good grass. Some pine and
Fir timber.

T. N. R. 34 East, Mill. mer.

142

chs.

North between Secs 17. + 18.

40.00

Set post and made Stone
mound for $\frac{1}{4}$ Section corner

80.00

Set Basalt Stone 18 + 14 + 10 for
the cor to 70. 17 + 18.

Land Kelly. Soil 2^d rate

Good grass. Some pine timber.

May, 11th 1871.

East on random between Secs
8 + 7.

Var. 20° East.

40.00

Set temporary $\frac{1}{4}$ Sec. corner

70.00
80.00

Intersected N + S. line 20 kts S of cor.

S 89° 52' N. on true line

40.03

Set Basalt Stone, 14 + 14 + 12 for
 $\frac{1}{4}$ Section corner

80.06

Corner

Land Kelly. Soil 2^d rate

Good grass. Some Pine and
Fir timber.

T. N. R 34, E. Mill, Meridian

145
chs West on random between Secs 7 + 8
40.00 Set temporary 1/4 Sec. corner.

80.14 Intersected N. + S. line 10 lks N of cor.
N. 89° 56' E. on true line

40.14 Set Bassalt Stone 14 + 14 + 8 for
1/4 Section corner

80.14 To corner

Land Kelly, Soil 2^d rate
Good grass, Some Pine timber.

North between Secs 7 + 8.

2.00 Brook 4 lks wide, flows E. 70

40.00 Set Bassalt stone 17 + 14 + 12 for
1/4 Sec. corner 60

80.00 Set Bassalt Stone 18 + 14 + 4 for
corner to Secs 5, 6, 7, 8.

Land Kelly, Soil 2^d rate
Good grass, No timber on this
line.

T. 1. N. R. 34. E. Mill sur.

144

chs

East on random between Secs
5 + 8.

Var. 20° E.

40.00

Set Temporary $\frac{1}{4}$ Section corner.

80.08

Intersected N. + S. line 25 ft off cor

N $89^{\circ}50'$ W. on true line.

40.04

Set Basalt Stone 14 + 14 + 9 for

$\frac{1}{4}$ Sec. corner.

80.08

To corner

Land Kelly, Soil 2^d rate
Good Grass.

West on random between Secs 6 + 7

40.00

Set temporary $\frac{1}{4}$ Sec. corner

80.10

Intersected N. + S. line 12 lbs S of cor.

S $89^{\circ}55'$ E. on true line

40.70

Set Basalt Stone 14 + 14 + 8 for $\frac{1}{4}$ S. corner

80.10

To corner

Land Kelly, Soil 2^d rate. Good
grass.

145
T. N. R. 34 E. Hill mer.

chs.

North on random between Secs
5 + 6.

4000 Set Temporary $\frac{1}{4}$ Sec. corner
80.54. Intersected north Boundary
10 lbs East of corner

4054 Set Bassalt Stone 14 + 12 + 10
for $\frac{1}{4}$ section corner

8034 To corner.

Land Hilley. Soil 2^d
rate. Good grass
May 12th 1871

Surveyor General's Office
 Eugene Oct 11th 1871

The foregoing field notes of the survey of the Subdivisional lines of S. N. P 34 & Mill River Oregon executed by G. F. Moody deputy Surveyor under his contract, bearing date April 23^d 1871 having been critically examined and the necessary explanations and corrections made the said field notes and the surveys they describe are hereby approved.

W. H. Odell
 Surveyor