

FIELD NOTES

859

Of the survey of the Subdivisional

Lines of Lower & Fourth Range

N. 25° East of, Willamette Meridian,

Oregon, as surveyed by Rufus S Moore

U. S. Deputy Surveyor, under his Contract No. 451

dated June ~~28~~ 12<sup>th</sup>, 1882

Survey commenced, October 1<sup>st</sup> 1882

Survey completed, October 4<sup>th</sup> 1882

NAMES AND DUTIES OF ASSISTANTS.

Rufus S Moore, Compassman.

James Cuttridg, Chainman.

John Cuttridg, Chainman.

\_\_\_\_\_, Chainman.

\_\_\_\_\_, Chainman.

Joe Parvelli, Axeman.

\_\_\_\_\_, Axeman.

\_\_\_\_\_, Flagman.



859A

PRELIMINARY OATHS OF ASSISTANTS:

We, James Guttridge and  
John Guttridge

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivisional lines of  
Town 1 South Range N<sup>o</sup> 35 East  
James Guttridge Willamette Meridian, Oregon.

John Guttridge, Chainman.

\_\_\_\_\_, Chainman.

\_\_\_\_\_, Chainman.

\_\_\_\_\_, Chainman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore  
Notary Public

We, J. Joe Parodi and

\_\_\_\_\_, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability,

in the survey of the Subdivisional lines of Town  
1 South Range 35 East of Willamette Meridian, Oregon.

Joe Parodi, Axeman.

\_\_\_\_\_, Axeman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore  
Notary Public



# INDEX.

Referring the Lines to the Pages of the field Notes.

T. *1 South* R. *35 East* Will. Mer.

6	5	4	3	2	13	1
				11		9
7	8	9	10	11	7	12
				3		5
18	17	16	55	15	36	14
			59	57		39
19	20	21	60	22	41	23
			63	61		44
30	29	28	65	27	46	26
			69	67		49
31	32	33	70	34	52	35
						32
						36

Reserve from 20 in p

Meanders of ----- Pages ----- to -----

Meanders of ----- Pages ----- to -----



Subdivision of T. 7 South R. 35 East 861

Willamette Meridian, Oregon.

Preliminary to commencing this Survey I ran West on a blank line on the Base Line on the North boundary of sec. 1, and at 40.00 chs. I found the  $\frac{1}{4}$  sec. cor. and at 80.25 the Sec. cor.

Thence I ran West on North boundary of Sec 2 at 40.85 I found the  $\frac{1}{4}$  sec. cor. and at 81.70 I found the Sec cor.

Thence I ran South on old line between Secs. 2 & 3 and at 39.95 I found the  $\frac{1}{4}$  sec. cor. and at 79.94 I found the Sec. cor.

The chaining therefor is long on the Base Line, and chaining on subdivision practically agrees and the Compass will run the same line

Survey commenced October 7<sup>th</sup> 1882 with a Berts Solar Compass  
As Secs. 3 and 10 have been



Subdivision of T. 1 North R. 35 East  
Willamette Meridian, Oregon.

A pine 24 ins. dia. bears S 45° E 26 lbs. dist.  
marked, T 1 S R 35 E S 11 B F.

Then a Iron

S 89° 51' E on true line bet. Secs. 2 & 11 <sup>with same bar</sup>

39,96 Set a post 3 ft. long 3 ins. sq. 24 ins. in  
ground for 1/4 sec. cor. marked 1/4 S.  
on W. face, from which

A pine 26 ins. dia. bears N 46° E 22 lbs.  
dist. marked 1/4 S B F

A pine 30 ins. dia. bears S 60° E 14 lbs.  
dist. marked 1/4 S B F

79,92 The cor. to sec. 1, 2, 11 & 12

Land high, mountainous &  
rolling, soil 2" rate

Heavily timbered, with pine, fir  
tamarack and spruce 74,92 cor.

~~and dense undergrowth of same~~ <sup>pine, fir</sup>  
tamarack & spruce,

North between Secs. 1 & 2

Ta. 20° East

2,00 Small dry gulch course NW



Subdivision of T. 1 South R. 35 East  
Willamette Meridian, Oregon.

40.00 Set a post 3 ft. long 3 ins. sq. 24 ins  
in ground for  $\frac{1}{4}$  sec. cor. 100 ft.  
below last Sec. Cor. marked  $\frac{1}{4}$  D.  
on W. face. from which

A tamarack 9 ins. in dia. bears S 66° E 24 lbs.  
dist. marked  $\frac{1}{4}$  D B J

A fir 7 ins. in dia. bears N 55° W 20 lbs.  
dist. marked  $\frac{1}{4}$  D B J

41.45 Dry gulch course West

52.30 " " " West

69.00 Enter Opening bears NW & SE

75.00 Leave Opening bears NW & SE & enter  
timber

79.88 Intersect Base Line 149 lbs. West of  
cor to sec. 35 & 36. Old post has  
been obliterated, but witness trees are  
still standing. I set a new post  
 $4\frac{1}{2}$  ft. long 4 ins sq. for cor to  
Sec. 35 & 36. marked B.L.

T. 1 N R 35 E on N

S 36 on E & D 35 on W. face.  
with 1 notch on E & 5 notches on



Subdivision of T. 7 South R. 35 East  
Willamette Meridian, Oregon.

W face, from which

A Tamarack 12 ins. in dia. bears S 25° W 18 lks.  
dist. marked J 1 D R 35 E B J

A pine 12 ins. in dia. bears N 50° W 36 lks.  
dist. marked, J 1 N R 35 E D 35 B J

A Tamarack 12 ins. in dia. bears N 60° E 7 lks.  
dist. marked, J 1 N R 35 E D 36 B J

Set a post 4 1/2 ft. long 4 ins sq. 24 ins. in  
ground for closing cor. to Dec.  
1 & 2, marked C. C. on D.

J 1 D R 35 E D 1 on E

J 1 D R 35 E D 2 on W. face, with  
1 notch on E and 5 notches on W. edge.  
150 ft above 1/4 Dec cor.

from which

A fir 22 ins. in dia. bears N 46° E 45 lks. dist  
marked C. C. J 1 N R 35 E D 35 B J

A pine 20 ins. in dia. bears S 34° W 29 lks.  
dist. marked, C. C. J 1 D R 35 E D 2 B J

A pine 18 ins. in dia. bears S 72° E 20 lks.  
dist. marked, C. C. J 1 D R 35 E D 1 B J

Land high and mountainous



FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Rufus S Moore, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the Subdivisional lines of Town 1 South Range 35 East of Willamette Meridian, Oregon, showing the respective capacities in which they acted :

- James Guttridge, Compassman.
John Guttridge, Chainman.
Joe Parodi, Axeman.
Chainman.
Chainman.
Axeman.
Axeman.
Flagman.

FINAL OATHS OF ASSISTANTS

We hereby certify that we assisted Rufus D. Moore, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivisional lines Town 1 South of Range No. 35 East of the Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction ; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- James Guttridge, Compassman.
John Guttridge, Chainman.
Chainman.
Chainman.
Chainman.
Joe Parodi, Axeman.
Axeman.
Flagman.

Subscribed and sworn to before me, this Twenty First day of November 1882

[SEAL.]

Rufus D. Moore
Notary Public



## FINAL OATH OF DEPUTY SURVEYOR.

I, Rufus S. Moore

United States Deputy Surveyor, do solemnly swear that in pursuance of in-

structions received from

James C. Johnson

U. S. Surveyor General for Oregon, bearing date of the

Twelfth  
~~Twenty Eighth~~

day of

June

, 1882, I have well, faith-

fully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all those

parts or portions of

The Subdivisional lines of

Township 1 South - Range 35 East of

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual; printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the *true* field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

Rufus S. Moore  
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this

10<sup>th</sup>

day of

February

1883

Benjford Robb  
Notary Public



**Office U. S. Surveyor General,**Portland, Oregon, *June 5,* 188*3.*

The following Field Notes of the Survey of the

*Subdivisions of Township*  
*1 South Range 35 East,*  
*Will. Mer., Oregon*  
executed by *Rufus S. Moore*

under his Contract No. *457*, dated *June*  
*12<sup>th</sup>* 188*2*, having been critically examined, the

necessary corrections and explanations made, the said field notes  
and the survey they describe, are hereby approved.

*James C. Tolman*  
Surveyor General.

