

FIELD NOTES

Of the Subdivisional Lines of

T. 3 South R. 47 East and
1 North 4 35 5
8 South 3 38 East
 Willamette Meridian, Oregon,

BY

Marius Buchanan

Deputy Surveyor.

UNDER

his Contract No. 635 dated April 19, 1895

Survey commenced May 24, 1896

Survey completed May, 1896

Platted _____

Copied for Washington _____

FIELD NOTES

177

supplemental
Of the survey of the subdivisional
Lines of T. 3 S. R. 47 E., T. 8 S. R. 38 E
and T. 1 N. R. 35 E Willamette Meridian, Oregon,
as surveyed by Marius Buchanan

U. S. Deputy Surveyor, under his Contract No. 635
dated April 19th, 1896



Survey commenced, May 24th, 1896

Survey completed, June 4th, 1896

NAMES AND DUTIES OF ASSISTANTS.

Walter G. Beith, Chainman.

Guy S. Stryker, Chainman.

_____, Chainman.

_____, Chainman.

_____, Axman.

_____, Axman.

_____, Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

1st We, *Walter G. Beith and Guy Z. Snyker*

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey of the

Subdivisional

lines of *T. 38. R. 47 E., T. 38. R. 38 E. T. 35. R. 35 E.* Willamette Meridian, Oregon.

Walter G. Beith, Chainman.

Guy Z. Snyker, Chainman.

_____, Chainman.

Subscribed and sworn to before me this *twenty third* day of *May* 189*9*

[SEAL.]

Marius Buchanan
U. S. Dept. Surveyor

We, _____ and _____

_____, do solemnly swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Willamette Meridan, Oregon.

_____, Axman.

_____, Axman.

Subscribed and sworn to before me this _____ day of _____, 189____

[SEAL.]

Subdivisions of T. A. R. 35 C.

Ans. As instructed I re-examine the line bet. secs. 34 and 35 and find it correct in alignment and measurement. Therefore from Cor. of secs. 26, 27, 34 and 35.

Thence I run West bet. secs. 27 and 34 descending gradually, through scattering timber & intersect U. S. R. Bdy. line 40 lks. S. ^{20° W} of closing cor. to fractional secs. 27 and 34 heretofore described. Being out of limits I set a basalt stone, 19 x 11 x 8 ins., 15 ins. in the ground for closing corner to fractional sec. 27 and 34, marked C. C. on the O; with one groove on S. and 5 on N. faces, raised a mound of stone, 2 ft. base, 1 1/2 ft. high on E. Pit is unpracticable.

For reestablishment of this corner see Book B. page 7. of supplement to atlas

772

1694

Subdivisions of T. 1 N. R. 35 E.

Ths.

Sec. 1

I go to cor. of secs. 1, 12, 6 and 7 on the E. Bdy. of the T. heretofore described;

Thence I run N. on E. Bdy. Sec. 1

40-
78.53

along high ridge - no timber
could find no corner.

Wa. 18°-30' E.

Intersect N. Bdy of T. 3 Ths. W. of cor. of T. 1 and 2 N. R. 35 and 36 E., which is a post marked and witnessed, as described by the Surveyor General.

From the Cor. above described,

I run S. 89°-48' W for the fractional sec. Cor. on the N. Bdy. of sec. 1 on the U. S. R. Bdy. which being in sight over high rolling prairie -

26.00 Intersect the U. S. R. Bdy. at the ^{closing} ~~fractional~~ ~~sec.~~ core which is a basalt stone in a mound of stone.

May 29th 1896

Marius Buchanan
U. S. Dept. Surveyor.

Office of U. S. Surveyor-General,

PORTLAND, OREG., *November 28,* 1896.

The ~~following~~ ^{foregoing} field notes of the ^{supplemental} survey of the

Subdivisional lines of Township
1. North Range 35 East
Willamette Meridian Oregon

executed by *Marius Buchanan*
U. S. Deputy Surveyor
under his contract No. *635*, dated *April*

19th, 189*5*, having been critically examined,
and the necessary corrections and explanations made, the said field
notes and the surveys they describe, are hereby approved.

Robert A. Habusham

U. S. Surveyor-General.