

81 Between Ranges 34 and 35 East. T 1 N.

- ds. Begin at the South East corner
of Township 1st. Range 34 East,
on Base Line. I run,
- North on East boundary of Sec. 36
var. $21^{\circ} E$
- 40.00 Set Bassalt Stone, 18+14+12 for
 $\frac{1}{4}$ Sec. corner.
- 63.00 Mc Kay creek, 14 lks wide. flows
West. $35^{\circ} 350$
- 80.00 Set Bassalt Stone 16+14+14 for
corner to Sections 25, 36, 30, 31, 4000
Land mountainous. Soil 2^d
rate, some grass. Good Pine
and Fir timber
- North on East boundary Sec. 25
Var. $20^{\circ} E$.
- 40.00 Set post for $\frac{1}{4}$ Sec. corner
from which:-
A pine 36 in diam bears N $82^{\circ} E$ both
- 80.00 Set Bassalt Stone 14+14+12 for corner
to Secs 24, 25, 19, 30.
- Land mountainous. Soil 2^d rate
some grass. Pine timber.

Between Ranges 34 & 35 East. T. N.

82

North on East boundary Sec. 24
Variation 20°30' E.

11.00 Brook 5 lks wide, flows E

40.00 Set post and raised stone mound
for 1/4 Sec. corner

44.75 Brook, 8 lks wide, flows East 25°

80.00 Set Bassalt Stone 18+14+12 for
corner to Sections 13, 24, 18, 19.

Land mountainous. Soil 2^d rate
good grass. Pine and Fir timber.

May. 6, 1871

North on East boundary of Sec. 13.

Vat. 20°30' E

40.00 Set post for 1/4 Sec. corner from which
A Fir 14 in diam bears N 60° W. 25 lks

44.50 To Spring of good water.

80.00 Set post for corner to Secs 12, 13, 7, 18
from which:-

A Fir 10 in diam bears N 50° W. 20 lks
do do do do do do S 39° E 16 lks

Table land. Soil 1st rate, good grass
Pine & Fir timber.

83 Between Ranges 34 and 35, E T 1 N.

ch. North on East boundary of Sec. 12.
Var. 21° E.
1050 Mc Kay creek 20 lks flows S W 25° 250
Set post and raised stone mound
for $\frac{1}{4}$ Sec. corner. $\frac{5}{10}$ +
55.50 Brook 8 lks wide, flows S E 400
Set post and raised stone mound
for cor to Secs 1, 12, 6, 7. 50 +
80.00 Land mountainous, Soil 1st
rate, good grass. Pine & Fir
timber.

North on East boundary Sec. 12
Var. 21° E.

4000 Set post and raised stone
mound for $\frac{1}{4}$ Sec. cor.
55.50 LaGrande & Pendleton wagon
road, comes NW + S E
8000 Set post for come to Townships 1 & 2
North, Ranges 34 & 35, East, from which
A fri 10 in diam bears N 80° E - 10 lks
do do 8 " " " N 70° W - 12 da
Land mountainous, Soil 2d
rate, Good grass. Pine & Fir timber

I, Juras F. Moody, deputy surveyor¹⁰⁰ do
solemnly swear that in pursuance of a
Contract with W. H. Odell, Surveyor General
of the public lands of the United States in the
State of Oregon, bearing date 23 day of April
1871, and in strict conformity to the
laws of the United States, and the
instructions furnished by the said Surveyor
General, I have faithfully surveyed the
exterior boundaries of Township 1 North
of the Base line Range No. 34
East of the Willamette Meridian,
and do further solemnly swear that the
foregoing are the true and original field
notes of such survey.

J. F. Moody
Deputy Surveyor.

Searched and Subscribed before me }
This 30th day of June 1871 }
W. M. Davenport }
Comr of the U.S. Circuit Court }
for the District of Oregon }

I. Genas F. Moody, having
been appointed Deputy Surveyor, of the
lands of the United States in Oregon,
do solemnly swear that I will well
and faithfully, and to the best of my
skill and ability, execute the duties
confided to me, pursuant to a con-
tract with W. H. Odell, Surveyor
general, of the public lands in Oregon,
bearing date 23 day of April 1871,
according to the laws of the United
States and the instructions received
from the said Surveyor General.

J. G. Moody

I do subscribe before me

This 29th day of April 1871

M. Davenport

Clerk of the U.S. Circuit Court

for the District of Oregon

I, M. A. Moody, do solemnly
swear that I will faithfully execute
the duties of chain carrier; that I will
level the pins upon uneven ground,
and plumb the tally pins, whether by
sticking or dropping the same; that I
will report the true distance to all
notable objects, and the true length
of all lines that I assist in measuring,
to the best of my skill and ability.

M. A. Moody

Sown and Subscribed before me
this 29th day of April 1871

M. Davenport

Comr^r of the U.S. Circuit Court
for the District of Oregon

I, E. G. Condon, do solemnly swear
that I will well and truly perform the
duties of axeman, according to
instructions given me, and to the
best of my skill and ability.

E G Condon

Sworn and Subscribed before me }
This 29th day of April 1871 }
W. Davenport- }
Clerk of the U.S. Circuit Court }
for the District of Oregon }

I. E. H. Henderson do solemnly ^{legg 8}
swear that I will faithfully execute
the duties of chain carrier; that I
will level the chain upon uneven
ground, and plumb the tally
pins, whether by striking or dropping
the same; that I will report the
true distance to all notable
objects, and the true length of all
lines that I assist in measuring,
to the best of my skill and
ability

I. E. H. Henderson

Swear and Subscribed before me
this 29th day of April 1871 }
M. Davenport }
Comr of the U.S. Circuit Court
for the District of Oregon }