

FIELD NOTES

Y
of the survey of the Subdivisional
Lines of Township 1 North of
Range 38 East Willamette Meridian,
Oregon, as surveyed by John W Kimbrell
U. S. Deputy Surveyor, under his Contract No. 579
dated June 22nd 1891

Survey commenced, Aug. the 12 1891
Survey completed, Sept the 7 1891

NAMES AND DUTIES OF ASSISTANTS.

John W Kimbrell, Compassman.
John W Vaughn, Chainman.
Jessie O Cornelison, Chainman.
, Chainman.

, Chainman.

Henry W Edwards, Axeman.

Fredrick J Ott, Axeman.

Samuel Emerson, Flagman.

TA

PRELIMINARY OATHS OF ASSISTANTS.

We, Jesse D. Cornelison and
John W. Vaughn

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivisional

lines of Township
one North Range 38 East Willamette Meridian, Oregon

Jesse D. Cornelison, Chainman.

John W. Vaughn, Chainman.

, Chainman.

, Chainman.

Subscribed and sworn to before me, this Eleventh

day of

August 1891

C. D. Doweele
Notary Public for Oregon

[SEAL.]
We, Henry W. Edwards and

Frederick J. Ott, do solemnly swear

that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our

skill and ability, in the survey of the Subdivision lines of

Township one North Range 38 East Willamette Meridian, Oregon.

Henry W. Edwards, Axeman.

Frederick J. Ott, Axeman.

Subscribed and sworn to before me, this Eleventh

day of

August 1891

C. D. Doweele

[SEAL.]

Notary Public for Oregon

IB

INDEX

Referring the Lines to the Pages of the Field Notes.

T. 1 North R. 38 East Will. Mer.

6	66	5	65	4	71	3	74	2	78	I
63		61		48						
7	58	8	46	9		10		11		12
55		53		48						
18	51	17	40	16		15		14		13
37		36		15-24						
19	33	20	15	21	14	22		23		24
30	26	29	21	28		27		26		25
13		11								
31	9	32	3	33		34		35		36
8		5								

Meanders of Pages to

Meanders of Pages to

7

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

I go to the Standard corner to Sec's 31 and 36 on Base Lines which is also the Standard corner to T1N R6S
37 ad 38 E which is a Post 4 $\frac{1}{2}$ feet long 4 ins square 24 ins in the ground. Marked S C T1N on N
R 38 E S 31 on E and R 37 E S 36 on W faces with 6 notches on N E and W edges from which a Spruce 5 ins dia brs N 60° W 61 lbs dist. Marked T1N R6S 37 E S 36 B.T.
a Spruce 12 ins dia brs S 45° W 20 lbs dist. Marked S C T1N R 37 ad 38 E B.T.
No other tree within limits. The old Bearing Tree in Sec 31 has been destroyed by fire

Hence I run

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

West on random line
bet Sec 30 and 31

Var $20^{\circ} 31' 8''$

4000 Set Temporary 1/4 sec. cor.

7978 Intersect-West Boundary 33

llks North of the corner to Sec

25-30-31 and 36 which is a
Post 4 $\frac{1}{2}$ feet long 4 ins square

2 feet in the ground Marked

J/N S30 on N E

R38 E S31 on S E

R37 E S36 on S W

and S35 on N W faces with 1 notch
on S and 5 notches on N edges

from which

a fin 30 ins dia bes $N56^{\circ} 8' 180$ llks dist

Marked J/N R38 S30 B.T.

a fin 30 ins dia bes $S82^{\circ} 8' 104$ llks dist

Marked J/N R37 E S31 B.T.

Mound of stones 1 $\frac{1}{2}$ feet high 3 feet wide at base
along side

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

(8003 10 M.)

1000 ravine course N 7° E follow
down ravine

2000 leave ravine course S 15° E
enter dense alder underbrush
and heavy fir and hemlock
timber

4070 The $\frac{1}{4}$ sec cor bet Sec 20 and 29 700

4070 chs Mountainous

Dense under brush on first 20 chs
dense underbrush and heavily timbered
on last 20 chs

Aug 22 1891

Hence I run

S $89^{\circ} 46'$ W on true line level
bet Sec 19 and 30

Var 20° E.

ascend steep N & face of ridge

600 Old Indian Trail course NW 88° E

750 Top of ridge course S E 200

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

1500	ravine course South	X	175-
2000	ridge " "	X	300
2500	ravine " "	X	250
2800	Sprw " "	X	325-
4000	Set Post 3 feet long 3 ins Square 24 ins in the ground for 1/4 sec cor. Marked 1/4 S on N face from which	X	300
	a fir 20 ins dia frs N 24° W 65 lks dist-Marked 1/4 S B T		
	a fir 20 ins dia frs S 69° E 90 lks dist Marked 1/4 S B T,		
4300	ravine course S 10° E	X	250
4800	Point-of-ridge course South	X	350
5500	Spring branch 3 lks wide runs S 20° E		
5700	" " 4 " " " S 85° E		
	ascend steep N E face of heavily timbered mountain Fir and Tamarack timber Undergrowth some		

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

(8093-10 M.)

- 7913 Intersect West Boundary 700
 Set Post 4 $\frac{1}{2}$ feet long 4 ins square
 24 ins in the ground for corner to
 Sec 19-30-24 and 25- Marked
 J1N S19 on N E
 R688830 on S E
 R37E S25 on S W and
 S24 on NW faces with 4 notches
 on the N and 2 notches on S edges
 from which
 a post 18 ins dia brs N67° E 84 lks dist-
 Marked J1N R6888 S19 B.T.
 a post 12 ins dia brs S46° E 72 lks dist-
 Marked J1N R688830 B.T.
 a Jamrake 12 ins dia brs S25° W 4 lks dist-
 Marked J1N R637 E S25-B.T.
 a Jamrake 20 ins dia brs N3° W 77 lks
 dist- Marked J1N R637 E S24 B.T.
 7913 chs mountainous, timber
 Pine fir and Jamrake Under.

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

groth fir and alder. dense willow undergrowth in ravines.

Note. I determine the west Boundary, from a Point 4 chs North of of this corner, the top of a Spur course East, at which Point I find a due South line from Light Tree, a small Fir Blazed at North end of Triangulation. 4377 chains North of this Point on top of high ridge course E & W which is in plain sight. No other tree, ang the 22nd 1891

No 4½ W bet Sec 19 and 20 level

Var $19^{\circ} 57' E$

descend Steep N side of ridge

225 bottom of ravine course E

35-

1325 top of ridge course $875^{\circ} E$

* 150

1750 ravine course E

* 25-

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

(8093 - 10 M.)

- 4000 Set Temporary $\frac{1}{4}$ sec cor
 7785 Intersect West Boundary
 28 lks South of the corner to
 Sec 13-18-19 and 24 which
 is a Tumrock 5 ins dia marked
 JIN S 18 on NE
 N 38 E S 19 on S E
 R 37 S 24 on S W and
 S 18 on NW faces with 3
 notches on N and 3 notches on S
 edges. from which
 a Tumrock 6 ins dia has $875^{\circ}E$ $73^{\circ}N$ 22°
 dist. Marked JIN N 38 E S 19 B.S.
 a Tumrock 7 ins dia has $N 55^{\circ}E$ 20 lks
 dist. Marked JIN N 38 E S 18 B.S.
 a Tumrock 8 ins dia has $N 58^{\circ}W$ 22 lks
 dist. Marked JIN N 38 E S 18 B.S.
 a Tumrock 8 ins dia has $S 39^{\circ}W$ 30 lks
 dist. Marked JIN N 37 E S 24 B.S
 Then I run

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

65 chs Mountainous
Timber Pine Underbrush
Willow ass and Indian arrow
on creek bottom.

1580 across old burnout. rolling
Soil 3rd rate

Sept 1 1891

S $89^{\circ}58'$ W on random line
bet Sec 7 and 18

Var $20^{\circ}25' E$

4000 ft Temp 68° $\frac{1}{4}$ sec low

7720 ft intersect-West Boundary

31 lcs south of the corner

to Sec 7-12-18th ad 18

which is a Post 4 $\frac{1}{2}$ feet long

4 ins square 24 ins in the
ground Marked

TIN 87 on N E

R 88 S 818 on S E

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

(8093-10 M.)

R 37 E S 13 on SW
S 1/2 and NW faces with
4 notches on S and 2 notches
on N edges

from which

a fir 6 ins dia bes S $70^{\circ} 8' 18''$ E dist-
Marked J/N 888 S 18 B.T.

a fir 7 ins dia bes S $53^{\circ} W$ 9 ft dist-
Marked J/N 888 S 18 B.T.

a fir 7 ins dia bes N $69^{\circ} W$ 27 ft dist-
Marked J/N 888 S 12 B.T.

The bearing tree in Sec 7 has fallen
down and decays I mark
a fir 5 ins dia bes N $47^{\circ} 8' 18''$ E dist-
Marked J/N 888 S 87 B.T.

Then I run

S $89^{\circ} 49' 8''$ on True line level

bet Sec 7 and 18

var $20^{\circ} E$

gently ascending through dense

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

8075- The corner to Sec 5-6-7 and 8 280

8075 chs Mountainous and
heavily timbered

The first 53 chs well timbered
with Pine and fir Soil 2nd rate

The last 2775 chs Steep Stony
a few scattering Pine

Soil poor 4th rate

dense Underbrush Buck Brush and
fir on first 20 chains

Sept 3 1891

S $89^{\circ} 49' W$ on random
line bet Sec 6 and 7

Var $25^{\circ} 30' E$

4000 Let Temporary 1/4 Sec cor.

7950 Intersect West Boundary

3 lks south of The corner

To Sec 1-6-7 and 12

Which is a Post 4 1/2 feet long

Subdivision of T. 1 North R. 38 East

Willamette Meridian, Oregon.

(8093-10 M.)

4 ins Square 24 ins in the ground
Marked
TIN S 6 on NE
R 38 E S 7 on S E
R 37 E S 12 on SW and
S 1 on NW faces with 5 notches
on S and 1 notch on N Edge
from which

a Pine 36 ins dia bears N $27^{\circ} E$ 144 lls
dist - marked TIN 1638 E S 6 B T,
a fir 10 ins dia bears S $10^{\circ} E$ 98 lls dist -
marked TIN 1638 E S 7 B T.

Then I run

N $89^{\circ} 50' E$ on True line level
bet Sec 6 and 7

var $20^{\circ} S$

descend steep E face of mountain
dense alder underbrush and
heavy fir timber

3750 Set Post 3 feet long 3 ins square $\overline{350}$

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by John W. Kimball, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivisional lines of Township 1 North Range 38 East Willamette Meridian, Oregon, showing the respective capacities in which they acted:

John W. Kimball, Compassman.
John W. Vaughn, Chainman.
Jessie D. Cornelison, Chainman.
Henry W. Edwards, Chainman.
Fredrick J. Ott, Axeman.
Samuel F. Emmerson, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted John W. Kimball, U. S. Deputy Surveyor, in surveying all those parts or portions of the Township one North of Range Thiry-eight East Willamette Meridian, Oregon.

as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

John W. Kimball, Compassman.
John W. Vaughn, Chainman.
Jessie D. Cornelison, Chainman.
Henry W. Edwards, Chainman.
Fredrick J. Ott, Axeman.
Samuel F. Emmerson, Flagman.

Subscribed and sworn to before me, this 21st day of

September 1891
W. D. Duvivier
Notary Public for Oregon

[SEAL.]

FINAL OATH OF DEPUTY SURVEYOR.

I, John W Kimball

United States Deputy Surveyor, do solemnly swear that in pursuance of

instructions received from W. Henry Byars

U. S. Surveyor General for Oregon, bearing date of The 22nd

day of July 1891, I have well, faithfully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all those

parts or portions of Townships 1 North of
Range 38 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the *true* field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

John W Kimball
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this

21st

day of September 1891

John D. Dowee
Notary Public for Oregon

Notary Public
You can't swear me

FINAL OATH OF DEPUTY SURVEYOR.

I, John W. Kimball, United States Deputy Surveyor, do solemnly swear that in pursuance of instructions received from W. Henry Byars, U. S. Surveyor General for Oregon, bearing date of the 22

day of July 1891, I have well, faithfully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all those

parts or portions of Township one North of Range 38 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

John W. Kimball
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 31
day of October 1891.

W. M. Pierce
County Clerk
Umatilla Co.
Oregon

89

Office U. S. Surveyor General,

Portland, Oregon, November 24, 1891.

The foregoing Field Notes of the Survey of the
Subdivisional lines of Township No 1
North, Range No 38 East Willamette
Meridian Oregon
executed by John W. Kimbrell U.S. Dept Surv
under his contract No. 579 dated June
22, 1891, having been critically examined, the
necessary corrections and explanations made, the said Field
Notes and the survey they describe, are hereby approved.

Surveyor General.

Office U. S. Surveyor General,

Portland, Oregon, November 24 1891

The foregoing Field Notes of the Survey of the
Subdivisional lines of Township
No 1 North, Range 38 East Willamette
Meridian Oregon
executed by John H. Kimbrell
under his contract No. 579, dated June
22, 1891; having been critically examined, the
necessary corrections and explanations made, the said Field
Notes and the survey they describe, are hereby approved.

W. Henry Byars
Surveyor General.