

FIELD NOTES

Of the survey of the Subdivisional
 Lines of Township 2 South Range
34 East Willamette Meridian, Oregon,
 as surveyed by Jas. P. Currier & Jas. E. Roland
 U. S. Deputy Surveyor, under his Contract No. _____
 dated May 4th, 1887.

Survey commenced, July 16th, 1887
 Survey completed, July 21st, 1887

NAMES AND DUTIES OF ASSISTANTS.

L. F. Hooley, Compassman.
J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Belshaw, Chainman.
Guy Davis, Chainman.
B. B. Browner, Axman.
A. V. Veatch, Axman.
 _____, Flagman.

4 PRELIMINARY OATHS OF ASSISTANTS.

We, J. S. Medley, W. H. Medley
Frank Belshaw Guy Davis

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the Subdivisional lines of T 2 S, Range 34 E Willamette Meridian, Oregon.

J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Belshaw, Chainman.
Guy Davis, Chainman.

Subscribed and sworn to before me this 16th day of July, 1887

[SEAL.] James P. Plurrien
W. S. Deputy Surveyor

We, B. B. Crown and H. Beach

do solemnly swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Subdivisional lines of T 2 S, R 34 E Willamette Meridian, Oregon.

B. B. Crown, Axman.
H. Beach, Axman.

Subscribed and sworn to before me this 16th day of July, 1887

[SEAL.] James P. Plurrien
W. S. Deputy Surveyor

INDEX

411

Referring the Lines to the Pages of the Field Notes.

T. 2 South R. 34 East Will. Mer.

| | | | | | | | | | | |
|----|---------------|----|---------------|----|---------------|----|---------------|----|---|----|
| 6 | 65 | 5 | 43 | 4 | 28 | 3 | | 2 | | 1 |
| 64 | 65 | 62 | | 41 | | | | | | |
| 7 | 61 | 8 | 40 | 9 | 27 | 10 | | 11 | | 12 |
| 60 | | 58 | | 39 | 38 | | | | | |
| 18 | 57 | 17 | 38 | 16 | 25 | 15 | | 14 | | 13 |
| 55 | | 54 | 38 | 37 | | 24 | | | | |
| 19 | 53 | 20 | 35 | 21 | 22 | 22 | 74 | 23 | | 24 |
| 51 | 52 | 50 | 35 | 34 | | 21 | 74 | 13 | | 6 |
| 30 | 49 | 29 | 32 | 28 | 19 | 27 | 77 | 26 | 4 | 25 |
| 47 | 48 | 44 | | 29 | 19 | 16 | | 8 | | 3 |
| 31 | 46 | 32 | 31 | 33 | 18 | 34 | 10 | 35 | | 36 |

Meanders of _____, Pages _____ to _____

Meanders of _____, Pages _____ to _____

28

448

Subdivisions of T. 2 South R. 34 East
 Willamette Meridian, Oregon.

(8093-10 M.)

- North on true line bet. Secs 3 & 4
 Va. $17^{\circ} 30'$ East.
- 1950 Dry bed of creek at N. E. - 200
 Ascend
- 2835 Gulch S. E. - 100
- 40.00 Set Basalt Stone $7 \times 8 \times 12$ ins.
 8 ins. in the ground for $\frac{1}{4}$ Sec.
 Cor. marked $\frac{1}{4}$ on N. face
 Over which I raised a
 mound of stone 18 ins. high
 with $3\frac{1}{2}$ ft. base. On side of
 mountain
- 63.00 Summit of mountain N. E. 800 +
 Descend
- 78.50 Intersect Township line 3.79 chs.
 N. of Cor. to 33 & 34 T. 1 S. R. 34 E.
 And set a Basalt Stone $10 \times 12 \times 16$ ins.
 12 ins. in the ground for
 closing cor. to Secs. 3 & 4 marked
 C. C. with 3 notches on E & N. edges
 from which a line 30 ins.

Subdivisions of T. 2 South R. 34 East.

Willamette Meridian, Oregon.

| | | | |
|-------|--|---|------|
| | North on true line bet. Secs. 4 & 5 Wa 20° East. | | |
| 15.00 | Creek 10 kcs. wide N.E. | - | 1000 |
| | Ascend | | |
| 25.00 | Bluff of Rock | + | 100 |
| 40.00 | Set Stone 12 X 12 X 8 ins. 8 ins. in the ground for $\frac{3}{4}$ Sec. Cor. marked $\frac{3}{4}$ on N. face. Over which I raised a mound of stone 18 ins. high with 3 $\frac{1}{2}$ ft. base On East side of hill | + | 900 |
| 55.00 | Top of mountain Descend | + | 1000 |
| 70.00 | Canyon East | - | 600 |
| 78.00 | Intersect Township line 3.95 chs. N. of Cor. to Secs. 32 & 33 T. 1 S. R. 34 E. Set a post 4 ft. long $\frac{3}{4}$ in. square 24 ins in the ground for closing Cor. to Secs 4 & 5 marked T. 2 S. R. 34 E on S. | | |

44464

Subdivision of T. 2 South R. 34 East

Willamette Meridian, Oregon.

(8093-10 M.)

S. H. on E and

S. 5 on N. faces with
H notches on E. and 2 on W.

Edges from which

A fir 10 ins diam. bears S. 5° E

8 2 lks. dist marked S. 2. S. R. 34.

E. S. H. C. C. B. D.

A Tamarack 12 ins diam bears

S. 35° N. 80 lks. dist. marked

S. 2. S. R. 34. E. C. C. S. 5. B. D.

Land very rough ^{78.00 ch} and mountainous

Pine fir and Tamarack timber

Soil 3rd rate

Post on true line bet. Secs 29 + 32

Na. 18° 45' E.

40.00

Set post 3 ft. long + 4 ins. square

4 ins in the ground for 1/4 sec.

Cor. marked 1/4 S. on N. face

from which.

A Tamarack 10 ins diam. bears.

Subdivisions of T. 2 South R. 34 East
Willamette Meridian, Oregon.

For clearing loc. to Secs. 6 & 7
marked C. C. U. R. on E. face
with 5 notches on S. and 1 on
N. edges. Over which
I raised a mound
of stone 2 ft. high with
4½ ft. base

Land mountingy \$9.00 chs
Timber in leaves.

Some good bunch
grass.
Soil 4th rate and rocky.

North Bet. Secs. 5 and 6
Pa. 19° 30' East.

| | | |
|-------|---------------------------------|----|
| 8.10 | Trail on Summit N.E. + | 80 |
| 15.00 | Descend | |
| 28.00 | Head of Gulch N. - | 20 |
| 40.00 | Set a Basalt Stone 4x12x14 ins. | |

66

Subdivisions of T. 2 South R. 34 East
Willamette Meridian, Oregon.

(8093-10 M.)

8 ins in the ground
for $\frac{1}{4}$ Sec. $\frac{1}{4}$ marked
 $\frac{1}{4}$ D. on W. face - 400
Over which I raised
a mound of Stone
18 ins. high with $3\frac{1}{2}$ ft.
base

73.00
76.93

Rock Joint W. + 20
Intersect Township
line 355 chs. W. of cor.
to Secs. 31 & 32 T. 1. S. R. 34. E.
and set a Basalt Stone
8 x 10 x 16 ins. ^{10 ins} in the ground
for closing cor. to Secs.
5 & 6 marked C. C. on S.
face with 5 notches on
E. and 1 on W. edges - 400
from which I raised
A line 12 ins diam. by
S. 23° W. 25 chs. dist. marked
T. 2. S. R. 34 E. C. C. S. C. B. D.

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Jas. P. Currier
and Jas. E. Noland, U. S. Deputy Surveyor, to assist in
 running, measuring, and marking the lines and corners described in the
 foregoing field notes of the survey of the Subdivisional
 lines of Township 2 South
R. 34. East Willamette Meridian, Oregon,
 showing the respective capacities in which they acted:

- L. J. Wooley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Brewer , Axman.
- H. Beach , Axman.
- , Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted Jas. P. Currier and
Jas. E. Noland, U. S. Deputy Surveyor, in surveying
 all those parts or portions of the Subdivisional
Lines of Township 2
South Range 34 East Willamette Meridian, Oregon,
 as represented in the foregoing field notes as having been surveyed by
 him and under his direction; and that said survey has been in all respects,
 to the best of our knowledge and belief, well and faithfully surveyed,
 and the corner monuments established, according to the instructions
 furnished by the U. S. Surveyor General of Oregon.

- L. J. Wooley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Brewer , Axman.
- H. Beach , Axman.
- , Flagman.

Subscribed and sworn to before me this 21st day of
July, 1887.

[SEAL.]

James P. Currier
 U. S. Deputy Surveyor.

FINAL OATH OF DEPUTY SURVEYOR.

I, James P. Currier & James E. Toland, United States

Deputy Surveyor, do solemnly swear that in pursuance of instructions received from Douglas H. Taylor, U. S.

Surveyor General for Oregon, bearing date of the 13th

day of May, 1887, I have well, faithfully,

and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all

those parts or portions of Townships 2 S

Range 34 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an act of Congress approved August 8, 1846.

James P. Currier & James E. Toland
U. S. Deputy Surveyors

Subscribed and sworn to before me this Fifteenth

day of February, 1888

A. L. Woodcock
Notary Public
for Oregon

500

Office of U. S. Surveyor General,

Portland, Oregon, June 28th, 1888

The ^{foregoing} following Field Notes of the Survey of the

Subdivisional lines of Township
2 South Range 34 East

Willamette Meridian Oregon

executed by Jas. P. Carrin and Jas. E. Noland
Special Joint U. S. Deputy Surveyors.
under his Contract No. _____, dated May

4th, 1887, having been critically examined,
the necessary corrections and explanations made, the
said Field Notes and the survey they describe, are
hereby approved.

Douglas W. Taylor -
Surveyor General.