

FIELD NOTES

859

Of the survey of the Subdivisional

Lines of Lower & Fourth Range

N. 25 East of, Willamette Meridian,

Oregon, as surveyed by Rufus S Moore

U. S. Deputy Surveyor, under his Contract No. 451

dated June 28th 12th, 1882

Survey commenced, October 1st 1882

Survey completed, October 4th 1882

NAMES AND DUTIES OF ASSISTANTS.

Rufus S Moore, Compassman.

James Cuttridg, Chainman.

John Cuttridg, Chainman.

_____, Chainman.

_____, Chainman.

Joe Parvelli, Axeman.

_____, Axeman.

_____, Flagman.

859A

PRELIMINARY OATHS OF ASSISTANTS:

We, James Guttridge and
John Guttridge

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivisional lines of
Town 1 South Range N^o 35 East
James Guttridge Willamette Meridian, Oregon.

John Guttridge, Chainman.

_____, Chainman.

_____, Chainman.

_____, Chainman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore
Notary Public

We, J. Joe Parodi and

_____, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability,

in the survey of the Subdivisional lines of Town
1 South Range 35 East of Willamette Meridian, Oregon.

Joe Parodi, Axeman.

_____, Axeman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore
Notary Public

INDEX.

Referring the Lines to the Pages of the field Notes.

T. *1 South* R. *35 East* Will. Mer.

6	5	4	3	2	13	1			
				11		9			
7	8	9	10	11	7	12			
				3		5			
18	17	16	55	15	36	14	16	13	
			59		57		39		18
19	20	21	60	22	41	23	21	24	
			63		61		44		23
30	29	28	65	27	46	26	26	25	
			69		67		49		29
31	32	33	70	34	52	35	32	36	

Reservation from 20 in p

Meanders of ----- Pages ----- to -----

Meanders of ----- Pages ----- to -----

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

on true line
East between Secs. 12 & 13

Var. 20° East

18.20 Dry bed of creek 10 lks. wide course
North. 200 ft. below sec. cor.

And ascend

31.16 Enter Opening bears N & S and top
of ridge bears N & S. 250 ft. above
Dry bed of creek

39.00 Leave Opening bears N & S.
And Descend

40.00 Set a basalt stone 12 x 8 x 6 ^{ms} 8 ins. in
ground for $\frac{1}{4}$ sec. cor. marked
 $\frac{1}{4}$ on W. face. from which

A pin 48 ins. in dia. bears N 32° W 55 lks. dist.
marked $\frac{1}{4}$ S B F

A pin 10 ins. in dia. bears S 3 1/2° E 55 lks. dist.
marked $\frac{1}{4}$ S B F

51.00 Dry gulch course North. 150 ft. below
top of ridge

108.75 Intersect East boundary of the town-
ship 642 lks. South of the cor. to sec.
7 & 18, 100 ft. below dry gulch which

Subdivision of T. 1 South R. 35 East
 Willamette Meridian, Oregon.

is a Fir tree 13 ins. in dia, marked
 T 1 S 7 on N E
 R 36 E S 18 on S E
 R 35 E S 13 on SW and S 12 on
 NW, face, with 4 notches on S and
 2 notches on N, edges.

from which

A fir 11 ins. in dia, bears S 10° W 17 lks. dist.
 marked, T 1 S R 35 E S 13 B F

A fir 10 ins. in dia, bears S 88° E 14 lks. dist.
 marked, T 1 S R 36 E S 18 B F

A fir 10 ins. in dia, bears N 13° E 17 lks. dist.
 marked, T 1 S R 36 E S 7 B F

Set post 4 ft. long 4 ins sq, 24 ins in
 ground for Closing Cor. to Sec.
 12 & 13. marked C.C. on W,

T 1 S R 35 E S 12 on N.

T 1 S R 35 E S 13 on S. with

4 notches on S, and 2 notches on
 N, edges.

from which

A fir 10 ins. in dia, bears N 57° W 53 lks.
 dist. marked, C.C. T 1 S R 35 E S 12 B F

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

A fir 15 ins. in dia. bears S 33° W 25 lb. dist.
marked C.C. J 1 D R 35 E D 13 B J

A tamarack 9 ins. in dia. bears S 29° E 22 lb.
dist. marked C.C. J 1 D R 36 E D 18 B J

Land high and mountainous
Soil 2" & 3" sat

Heavily timbered with fir, pine

Spruce and Tamarack 99, 91 cho.

~~and some~~ ~~undergrowth~~ of
fir pine spruce & tamarack.
~~and~~ mountain laurel

October 1st 1882

Commencing at the cor to Secs 11, 12, 13 & 14 from
North between Secs. 11 & 12

Var. 20° East

28.60 Old road bears NW & East

40.00 Set a post 3 ft. long 3 ins. sq. 24 ins.
in ground. for 1/4 sec. cor. marked
1/4 D, on W. face. from which

A tamarack 3 ins. in dia. bears S 15° E 29 lb.
dist. marked 1/4 D B J

A Spruce 2 ins. in dia. bears N 54° W 42 lb. dist.
marked 1/4 D B J

868

-8-

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

- 40.20 Dry gulch course N. E.
- 66.00 Dry bed of creek 500. wide course
W 30° W
- 74.00 Enter Opening bears NW & SE
- 76.45 Wagon road bears NW & SE
- 76.97 Corral fence bears NW & SE
- 78.60 " " " E & W
- 80.00 Set a post 4 ft. long 4 ins. sq. 24 ins.
in ground for cor. to sea. 1. 2. 11 & 12
marked. T 1 S R 35 E S 1 on N E
T 1 S R 35 E S 2 on NW
S 11 on S W and S 12 on S E, face
with 5 notches on S and 1 on E edge
from which
- A pine 6 ins. in dia. bears N 45° E 400 k. dist,
marked. T 1 S R 35 E S 1 B F
- A pine 6 ins. in dia. bears N 17° W 230 k.
dist, marked. T 1 S R 35 E S 2 B F
- A pine 22 ins. in dia. bears S 17° W 410 k.
dist, marked T 1 S R 35 E S 11 B F
- A pine 4 ins. in dia. bears S 63° E 410 k.
dist, marked. T 1 S R 35 E S 12 B. F.

Subdivision of T. 1 South R. 35 E 869
Willamette Meridian, Oregon.

Land high and mountainous
Soil 2" rate
Heavily timbered with pine, fir, and
tamarack 74 chs. ~~and dense~~
undergrowth of ~~pine~~ pine, fir
tamarack.

on true line
East between Secs. 1 & 12

Var. 50° East

- 2,00 Enter Opening bears W & D
- 2,50 Cabin bears S 10° W about 3 chs.
- 8,50 Leave Opening and enter timber bears
W & D.
- 16,80 Enter Opening bears W & D.
- 21,00 Leave Opening and enter timber bear
W & D.
- 31,20 Leave timber & enter Opening bears W & D.
- 37,50 Top of hill bears W & D. 200 ft. above
Sec. Cor., and descend & enter
timber bears W & D.
- 40,00 Set a post 3 ft. long 3 ins. g. 24 ins. in
ground for 1/4 sec. cor. marked

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

- $\frac{1}{4}$ S. on N. face, from which
A pine 26 ins. in dia. bears $N64^{\circ}E$ 91 lbs.
dist, marked $\frac{1}{4}$ D B J
- A fir 26 ins. in dia. bears $S68^{\circ}W$ 95 lbs. dist,
marked $\frac{1}{4}$ D B J
- 99.00 Dry ravine course course SE . 150 ft.
below top of hill
- 101.20 Dry ravine course South
- 106.30 Enters Opening bears W & D ,
- 108.52 Intersect East boundary of the town-
ship 580 lbs. South of the cor. to cor.
6 & 7, 150 ft. Below dry ravine
which is a fast 4 ins. sq. marked
T 1 S D 6 on NE
R 36 E D 7 on SE
R 35 E D 12 on DW and D 1 on
 NW , face, with 5 notches on D ,
and 1 notch on W edge.
from which
A pine 30 ins. in dia. bears $N3^{\circ}E$ 76 lbs. dist,
marked, T 1 S R 36 E D 6 B F
- A pine 22 ins. in dia. bears $N62^{\circ}W$ 72 lbs.

Subdivision of T. 1 South R. 35 East 871
Willamette Meridian, Oregon.

dist, marked. T1DR35E D1BF

Apr 20 ins. in dia, bears S 70° W 92 MB.

dist, marked. T1DR35E D12BF

Set a basalt stone, 24 x 10 x 3 ⁱⁿ 18 in
in ground for Closing Cor. to sec.

1 & 12, marked C, E, on W, with

5 notches on D, and 1 notch on W edge,

from which

Apr 30 ins. in dia bears N 42° W 162 MB.

dist, marked, C, C, T1DR35E D1BF

and raised a mound of stone

along side. Too impracticable

Land high and mountainous

Soil 2" or 3" rate

Heavily timbered with fir, Spruce

and pine 89, 30 Cho. ~~and some~~

Ans. undergrowth of ~~fir, spruce~~
& pine.

West on a random line bet. Dec. 2 & 11

To 20° East

9.00 Old road bears NW & SE, 100 ft. below

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

- 40.00 Set a post 3 ft. long 3 ins. sq. 24 ins. in ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S. on W. face, from which a tamarack 16 ins. in dia. bears $N40^{\circ}W$ 132 R. dist. marked $\frac{1}{4}$ S B T
- A fir 12 ins. in dia. bears $S58^{\circ}E$ 31 R. dist. marked $\frac{1}{4}$ S B T
- 43.00 Descend hill bears $N \& S$.
- 55.00 Enter Opening bears $N \& S$.
- 60.00 Leave Opening and enter timber bears $N \& S$.
- 67.45 Dry ravine course S, E . 300 ft. below top of hill, and ascend
- 71.00 Enter Opening bears $NW \& SE$
- 74.00 Leave Opening and enter timber bears $NW \& SE$
- 75.00 Top of hill bears $NW \& SE$ 400 ft. above last ravine
- 77.00 Descend hill bears N, S .
- 83.87 Dry gulch course S . 300 ft. below top of hill
- 85.50 Enter Opening bears $N \& S$

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

3 notches on W & S edges,

from which

A pine 14 ins. in dia. bears N 43° E 97 LR,
dist. marked C. C. J. I. S. P. 36 E D 19 B. J
and raised a mound of stone
alongside. Pits impracticable

Land high and mountainous
Soil 2" or 3" rot

Heavily timbered with pine, fir,
and tamarack 81,60 cho ~~and~~
pine, fir, tamarack
Dense undergrowth of ~~and~~
mountain laurel

South between Decs. 23 & 24

Var. 18° 30' East

- 2,250 Tie road bears NW & SE
- 20.50 Top of hill bears NW & SE 150 ft,
above Dec. cor.
- 30.00 Descend hill bears NW & SE
- 30.20 Old road bears NW & SE
- 40.00 Set a post 3 ft. long 3 ins. sq. 24 in. in

882

Subdivision of T. 7 South R. 35 East
Willamette Meridian, Oregon.

for 1/4 sec. cor.
ground 40 ft. below top of hill marked
1/4 S on W. face, from which
A pine 9 ins. in dia. bears N 64° E 259 Mb. dist
marked 1/4 S B J

A tamarack 34 ins. in dia. bears N 88° W
27 Mb. dist. marked 1/4 S B J

45.45 Ravine course NW, 20 ft. below
1/4 sec. cor.

50.60 Old road bears E S W

56.50 Ravine course N 20° E. same as last
ravine

68.40 Old road bears NW + S E

80.00 Set a post 4 ft. long 4 ins. sq. 24 ins
in ground for cor. to secs. 23, 24,
25 & 26, marked

J 1 S R 35 E S 24 on W E

J 1 S R 35 E S 23 on NW

S 26 on S W and S 25 on S E faces
with 2 notches on S. and 1 notch
on E edges. from which

A pine 9 ins. in dia. bears N 18° E 8 Mb. dist
marked J 1 S R 35 E S 24 B J

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

A pine 10 ins. in dia. bears N 28° W 11 lbs. dist.
marked J 1 S R 35 E S 23 B J

A pine 12 ins. in dia. bears S 67° W 22 lbs. dist.
marked J 1 S R 35 E S 26 B J

A pine 14 ins. in dia. bears S 73° E 25 lbs. dist.
marked J 1 S R 35 E S 25 B J

Land high and mountainous

Soil 2" rate

Heavily timbered with fir, tamarack
and pines

Dense undergrowth of ~~sage~~ fir, tamarack, pine
and Mountain laurel

Contour line
East bet. Secs. 24 + 25

Var. 18° 30' East

Gradual Descent

3,76 Old Emigrant road bears NW & S

5,50 Top of hill bears NW & SE 75 ft. above
Sec. cor.

8,30 Descend hill bears NW & SE

24,75 Ravine course North, 250 ft. below

Subdivision of T. 1 South R. 35 East

Willamette Meridian, Oregon.

- top of hill, and ascend
- 35.50 Enter Opening bears W & S.
- 39.50 Top of ridge bears W & S. 200 ft. above Ravine
- 40.00 Ditto basal stone 18 x 12 x 7ⁱⁿ - 12 in. in ground for $\frac{1}{4}$ Sec. Cor, marked $\frac{1}{4}$ on W. face. from which
- A pine 12 ins. dia. bears S 55° W 69 lks. dist, marked $\frac{1}{4}$ S B C. and raised a mound of stone alongside
- Pite impracticable
- And Descend
- 44.00 Leave Opening and enter timber bears W & S.
- 64.40 Branch 3 lks. wide runs North 500 ft. below $\frac{1}{4}$ Sec. cor.
- Ascend
- 93.20 Enter Opening bears NW & SE
- 101.20 Leave Opening and enter timber bears W 20° W & S 20° E
- 108.60 Intersect East boundary of the township 503 lks. South of the

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

cor. to Sec. 19 & 30. 550 ft above
Branch, which is a post 4 ins. sq.
marked, T 1 S D 19 on N E

R 36 E D 30 on D E

R 35 E D 25 on D W and D 24 on
NW, faces, with 2 notches on South
and 4 notches on W. edge.

from which

A fir 18 ins. in dia. bears S 81° W 23 lks.
dist. marked, T 1 S R 35 E D 25 B F

A tamarack 16 ins. in dia. bears S 49° E 215 lks.
dist. marked, T 1 S R 36 E D 30 B F

A tamarack 14 ins. in dia. bears N 47° E 25 lks.
dist. marked, T 1 S R 36 E D 19 B F

A fir 16 ins. in dia. bears W 58° W 15 lks. dist.
marked, T 1 S R 35 E D 24 B F

Set a post 4 ft. long 4 ins. sq. for closing
cor. to Sec. 24 & 25, marked

C, C, on W. T 1 S R 35 E D 24 on W.

D T 1 S R 35 E D 25 on D face. with
2 notches on D and 4 notches on
W edge. from which

Subdivision of T. 1 South R. 35 East

Willamette Meridian, Oregon.

A pine 10 ins. in dia. bears $N40^{\circ}E$ 29 lb. dist.
marked ^{CC} J 1 D R 36 E D 30 B F

A pine 22 ins. in dia. bears $N43^{\circ}W$ 48 lb. dist.
marked C. C. J 1 D R 35 E D 24 B F

A pine 12 ins. in dia. bears $S70^{\circ}W$ 67 lb. dist.
marked C. C. J 1 D R 35 E D 25 B F

Dense high and mountainous

soil 2" & 3" rot

heavily timbered with fir,

tamarack and pine 9, 60 etc.

~~and some~~ ~~hins~~, undergrowth
fir tamarack pine
of ~~some~~ and mountain laurel

South between Secs. 25 & 26

$Tor. 18^{\circ}30'$ East

15.00 Top of hill bears NW & SE 150 ft.
above Sec. cor. and near summit
of Mountains in this Township

18.00 Descend hill bears NW & SE

32.70 Fosters tollroad bears $N25^{\circ}W$ &
 $S25^{\circ}E$ 100 ft. below summit

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

40.00 Set a post 3 ft. long 3 ins. sq. 24 ins.
inground for $\frac{1}{4}$ sec. cor. marked
 $\frac{1}{4}$ S on W. face. from which
A fir 10 ins. dia, bears S 40° E 19 lbs. dist.
marked $\frac{1}{4}$ S B F

A fir 10 ins. dia, bears S 53° W 19 lbs. dist.
marked $\frac{1}{4}$ S B F

43.00 Enter Opening bears NW + SE

45.00 Leave Opening and enter timber bears
NW + SE

53.25 Old road bears E + W

58.32 Fir 34 ins. dia.

61.55 Dry gulch course NW. 250 ft. below
Foster's toll road

63.45 Same dry gulch course NE

65.30 " " " " NW

And ascend

75.20 Enter Opening bears NW + SE

77.50 Leave Opening and enter timber bears
NW + SE

80.00 Set a post 4 ft. long 4 ins. sq. 24 ins.
inground for. cor. to sec. 25, 26. 35 x 36.

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

190 ft. above Dry gulch, marked
T, S R 35 E S 25 on N E
T, S R 35 E S 26 on NW,
S 35 on SW and S 36 on SE,
facs. with 1 notch on D, and
1 notch on E. edges,
from which

A fir 15 ins. dia, bears $N 48^{\circ} E$ 23 lb. dist,
marked, T, S R 35 E S 25 B T

A fir 16 ins. dia, bears $N 55^{\circ} W$ 9 lb. dist
marked, T, S R 35 E S 26 B T

A fir 8 ins. dia, bears $S 61^{\circ} W$ 36 lb. dist,
marked, T, S R 35 E S 35 B T

A fir 12 ins. dia, bears $S 64^{\circ} E$ 12 lb. dist,
marked, T, S R 35 E S 36 B T

Land high out mountain
Joel D'rat

Heavily timbered with fir, tam-
arack, spruce and pine 75, 70 lbs

~~and~~ dense undergrowth of fir
tammarack spruce

& pine,

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

Continue line
East between Secs. 25 & 36
Var. 19° 30' East

5.80 Dry gulch course N 20° W. 100 ft,
below sec. cor., and asend

18.00 Enter Opening bears N 25° W & S 25° E

22.70 Wagon road from Foster's toll road
to Brown Meadow, bears N 25° W &
S 25° E.

24.00 Leave Opening and enter timber
bears N 25° W & S 25° E

25.00 Top of hill bears N 25° W & S 25° E,
250 ft. above dry gulch

28.50 ~~Down~~ hill bears N 25° W & S 25° E

41.00 Set a post 3 ft. long 3 in. dia., 24 in.
in ground for $\frac{1}{4}$ sec. cor., 200 ft.
below top of hill marked $\frac{1}{4}$ S. or
W. face, from which

A fir 6 in. dia., bears N 10° E 12 lks. dist,
marked $\frac{1}{4}$ S B J

A fir 14 in. dia., bears S 21° W 13 lks.,
dist. marked $\frac{1}{4}$ S B J

37.36 Foster's toll road bears NW & SE, 250 ft

820

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

below $\frac{1}{4}$ sec. cor.

67.25 Ravine course North 100 ft. below
Foster toll road, and ascend

73.00 Top of hill bears NW & SE 150 ft.
above ravine

76.00 Descend hill bears NW & SE

87.23 Old Railroad Survey bears N.W. &
S.E.

89.00 Dry gulch course NE, 125 ft. below
top of last hill & ascend

98.00 Enter Opening bears N 20° W & S 20° E

103.50 Leave Opening and enter timber
bears NW & SE

108.75 Intersect East boundary of the
Township 538 R. South of the cor.,
to sec. 30 & 31, 250 ft. above

dry gulch which is a post 4 in.
sq. marked. F 1 S 30 on NE

R 36 S 31 on SE

R 35 E S 36 on SW and S 25,
on N.W. face, with 1 notch on
S, and 3 notches on N. edge.

Subdivision of T. 1 South R. 35 East 891
Willamette Meridian, Oregon.

from which

A fir 24 ins. in dia. bears S 10° W 26 R.
dist. marked, T 1 S R 35 E S 36 B F

A tamarack 12 ins. in dia. bears S 63° E
23 R. dist. marked, T 1 S R 36 E S 31 B F

A tamarack 14 ins. in dia. bears N 22° E 28 R.
dist. marked, T 1 S R 36 E S 30 B F

A fir 24 ins. in dia. bears N 84° W 20 R. dist.
marked T 1 S R 35 E S 25 B F

Set a post 4 ft. long 4 ins. sq. 24 ins. in
ground for closing cor. to sec.

25 & 36, marked C. C. on W,

T 1 S R 35 E S 25 on W,

T 1 S R 35 E S 36 on S. face, with
1 notch on S. and 5 notches on W.
edges.

from which

A fir 8 ins. in dia. bears S 56° E 10 R. dist.
marked C. C. T 1 S R 36 E S 31 B F

A fir 4 ins. in dia. bears N 42° W 25 R. dist.
marked C. C. T 1 S R 35 E S 25 B F

A fir 7 ins. in dia. bears S 50° W 24 R. dist.
marked C. C. T 1 S R 35 E S 36 B F

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Rufus
S Moore, U. S. Deputy Surveyor, to assist in
 running, measuring and marking the lines and corners described in the foregoing field
 notes of the survey of the Subdivisional
 lines of Town 1 South
Range 35 East of Willamette Meridian, Oregon,
 showing the respective capacities in which they acted :

- _____, Compassman.
- James Guttridge, Chainman.
- John Guttridge, Chainman.
- _____, Chainman.
- _____, Chainman.
- Joe Parodi, Axeman.
- _____, Axeman.
- _____, Flagman.

FINAL OATHS OF ASSISTANTS

We hereby certify that we assisted _____
Rufus D. Moore, U. S. Deputy Surveyor, in surveying all
 those parts or portions of the Subdivisional lines
Town 1 South of Range No.
35 East of the Willamette Meridian, Oregon,
 as are represented in the foregoing field notes as having been surveyed by him and under
 his direction ; and that said survey has been in all respects, to the best of our knowledge
 and belief, well and faithfully surveyed, and the corner monuments established, according
 to the instructions furnished by the U. S. Surveyor General of Oregon.

- _____, Compassman.
- James Guttridge, Chainman.
- John Guttridge, Chainman.
- _____, Chainman.
- _____, Chainman.
- Joe Parodi, Axeman.
- _____, Axeman.
- _____, Flagman.

Subscribed and sworn to before me, this Twenty First day of
November 1882

[SEAL.]

Rufus D. Moore

Notary Public

FINAL OATH OF DEPUTY SURVEYOR.

I, Rufus S. Moore

United States Deputy Surveyor, do solemnly swear that in pursuance of in-

structions received from

James C. Johnson

U. S. Surveyor General for Oregon, bearing date of the

Twelfth
~~Twenty Eighth~~

day of

June

, 1882, I have well, faith-

fully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all those

parts or portions of

The Subdivisional lines of

Township 1 South - Range 35 East of

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual; printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the *true* field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

Rufus S. Moore
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this

10th

day of

February

1883

Benjford Robb
Notary Public

Office U. S. Surveyor General,

Portland, Oregon, June 5, 1883.

The following Field Notes of the Survey of the
Subdivisions of Township
1 South Range 35 East,
Will. Mer., Oregon
executed by Rufus S. Moore

under his Contract No. 457, dated June
12th 1882, having been critically examined, the

necessary corrections and explanations made, the said field notes
and the survey they describe, are hereby approved.

James C. Tolman
Surveyor General.

