

FIELD NOTES

859

Of the survey of the Subdivisional

Lines of Lower & Fourth Range

N. 25 East of, Willamette Meridian,

Oregon, as surveyed by Rufus S Moore

U. S. Deputy Surveyor, under his Contract No. 451

dated June 28th 12th, 1882

Survey commenced, October 1st 1882

Survey completed, October 4th 1882

NAMES AND DUTIES OF ASSISTANTS.

Rufus S Moore, Compassman.

James Cuttridg, Chainman.

John Cuttridg, Chainman.

_____, Chainman.

_____, Chainman.

Joe Parvelli, Axeman.

_____, Axeman.

_____, Flagman.

859A

PRELIMINARY OATHS OF ASSISTANTS:

We, James Guttridge and
John Guttridge

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivisional lines of
Town 1 South Range N^o 35 East
James Guttridge Willamette Meridian, Oregon.

John Guttridge, Chainman.

_____, Chainman.

_____, Chainman.

_____, Chainman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore
Notary Public

We, J. J. Parodi and

_____, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability,

in the survey of the Subdivisional lines of Town
1 South Range 35 East of Willamette Meridian, Oregon.

J. J. Parodi, Axeman.

_____, Axeman.

Subscribed and sworn to before me, this Fifteenth

day of August 1882

[SEAL.]

Jugus S. Moore
Notary Public

INDEX.

Referring the Lines to the Pages of the field Notes.

T. *1 South* R. *35 East* Will. Mer.

6	5	4	3	2	13	1			
				11		9			
7	8	9	10	11	7	12			
				3		5			
18	17	16	55	15	36	14	16	13	
			59		57		39		18
19	20	21	60	22	41	23	21	24	
			63		61		44		23
30	29	28	65	27	46	26	26	25	
			69		67		49		29
31	32	33	70	34	52	35	32	36	

Reservation from 20 in p

Meanders of ----- Pages ----- to -----

Meanders of ----- Pages ----- to -----

882

Subdivision of T. 1 South R. 35 East

Willamette Meridian, Oregon.

Land high and mountainous
 Soil 2" rate
 Heavily timbered with fir, spruce
 tamarack and pine, ~~and some~~
 undergrowth of ~~some~~ fir, spruce tam-
 arack & Pine 97.35 chs.

South between Secs. 35 & 36

Var. 79° 30' East

10.00 Enter prairie bears NW & South

10.50 Top of hill bears NW & SE 50 ft.
above Sec. cor.

12.00 Descend hill bears NW & SE

27.50 Leave prairie and enter timber
bears E & W

32.50 Dry gulch crosses West

38.40 Enter clearing of right of way bears
W40°W & S35°E.

39.96 Intersect Railroad Survey bears
W40°W & S40°E, Location stake
No. 297 bears W40°W 14 lks,
dist.

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

40,00 Set a post 3 ft. long 3 ins. sq. 24 ins.
in ground for $\frac{1}{4}$ sec. cor. 300 ft.
below point of descending hill
marked $\frac{1}{4}$ S on W. face.

from which

A pine 6 ins. in dia. bears $N 70^{\circ} E 118$ ft.
dist marked $\frac{1}{4}$ S B F

A pine 12 ins. in dia. bears $S 70^{\circ} W 88$ ft.
dist. marked $\frac{1}{4}$ S B F.

From this cor.

A pine 8 ins. in dia. bears $S 7^{\circ} E 200$ ft.
dist, marked as the highest

point on Min's Division on the
line of the Railroad between
Mechams Station and Snake

River and 4407 + 57,

Cronks House bears $S 31^{\circ} E$ about
200 chs. from $\frac{1}{4}$ cor. & gradually ascend

41,00 Leave clearing of right of way
bears $N 40^{\circ} W$ or $S 40^{\circ} E$

55,50 S. S. Cronks. House bears $S 15^{\circ} E$, and

55,50 Old Road bears $E + W, 15$ ft

Subdivision of T. 1 South W. R. 35 East
Willamette Meridian, Oregon.

above $\frac{1}{4}$ sec. cor.

73.88 Intersect South boundary of the
township 2834 lks. West of the cor
to sec. 1 & 2, which is a post
4 ins. sq. marked, T 1 D 36 on N E
R 35 E D 1 on D E
T 2 D 2 on D W and D 35 on
NW. face, with 1 notch on E. and
5 notches on W. edge.

from which

A pine 12 ins. ~~dia.~~ dia. bears S 21° E 14 lks.
dist. marked T 2 D R 35 E D 1 B J

A pine 9 ins. ~~dia.~~ dia. bears S 3° W 22 lks.
dist. marked T 2 D R 35 E D 2 B J

A pine 13 ins. ~~dia.~~ dia. bears N 2° W 12 lks.
dist. marked, T 1 D R 35 E D 35 B J

A pine 9 ins. ~~dia.~~ dia. bears N 82° E 2.8 lks. dist
marked, T 1 D R 35 E D 36 B J

Put a post 4 ft. long 4 ins. sq. 2 1/4 ins. in
ground for closing corner. to
sec. 35 & 36, marked C, C, on N.

T 1 D R 35 E D 36 on E and

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

-) T. 1 S R. 35 E S. 35 on W. face, with 1 notch on E and 5 notches on W. edges, from which
- A fir 16 ins. ~~in dia.~~ bears $N 60^{\circ} E$ 25 lks. dist. marked C.C. T. 1 S R. 35 E S. 36 B J
- A fir 15 ins. ~~in dia.~~ bears $N 48^{\circ} W$ 24 lks. dist. marked C.C. T. 1 S R. 35 E S. 35 B J
- A fir 8 ins. ~~in dia.~~ bears $S 48^{\circ} E$ 26 lks. dist. marked C.C. T. 2 S R. 35 E S. 2 B J

Land high and mountainous

Soil 2" & 3" rate

Heavily timbered with fir, pine, tamarack and Spruce 53, 78 ch. ~~fir~~ fir pine tamarack spruce. Dense undergrowth of ~~grass~~ and some Mountain laurel

Compared Compass with line established by an observation on the Star Polaris and find that Compass runs correct
October 3rd 1882.

912
Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

South between Secs. 34 & 35
Var. 24° East

10.55 Tie road bears NE & SW

12.40 Wagon road to Big Meadows bears
N 20° E & S 20° W

13.95 Same road to Big Meadows from
right of way bears N 20° W & S 40° E

21.60 Tie road bears NE & SW

40.00 Set a post 3 ft. long 3 ins. sq. 24 ins. in
ground for $\frac{1}{4}$ sec. cor. 200 ft. above
last sec. cor. marked $\frac{1}{4}$ S on W.

face. from which

A Spruce 8 ins. in dia. bears N 54° E 67 lks.
dist. marked $\frac{1}{4}$ S B F

A Spruce 10 ins. in dia. bears S 22° W 12 lks.
dist. marked $\frac{1}{4}$ S. B F

74.50 Intersect. South boundary of town-
ship 2857 lks. West of the cor. to
secs. 2 & 3, which is a post 4 ins.
sq. marked, T 1 S R 35 on NE

R 35 E S 2 on SE

T 2 S S 3 on SW and S 34 on NW.

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

913

faces, with 2 notches on E and 4 notches
on W. edges from which

A pine 18 ins. in dia. bears S 56° W 17 lks. dist.
marked T 2 S R 35 E D 3 B F

A pine 9 ins. in dia. bears S 42° E 21 lks.
dist. marked T 2 S R 35 E D 2 B J

A pine 11 ins. in dia. bears N 15° W 19 lks. dist.
marked T 1 S R 35 E D 34 B F

A pine 9 ins. in dia. bears N 47° E 19 lks. dist.
marked T 1 S R 35 E D 35 B J

Set a post 4 ft. long 4 ins. sq. 24 ins. in
ground for closing cor. to sec. 34 &
35, 250 ft. at our last 1/4 sec. cor.
marked C. C. on W.

T 1 S R 35 E D 35 on E

T 1 S R 35 E D 34 on W. faces.

with 2 notches on E. and 4 notches
on W. edges. from which

A fir 10 ins. in dia. bears N 47° E 213 lks. dist.
marked C. C. T 1 S R 35 E D 35 B J

A spruce 7 ins. in dia. bears N 38° W 11 lks. dist.
marked C. C. T 1 S R 35 E D 34 B F

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

A Spruce Pine, ~~indis.~~ bears $S 43^{\circ} W 23$ lbs.
dist. marked, C.C. T2 DR 35 E D 3 B F

Land high and mountainous

Soil D'rot

Heavily timbered with fir, spruce
tamarack and pine, ~~and~~

Dense undergrowth of ~~fir~~ fir, spruce
tamarack, pine
and yew

Compared Compass with
line established by an observation
on the Star Polaris and fine Compass
agrees with line thus established
October 5th 1882;

From the cor. to sec. 9, 10, 15 & 16
which is a post rotten and decayed
in mound of earth, which I
reestablished by setting a new
Post 4 ft. long 4 ins. sq. 24 ins. in
ground for cor. to sec. 9, 10, 15 & 16
marked, T1 DR 35 E D 10 on NE

030

-70-

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

account of Umatilla Indian
Reservation, rugged country and
a South boundary of township was
not run farther ^W than $\frac{1}{4}$ sec cor.
bet Sec. 4 + 33, there is no limit
close to.

Land rough, broken and
mountainous, soil 3" rate
Heavily timbered with fir,
Tamarack, spruce and pine
32,50 ~~ch.~~ ~~and some dense under~~
-growth of ^{fir, tamarack} spruce & pine.

South between Secs. 33 + 34

Ta. 50° East

- 2.40 Indian trail bears NW & SE and
descend hill bears NW & SE
3.00 Enter Opening bears NW & SE
3.50 Leave opening and enter timber bears
NW & SE
8.28 Ravine crosses NW, 150 ft. below

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

sec. cor. Brook 2 lks, wide in ravine
course W. ascend from brook

40.00 Set a basalt stone 12 x 12 x 7 ins. ^{marked 1/4 on W face.}

in ground for 1/4 sec. cor. from which

A 7i 20 in diam bears N85°E 9 lks dist, marked 1/4 S. B. J.

A 7i 30 " " " N36°W 31 " " " 1/4 S B J 500 ft

75.10 ^{above last Ravine} Intersect South boundary of the township

2830 lks. West of the cor. to sec. 3 & 4,

which is a post 4 ins. sq. marked -

T 1 D D 34 on Dr E

R 35 E D 3 on D E

T 2 D. D 4 on DW and D 33 on NW,

face, with 3 notches on E. & W. edges.

from which

A 7i 12 ins. in dia. bears S 60° W 22 lks,
dist. marked, T 2 D R 35 E D 4 B J

A 7i 11 ins. in dia. bears S 53° E 27 lks, dist
marked, T 2 D R 35 E D 3 B J

A 7i 16 ins. in dia. bears N 30° W 14 lks, dist, marked
T 1 D R 35 E D 33 B J

A 7i 14 ins. in dia. bears N 11° E 38 lks, dist,
marked, T 1 D R 35 E D 34 B J

Set a post 4 ft. long 4 ins. sq. 24 ins. in

932

Subdivision of T. 1 South R. 35 East
Willamette Meridian, Oregon.

ground for closing cor. to sec. 33 & 34
150 ft. above last $\frac{1}{4}$ sec cor. marked
C.C. on W. — T. 1 S. R. 35 E. S. 34 on E
T. 1 S. R. 35 E. S. 33 on W. face,
with 3 notches on E & W. edges,
from which

A fir 9 ins. ~~dia.~~ dia. bears N 60° E 10 lks. dist.
marked, C.C. T. 1 S. R. 35 E. S. 34 B. J.

A pine 20 ins. ~~dia.~~ dia. bears N 49° W 24 lks. dist.
marked C.C. T. 1 S. R. 35 E. S. 33 B. J.

A fir 24 ins. ~~dia.~~ dia. bears S 23° W 23 lks. dist.
marked C.C. T. 2 S. R. 35 E. S. 4 B. J.

Land high and mountainous
Soil 2^d rate

Heavily timbered with pine, fir,
and tamarack 72,600 chs. and
dense undergrowth of pine, fir & tamarack
October 7th 1882.

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Rufus
S Moore, U. S. Deputy Surveyor, to assist in
 running, measuring and marking the lines and corners described in the foregoing field
 notes of the survey of the Subdivisional
 lines of Town 1 South
Range 35 East of Willamette Meridian, Oregon,
 showing the respective capacities in which they acted :

- _____, Compassman.
- James Guttridge, Chainman.
- John Guttridge, Chainman.
- _____, Chainman.
- _____, Chainman.
- Joe Parodi, Axeman.
- _____, Axeman.
- _____, Flagman.

FINAL OATHS OF ASSISTANTS

We hereby certify that we assisted _____
Rufus D. Moore, U. S. Deputy Surveyor, in surveying all
 those parts or portions of the Subdivisional lines
Town 1 South of Range No.
35 East of the Willamette Meridian, Oregon,
 as are represented in the foregoing field notes as having been surveyed by him and under
 his direction ; and that said survey has been in all respects, to the best of our knowledge
 and belief, well and faithfully surveyed, and the corner monuments established, according
 to the instructions furnished by the U. S. Surveyor General of Oregon.

- _____, Compassman.
- James Guttridge, Chainman.
- John Guttridge, Chainman.
- _____, Chainman.
- _____, Chainman.
- Joe Parodi, Axeman.
- _____, Axeman.
- _____, Flagman.

Subscribed and sworn to before me, this Twenty First day of
November 1882

[SEAL.]

Rufus D. Moore

Notary Public

FINAL OATH OF DEPUTY SURVEYOR.

I, Rufus S. Moore

United States Deputy Surveyor, do solemnly swear that in pursuance of in-

structions received from

James C. Johnson

U. S. Surveyor General for Oregon, bearing date of the

Twelfth
~~Twenty Eighth~~

day of

June

, 1882,

I have well, faithfully and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all those

parts or portions of

The Subdivisional lines of

Township 1 South - Range 35 East of

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual; printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

Rufus S. Moore
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this

10th

day of

February

1883

Benjford Robb
Notary Public

Office U. S. Surveyor General,Portland, Oregon, *June 5,* 188*3.*

The following Field Notes of the Survey of the

Subdivisions of Township
1 South Range 35 East,
Will. Mer., Oregon
executed by *Rufus S. Moore*

under his Contract No. *457*, dated *June*
12th 188*2*, having been critically examined, the

necessary corrections and explanations made, the said field notes
and the survey they describe, are hereby approved.

James C. Tolman
Surveyor General.

