

Field Notes of the Survey of the  
Exterior boundaries of Township 2  
North of Range 28 East of the Willamette  
Meridian in the State of Oregon by  
David P. Thompson, deputy Surveyor  
under his contract No. 83 bearing  
date the 23<sup>rd</sup> day of July 1859

Begin at the Established corner  
to Townships 1 & 2 North of Ranges  
27 & 28 East I run  
North between Secs 31 & 36  
Variation 21° 05' East  
chains  
40.00 Set post for 1/4 Sec corner in mound of  
Earth &c as per instructions  
80.00 Set post for corner to Secs 30, 31, 25 & 36  
in mound of Earth &c as per instructions  
Land gently rolling Soil good <sup>and</sup> rate

North between Secs 25 & 30  
Variation 19° East  
40.00 Set post for 1/4 Sec corner in mound of Earth  
&c as per instructions  
80.00 Set post for corner to Secs 24, 25, 19 & 30  
in mound of Earth &c as per instructions  
Land gently rolling. Soil good <sup>and</sup> rate  
August 27<sup>th</sup> 1859

D. N. P. S. E.

45-11

505

chain North between Secs 19 & 24

Variation  $19^{\circ}25'$  East

40.00 Set post for  $\frac{1}{4}$  Sec corner in mound of earth  
& as per instructions

80.00 Set post for corner to Secs 18, 19, 13 & 24  
in mound of earth & as per instructions  
Land gently rolling. Soil good 2<sup>nd</sup> rate

---

North between Secs 13 & 18

Variation  $20^{\circ}25'$  East

40.00 Set post for  $\frac{1}{4}$  Sec corner in mound of earth

80.00 & as per instructions

80.00 Set post for corner to Secs 12, 13, 13 & 18 in  
~~mound~~ mound of earth & as per instructions  
Land gently rolling. Soil good 2<sup>nd</sup> rate

46 506

D. W. R. 28. E.

chains North between Secs 7 & 12

Variation  $20^{\circ}30'$  East

40.00 Set post for  $\frac{1}{4}$  Sec corner in Monna of Earth &c as per instructions

80.00 Set post for corner to Secs 6, 7, 11 & 12 in Monna of Earth &c as per instructions  
Land gently rolling Soil good 2<sup>nd</sup> rate

---

North on line between Secs 18 & 6

Variation  $20^{\circ}10'$  East

40.00 Set post for  $\frac{1}{4}$  Sec corner in Monna of Earth &c as per instructions

80.00 Set post for corner to Townships 28 & 3 North of Ranges 27 & 28 East in Monna of Earth &c as per instructions  
Land Level Soil 1<sup>st</sup> rate

---

From the corner to Township 28 & 3 North of Range 27 & 28 East I run a random line between said Townships East setting temporary half mile and mile posts at 40.00 & 80.00 chains I find the line to be 5 miles 78 chains & 36 links and the falling to be 420 links North of Township

## List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 182 North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)  
 Allen Thompson "  
 Benj. Athey Axeman

We hereby certify that we assisted  
 David P. Thompson deputy surveyor  
 in surveying the Exterior boundaries  
 of Townships Nos 1 & 2 North of the  
 Base Line of Ranges Nos 28, 29, &  
 30 East of the Willamette Meridian  
 and that said Townships have been  
 in all respects to the best of our  
 knowledge and belief well and faithfully  
 surveyed and the boundary monuments  
 planted according to the instructions  
 furnished by the Surveyor General

D. J. Fournell

Allen Thompson

Benjamin H. H. H.

Sworn and Subscribed to before  
 me this 18<sup>th</sup> day of October 1859

W. C. Mowbray

County Clerk  
 Wasco County Oregon

I David P. Thompson deputy Surveyor do  
 Solemnly Swear that in pursuance of  
 a contract with W. W. Chapman Surveyor  
 of the public Lands of the United States  
 in the State of Oregon bearing date  
 the 22<sup>nd</sup> day of July 1859 and in strict  
 conformity to the laws of the United States  
 and the instructions furnished by the said  
 Surveyor General I have faithfully surveyed  
 the exterior boundaries of Townships Nos.  
 18 & 19 North of the Base Line of Ranges 28  
 29 & 30 East of the Willamette Meridian in the  
 State aforesaid and do further Solemnly  
 Swear that the foregoing are the true and original  
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1<sup>st</sup> day  
 of November 1859 at Salem Oregon  
 L. C. White  
 Not Pub

Surveyor General's Office,

Eugene City January 31<sup>st</sup> 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22<sup>d</sup> day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman  
Sur. Genl. of Oregon.