

General Description ³⁴

494

The quality of land in this Township is good 2nd rate rolling Prairie covered with a thick growth of Bunch Grass. There are numerous Springs in this Township.

This Township will admit of considerable settlement and therefore should be subdivided.

Field Notes of the Survey of the Exterior boundaries of Township 1 North of Range 28 East of Willamette Meridian, in the State of Oregon by David P. Thompson deputy Surveyor under his contract No 83, bearing date the 23rd day of July 1859

X North between Secs 186:

x x x x

Variation 20° 51' East

chains

4000

Set post for 1/4 Sec corner in middle of East 8th as per instructions

8000

Set post for corner to Townships Nos 182 North of Ranges 27828 East in middle of East 8th as per instructions

Variation 21° 05' East

Land gently rolling. Soil 2nd rate

From the corner to Townships 182 North of Ranges 27828 East I run a line

due East between Secs Townships

A fine Sec line to be 5 miles

79 chains and 25 links. and the

falling to be 250 links North of Township corner

The correction for the true line will therefore be 75 links East and 3.83 links North per mile

Chains from the corner to Township 182
North of Ranges 28 & 29 East Iron
N 89° 35' W on a true line between Secs 1 & 36
Variation 20° East

4000 Set post for $\frac{1}{4}$ Sec corner in mound
of Earth & as per instructions

8000 Set post for corner to Secs 1, 2, 35 & 36
in mound of Stone & as per instructions
Land Level Soil good 2nd rate

N 89° 35' W on true line between Secs 2 & 35
Variation 20° 20' East

4000 Set post for $\frac{1}{4}$ Sec corner in mound of Earth
& as per instructions

8000 Set post for corner to Secs 2, 3, 34 & 35
in mound of Earth & as per
instructions

Level

Soil good 2nd rate

August 26th 1859

Chains N 89° 35' W on true line between Secs 38 & 34
 Variation 20° 15' East

4000 Set post for 1/4 Sec corner in mound
 of Earth &c as per instructions

7300. Precious Soil bears N & S

8000 Set post for corner to Secs 3, 4, 33 & 34
 in mound of Earth &c as per instructions
 Level Soil good 2nd rate

N 89° 35' W on true line between Secs 48 & 33
 Variation 20° 10' East

4000 - Set post for 1/4 Sec corner in mound of
 Earth &c as per instructions

8000 Set post for corner to Secs 4, 5, 32 & 33
 in mound of Earth &c as per instructions
 Level gently rolling
 Soil good 2nd rate

T. N. P. S. E.

chains N 89° 35' W on true line between Secs 5 & 32
 Variation 19° 30' East

40.00 Set post for ^{1/4} Sec corner in mound of Earth
 8° as per instructions

80.00 Set post for corner to Secs 5, 6, 31, 32
 in mound of Earth 8° as per instructions
 Land gently rolling Soil good ²/₄ rate

N 89° 35' W on true line between Secs 6 & 31
 Variation 18° 55' East

40.00 Set post for ^{1/4} Sec corner in mound of
 Earth 8° as per instructions

79.25 The corner to Townships 182 North
 Ranges 27 & 28 East Var 21° 05' East
 Land gently rolling Soil ²/₄ rate

General Description

The quality of Land in this Township is
²/₄ rate rolling prairie covered with
 Birch Grass is well watered by
 Butter Creek and numerous springs
 This Township will admit of large settlements
 and should there fore be subdivided

List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 18 & North of Ranges Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)
 Allen Thompson "
 Benj. Athey Axeman

We hereby certify that we assisted
 David P. Thompson deputy surveyor
 in surveying the Exterior boundaries
 of Townships Nos 1 & 2 North of the
 Base Line of Ranges Nos 28, 29, &
 30 East of the Willamette Meridian
 and that said Townships have been
 in all respects to the best of our
 knowledge and belief well and faithfully
 surveyed and the boundary monuments
 planted according to the instructions
 furnished by the Surveyor General

D. J. Powell

Allen Thompson

Benjamin H. H. H.

Sworn and Subscribed to before
 me this 18th day of October 1859

W. C. Mowbray
 County Clerk
 Wasco County Oregon

I David P. Thompson deputy Surveyor do
 Solemnly Swear that in pursuance of
 a contract with W. W. Chapman Surveyor
 of the public Lands of the United States
 in the State of Oregon bearing date
 the 22nd day of July 1859 and in strict
 conformity to the laws of the United States
 and the instructions furnished by the said
 Surveyor General I have faithfully surveyed
 the exterior boundaries of Townships Nos.
 18 & 19 North of the Base Line of Ranges 28
 29 & 30 East of the Willamette Meridian in the
 State aforesaid and do further Solemnly
 Swear that the foregoing are the true and original
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1st day
 of November 1859 at Salem Oregon
 L. C. White
 Not Pub

Surveyor General's Office,

Eugene City January 31st 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22^d day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman
Sur. Genl. of Oregon.