

Recd Nov 3

599

W.D.

Carter

Smith

Gamma & Corrected

Thompson

Field Notes

Subdivisions	N. D. N. R. D. E.
commenced	October 3 rd 1839
completed	October 10 th 1839

Washington transcript made
C.P.T.

Manuscript compared with
Notes 3.00

599 1/2

599 A

Field notes of The Subdivision
Lines in Township No 2 N of Range
28 East of the Willamette Meridian
in the State of Oregon by David
P. Thompson deputy Surveyor
renewed his contract No 83 bearing
date the 22nd day of July 1859

Township 2 North of Range 28 East

6	32	5	24	4	18	3	12	2	6	1
32		31		23		17		11		5
7	31	8	23	9	17	10	4	11	5	12
30		30		22		16		10		4
18	29	17	22	16	16	15	10	14	4	13
28		28		21		15		9		3
19	28	20	21	21	15	22	9	23	3	24
27		27		20		14		8		2
30	26	29	20	28	4	27	8	26	2	25
26		25		29		13		7		2
31	25	32	19	33	13	34	7	35	1	36

T. 2. N. R. 28. E.

601

Subdivisions T. 2. N. R. 28. E.

Chains North between Secs 35 & 36

4000 Set post for $\frac{1}{4}$ Sec corner in mound of Earth &c as per instructions

8000 Set post for corner to Secs ^{26, 35, & 36} 25, 26, 35 & 36 in mound of Earth &c as per instructions
Land gently rolling
Soil good $\frac{2}{3}$ rate

East on remainder line between Secs 25 & 36

4000 Set post for $\frac{1}{4}$ Sec corner

79.70 Intersect East boundary 70 links North of Sec corner

N 89° 30' W on true line between Secs 25 & 36

39.85 Set post for $\frac{1}{4}$ Sec corner in mound of Earth &c as per instructions

79.70 The corner to Secs 30, 31, 25 & 36

Land gently rolling
Soil $\frac{2}{3}$ rate

chains North between Secs 25 & 26
Variation 20° 30' East

40.00 Set post for 1/4 Sec corner in corner
of Earth & as per instructions

80.00 Set post for corner to Secs 23, 24, 25
& 26 in corner of Earth & as per
instructions

Lower ²/₁₀₀ rate. Soil ²/₁₀₀ rate

East on a random line between Secs 24 & 25

40.00 Set post for ^{1/4} Sec corner ^{temp.}

79.80 Intersect East boundary 70 links
North of Sec corner

N 89° 30' W on true line between Secs 24 & 25

39.90 Set post for 1/4 Sec corner in corner of
Earth & as per instructions

79.80 Set post corner to Secs 23, 24, 25 & 26

Land gently rolling
Soil ^{1/100} rate

Merino North between Secs 23 & 24
 Variation 19° 45" East

40.00 Set post for 1/4 sec corner in mound
 of Earth &c as per instructions

80.00 Set post for corner to Secs 13, 14, 23 &
 24 in mound of Earth &c as per
 instructions
 Level Soil 1/4 rate

East on remnant line between Secs 13 & 24

40.00 Set post for ^{Merino} 1/4 sec corner

79.70 Intersect East boundary 70 links North
 of sec corner

N 89° 30' W on true line between Secs 13 & 24

39.88 Set post for 1/4 sec corner in mound of Earth
 &c as per instructions

79.70 The corner to Secs 13, 14, 23 & 24
 Level Soil 1/4 rate

4 604

D. 2. N. R. 28. E.

chains North, between Secs 13 & 14

Variation 20° 10' East

40.00 Set post for $\frac{1}{4}$ Sec corner in corner of Earth & as per instructions

80.00 Set post for corner to Secs 11, 12, 13 & 14. in corner of Earth & as per instructions Same level soil $\frac{1}{4}$ rate

East on remain line between Secs 12 & 13

40.00 Set post for temp. $\frac{1}{4}$ Sec corner ~~in~~

79.83 Intersect East boundary at corner to sec 12 & 13

West on true line between Secs 12 & 13

39.92 Set post for $\frac{1}{4}$ Sec corner in corner of Earth & as per instructions

79.83 The corner to Secs 11, 12, 13 & 14

~~in corner of Earth & as per instructions~~
Same level soil $\frac{1}{4}$ rate

North between Secs 11 & 12
 Var 193.0' East

4000 Set post for 1/4 Sec corner in corner
 of Earth & as per instructions

8000 Set post for corner to Secs 1, 2, 11 & 12
 in corner of Earth & as per instructions
 Land gently rolling Soil 1st rate

East on random line between Secs 18 & 12

4000 Set post for ^{1/4} Sec corner in

7960 Intersect East boundary 42 links South
 of Sec corner

N 89° 42' W on true line between Secs 18 & 12
 in corner of Earth & as per instructions

1150 In view trail bears N E & S W

3980 Set post for 1/4 Sec corner in corner of Earth &
 as per instructions

7960 Set post for corner to Secs 1, 2, 11 & 12
 Land level Soil 1st rate

⁶
606 G. L. N. P. 28. E.

chains North old ranamou line between Secs 1 & 2
Variation 20° East

40.00 Set post for temp. 1/4 Sec corner

80.70 Intersect North boundary 60 links East
of Sec corner

S. 26° East on ~~tree~~ line between Secs 1 & 2

40.70 Set post for 1/4 Sec corner in corner of Earth
80 as per instructions

80.70 The corner for Secs 1, 2, 11 & 12

Level Level Soil 1st rate

October 5th 1859

North between Secs 34 & 35

Chains

4000 Set post for 1/4 Sec corner in Monna of Earth
8° as per instruction

8000 Set post for corner to Secs 26, 27, 34 & 35
in Monna of Earth 8° as per instructions
Land gently rolling
Soil good 2nd rate

East on railroad line between Secs 26 & 35

4000 Set post for Temp. 1/4 Sec corner

8000 Intersect N & S Line 71 links North of
Sec corner

N 89° 30' W on true line between Secs 26 & 35

4000 Set post for 1/4 Sec corner in Monna of
Earth 8° as per instructions

8000 Set post for corner to Secs 26, 27, 34 & 35
Land gently rolling
Soil 1st rate

8 608

T. J. W. P. 28. E.

chains north between Secs 26 & 27
Variation 22° East

4000 Set post for $\frac{1}{4}$ Sec corner in corner of
Earth & as per instructions

8000 Set post corner to Secs 22, 23, 26 &
27 in corner of Earth & as per
instructions

Land gently rolling
Soil 1st rate

East on remeasure line between Secs 23 & 26

4000 Set post for ^{temp} $\frac{1}{4}$ Sec corner

8000 Intersect N & S Line 70 links north of
Sec corner

N 89° 30' W on true line between Secs 23 & 26

4000 Set post for $\frac{1}{4}$ Sec corner in corner of
Earth & as per instructions

6900 Level bears N E & S W

8000 The corner to Secs 22, 23, 26 & 27
Level level Soil 1st rate

North between Secs 22 & 23
 chains Variation 21° 20' East
 40.00 Set post for 1/4 sec corner in mound
 of earth & as per instructions
 80.00 Set post for corner to Secs 14, 15, 22 & 23
 in mound of earth & as per instructions
 Land gently rolling Soil 1st rate

East on random line between Secs 14 & 23
 40.00 set post for temp 1/4 sec corner
 79.94 Intersect N & S line at corner to Secs
 13, 14, 23 & 24

West on true line between Secs 14 & 23
 39.97 Set post for 1/4 sec corner in mound
 of earth & as per instructions
 79.94 He corner to Secs 13, 14, 22 & 23
 Same Level Soil 1st rate

12 610

O. W. P. S. E.

North between Secs 14 & 15
Variation 19°30' East

40.00 Set post for 1/4 sec corner in mound of
Earth & as per instructions

80.00 Set post for corner to Secs 10, 11, 14 & 15
in mound of Earth & as per instructions
Level Soil 1st rate

East on remeasured line between Secs 11 & 14

40.00 Set post for temp 1/4 sec corner

79.76 Intersect N & S line at sec corner

West on true line between Secs 11 & 14

35-
39.88 Set post for ~~corner to~~ 1/4 sec ^{Cor} in mound of
Earth & as per instructions

79.76 The corner to Secs 10, 11, 14 & 15 ~~is~~
at Earth & as per instructions
Level gently rolling Soil 1st rate

G. 2. N. R. 28. E

611

North between Secs 10 & 11

Variation $19^{\circ}20'$ East

- 4000 Set post for $\frac{1}{4}$ sec corner in Mound of Earth &c
as per instructions From this corner a fine
Large Spring bears $S 79^{\circ} W$ about 10 chains east
- 3600 Trail bears N E & S W
- 6600 Trail bears N E & S W
- 8000 Set post for corner to Secs 2, 3, 10 & 11
in Mound of Earth &c as per instructions
Land gently rolling. Soil 2nd rate
-

East between Secs 2 & 11 on range line

- 4000 Set post for temp $\frac{1}{4}$ sec corner
- 7950 Intersect N & S Line 28 links North of
Sec corner
- N $89^{\circ}48'$ W on true line between Secs 2 & 11
- 2000 Trail bears N. E. & W.
- 3975 Set post for $\frac{1}{4}$ sec corner in Mound of Earth
&c as per instructions
- 7950 The corner to Secs 2, 3, 10 & 11
Land gently rolling Soil good 2nd rate

12

612

Fig. No. P. 28. E.

Chains north on range line between Secs 2 & 3

Variation 2°20' East

40.00 Set post for temp 1/4 Sec corner

80.81 Intersect north boundary of Township.

36 links East of Sec corner

S 234' E on true line between Secs 2 & 3

40.81 Set post for 1/4 Sec corner in corner of earth
80 as per instructions

80.81 The corner to Secs 2, 3, 10 & 11

Level Level Soil & Grate

Oct 6th 1859

Cheris North between Secs 33 & 34

4000 Set post for 1/4 Sec corner in mound of Earth &c as per instructions

8000 Set post for corner to Secs 27, 28, 33 & 34 in mound of Earth &c as per instructions

Large gently rolling
Soil 1st rate

East on renewal line between Secs 27 & 34

4000 Set Temp 1/4 Sec corner

4994 Intersect N & S Line 1 at Sec corner

West on true line between Secs 27 & 34

3450 Indian Trail bears N 88 S W

3997 Set post for 1/4 Sec corner in mound of Earth &c as per instructions

4994 The corner to Secs 27, 28, 33 & 34
Soil hilly Soil 2nd rate

14 604

D. S. N.

R. 28. E.

chains north between Secs 27828
Variation 20° East

Descend hill

2500 Deep Ravine bears E & W foot of hill bears
E & W ascend hill

4000 Set post for 1/4 Sec corner in Monna of
Earth 8° as per instruction

8000 Set post for corner to Secs 21, 22, 27828
in Monna of Stone
Lined hilly Soil 2 over rate

East on remnant line between Secs 22827

4000 Set Temp 1/4 Sec corner ~~post~~

7999 Intersect N & S line 70 links north of
Sec corner

N 89° 30' W on true line between Secs 22827

940 Quarian Trail bears N & S ascend hill

4000 Set post for 1/4 Sec corner in Monna of Earth

7 8° as per instructions

78.50 Top of hill bears N & S

7999 The corner to Secs 21, 22, 27828

Lined steep & broken Soil 2 over rate

Chains North between Secs 21 & 22

Variation 19° 20' East

ascend hill

1000 Top of hill N 3° W S 3° E

4000 Set post for 1/4 Sec corner in corner of Earth & as per instructions

8000 Set post for corner to Secs 15, 16, 21 & 22 in corner of Earth & as per instructions
Level hilly Soil 2nd rate

East on remainder between Secs 15 & 22

4000 Set post for temp 1/4 Sec corner

7940 Intersect N & S Line 60 links North of Sec corner

N 89° 34' W on true line between Secs 15 & 22

800
3970 Northern Grail bears N & S ascend hill
Set post for 1/4 Sec corner in corner of Earth & as per instructions

7940 True corner to Secs 15, 16, 21 & 22 in corner of Earth
Level hilly Soil 2nd rate

chains North between Secs 15 & 16
 Variation 21° East
 40.00 Set post for ^{1/4} Sec corner in ^{1/4} corner of Earth
 80 as per instructions
 80.00 Set post for corner to Secs 9, 10, 15 & 16
 in corner of Earth 8° as per instructions
 Land gently rolling. Soil 2nd rate

East on remeasure line between Secs 10 & 15
 40.00 Set temp. 1/4 Sec corner
 79.75 Intersect N & S line 70 links north of
 Sec corner
 N 89° 30' W on true line between Secs 10 & 15.
 13.00 In view of trail bears N & S across hill
 39.87 Set post for 1/4 Sec corner in corner of
 Earth 8° as per instructions
 79.75 The corner to Secs 9, 10, 15 & 16
 Top of hill
 Land hilly Soil 2nd rate

V. I. N. P. 288

617

Main North between Secs 9810
4000 ^{Seequa hill} Variation 19° 45' East
Set post for 1/4 Sec corner in mound
of Earth &c as per instructions
8000 Set post for corner to Secs to 3, 4, 9, 8, 10
in mound of Earth &c as per
instructions. Foot of hill
Level hilly. Soil 2nd rate

East on range line between Secs 3810
4000 Set post for temp 1/4 Sec corner
8000 Intersect N 89° 31' W line 20 links
North of Sec corner
N 89° 31' W on true line between Secs 3810
4000 Set post for 1/4 Sec corner in mound
of Earth &c as per instructions
Spring bears S 40° W 25 chs
dist
8000 Set post for corner to Secs 3, 4, 9, 8, 10
Level. Level Soil 1st rate

18

618

2nd N.

R. 28. E.

chain north on remayne line between Secs 3 & 4
Variation 20° 30' East

40.00 Set post for temp 1/4 sec corner

80.30 Intersect north boundary at the corner
to Secs 3 & 4

South on true line between Secs 3 & 4

40.00 Set post for 1/4 sec corner in name
of Earth & Co as per instructions

80.30 The corner to Secs 3, 4, 9 & 10

Level Soil 1st rate

October 17th 1859

G. N. O. 288.

19
619

North between Secs 28 & 33

- 4000 Set post for 1/4 Sec corner in Mound of Earth
as per instructions
- 8000 Set post for corner to Secs 28, 29, 32 & 33 in
Mound of Earth as per instructions
Land Level rat. Level
-

Easton remainder between Secs 28 & 33

- 4000 Set Trip 1/4 Sec corner
- 7950 Intersect N & S Line 70 buks North of
Sec corner
- 18930' W on true line between Secs 28 & 33
ascend hill
- 8975 Set post for 1/4 Sec corner in Mound of Earth as
per instructions
- 7950 The corner to Secs 28, 29, 32 & 33
Land gently rolling
Soil Level rat.

Chains North between Secs 28829

Variation 19° East

40.00 Set post for $\frac{1}{4}$ sec corner in corner
of Earth & as per instructions

80.00 Set post for corner to Secs 20, 21, 28829
in corner of Earth & as per instructions
Land gently rolling Soil good 2nd rate

Easton remainder line between Secs 21 & 28

40.00 Set post for $\frac{1}{4}$ sec corner

79.60 Intersect N & S line 70 links north of
Sec. corner

$N 89^{\circ} 30' W$ on true line between Secs 21 & 28
at corner hill

39.80 Set post for $\frac{1}{4}$ sec corner in corner of Earth

? 80 as per instructions

79.60 The corner to Secs 20, 21, 28 & 29

Land gently rolling Soil good 2nd rate

- North between Secs 20 & 21
 Variation 1930' East
- chains
 40.00 Set post for 1/4 sec corner in corner of
 Earth & as per instructions
- 80.00 Set post for corner to Secs 16, 17, 20 & 21
 in corner of Earth & as per instructions
 Landed level. Soil 1st rate
-
- Eastward narrow line between Secs 16 & 21
- 40.00 Set post for temp. 1/4 sec corner in corner
- 80.06 Intersect N & S Line 78 links north
 of corner
- N 89° 27' W. Old true line between Secs 16 & 21
 Jessena Hill
- 40.00 Set post for 1/4 sec corner in corner of
 Earth & as per instructions
- 80.06 Foot of hill The corner to Secs 16, 17, 20 & 21
 Landed hilly Soil 2nd rate

Ch. 2. N. P. 28. E.

chains North between Secs 16 & 17

Variation 20° East

40.00 Set post for 1/4 sec corner in Mound of Earth & c
as per instructions

80.00 Set post for corner to Secs 8, 9, 16 & 17
in Mound of Earth & c as per instructions
Land gently rolling Soil 1st rate

East on reman line between Secs 9 & 16

(Variation 20° East

40.00 Set temp 1/4 sec corner

80.60 Diver set N & S line 70 links north of
Sec corner

N 89° 30' Word true line between Secs 9 & 16

15.00 Seeena hill

40.30 Set post for 1/4 sec corner in Mound of Earth & c
as per instructions

80.60 The corner to Secs 8, 9, 16 & 17. Foot of hill

Land hilly Soil good 2nd rate

chains North between Secs 889

Variation 20° East

40.00 Set post for 1/4 Sec corner in mound of earth

8° as per instructions

Level gently rolling

80.00 Set post for corner to Secs 4. 5. 889

in mound of earth 8° as per instructions

Level Level Soil good 2nd rate

East or remainder line between Secs 489

Variation 19° East

40.00 Set temp 1/4 Sec corner in mound of

earth 8° as per instructions

80.90 Intersect N & S Line 7 links north of Sec corner

N $89^{\circ} 37'$ W on true line between Secs 489

40.45 Set post for 1/4 Sec corner in mound of earth

8° as per instructions

80.90 The corner to Secs 4. 5. 889

Level gently rolling

Soil 1st rate

chains North on rancon line between Secs 485-

Variation 19° East

40.00 Set temp. 1/4 sec corner ~~in ground~~

80.80 Intersect North boundary 42 links East of
Sec corner

N. 18° East on true line between Secs 485-

40.80 Set post for 1/4 sec corner in corner of East

47.70 Links bears N. E. & S. W

80.80 Set corner to Secs 485, 889.

Land gently rolling. Soil 1st rate
October 8th 1859

chains North between Secs 29 & 32

4000 Set post for $\frac{1}{4}$ Sec corner in Mound of Earth & as per instruction

8000 Set post for corner to Secs 29, 30, 31 & 32 in Mound of Earth & as per instructions
Level Soil 1st rate

East on random ^{Line} between Secs 29 & 32

4000 Set post for ~~post~~ $\frac{1}{4}$ Sec corner in Mound

8000 of Interest at N & S line 68 links North of Sec corner

N 89° 31' W on true line between Secs 29 & 32

4000 Set post for $\frac{1}{4}$ Sec corner in Mound of Earth & as per instructions

8000 Set post for corner to Secs 29, 30, 31 & 32

Q. N. P. 28. E.

Chains West on random line between Secs 30 & 31

40.00 Set Lump 1/4 Sec corner

79.40 Intersect West boundary 70 links north
of Sec corner

N 89° 30' E on true line between Secs 30 & 31

39.40 Set post for 1/4 Sec corner in Monong
Earth & as per instructions

79.40 They corner to Secs 29, 30, 31 & 32

Land gently rolling Soil 2nd rate

North between Secs 29 & 30

Variation 20° East

40.00 Set post for 1/4 Sec corner in Monong
Earth & as per instructions

80.00 Set post for corner to Secs 19, 20, 29 & 30
(in) Monong of Earth & as per instructions
Emergently rolling Soil 1st rate

J. W. P. D. E.

27
627

chains East on remainder Line between Secs 20 & 29
40.00 Set post for temp. 1/4 Sec corner in corner
80.00 Intersect N & S line 70 links north of
Sec corner.

N 89° 30' W on true line between Secs 20 & 29
40.00 Set post for 1/4 Sec corner in corner of
Earth & as per instructions
80.00 They corner to Secs 19, 20, 29 & 30
Land gently rolling Soil 1st rate

West on remainder line between Secs 19 & 30
40.00 Set post for temp. 1/4 Sec corner
80.00 Intersect West boundary at corner
East on true line between Secs 19 & 30
40.00 Set post for 1/4 Sec corner in corner of
Earth & as per instructions
80.00 They corner to Secs 19, 20, 29, & 30
Land gently rolling
Soil 1st rate

J. Q. N. P. S. & C.

chains North between Secs 17 & 20 East
Variation $19^{\circ}30'$ East

4000 Set post for $\frac{1}{4}$ Sec corner in Monna of Earth
& as per instructions

8000 Set post for corner to Secs 17, 18, 19 & 20
in Monna of Earth & as per instructions
Sena Level Soil 1st rate

chains East on remaon line between Secs 17 & 20

4000 Set post for temp. $\frac{1}{4}$ Sec

7941 Intersect N & S. Line 70 links north of Sec corner

$N 89^{\circ}30'$ W or true line between Secs 17 & 20

3970 Set post for $\frac{1}{4}$ Sec corner in Monna of
Earth & as per instructions

7941 The corner to Secs 17, 18, 19 & 20

Same gently rolling. Soil 1st rate

October 9th 1859

Chains Westward resection line between Secs 18 & 19
 40.00 Set post for ^{temp} 1/4 Sec corner in ~~the~~ ^{the} ~~middle~~ ^{middle} of East
 79.35 Intersect West boundary at corner
 East or true line between Secs 18 & 19
 39.35 Set post for 1/4 Sec corner in ^{middle} ~~middle~~
 of East & as per instructions
 79.35 The corner to Secs 17, 18, 19 & 20
~~in mound of earth & as per instructions~~
 Same Level Soil ^{1/4} rate

North between Secs 17 & 18

Variation 20° 10' East

40.00 Set post for 1/4 Sec corner in mound
 of Earth & as per instructions
 80.00 Set post for corner to Secs 17, 18, 19 & 20
 in mound of Earth & as per instructions
 Same Level Soil ^{1/4} rate

O. G. W. P. 28. E.

chains East or removed line between Secs 8817

4000 Set post for temp $\frac{1}{4}$ Sec corner

7941 Intersect N & S line 70 links north of Sec corner

A $89^{\circ}30'$ W. or true line between Secs 8817

3971 Set post for $\frac{1}{4}$ Sec corner in corner of Earth & as per instructions

7941 The corner to Secs 78, 17818

Land Level Soil 1^{st} ~~rate~~

West or removed line between Secs 7818

4000 Set post for temp $\frac{1}{4}$ Sec corner

7920 Intersect West boundary at corner

East or true line between Secs 7818

3920 Set post for $\frac{1}{4}$ Sec corner in corner of

Earth & as per instruction

7920 The corner to Secs 78, 17818
Land Level Soil 2^{nd} rate

chains North between Secs 788

Variation 20° 20' East

40.00 Set post for 1/4 Sec corner in corner of
Earth 8° as per instructions

80.00 Set post for corner to Secs S. 6. 788
in corner of Earth 8° as per instructions
Same Level Soil 1st rate

East on random line between Secs 588

40.00 Set post for temp 1/4 Sec corner

79.68 Intersect East boundary 42 links north
of Sec corner

N 89° 42' W on true line between Secs 588

32.50 Iron nail bears N E & S W

39.84 Set post for 1/4 Sec corner in corner of
Earth 8° as per instructions

79.68 The corner to Secs S. 6. 788
Same Level Soil 1st rate

T. 2, N. P. 28, E.

chains West on random line between Secs 687

40.00 Set post for temp 1/4 Sec corner

79.00 Intersect West boundary at corner
to Secs 687

East on true line between Secs 687

39.00 Set post for 1/4 Sec corner in *Monna*
of Earth &c as per instructions

79.00 The corner to Secs 5, 6, 7 & 8

Land gently rolling Soil 1st rate

North on random between Secs 5 & 6

Variation 193° 3' East

40.00 Set post for temp 1/4 Sec corner

79.97 Intersect North boundary 60 links East
of Sec corner

126' East on true line between Secs 5 & 6

39.97 Set post for 1/4 Sec corner in *Monna*
of Earth &c as per instructions

79.97 The corner to Secs 5, 6, 7 & 8

Land level Soil 1st rate *Same*

October 10th 1859

General Description

The quality of Land is gently rolling Prairie (Not a tree in the Township) covered with a thick growth of Bunch Grass There are numerous well Springs of clear fresh water

This Township will admit of a Large Settlement ~~and should be settled~~

List of Names

A list of the names of the men employed to assist in measuring or marking the lines and corners described in the foregoing field notes of Township No 2 North of the Base Line of Range No 28 East of the Willamette Meridian showing the respective capacities in which they acted

- Allen Thompson (Chairman)
- William Godamkee "
- Benj Athey (Amen)

We hereby certify that we assisted
David P Thompson deputy
Surveyor in Subdividing Township
No. 2 North of Range No 28 East
of the Millenette Meridian and
that said Township has been in all
respects to the best of our knowledge
and belief well and faithfully
Surveyed and the boundary monuments
planted according to the instructions
furnished by the Surveyor General

Allen Thompson
William Gedamke
Benjamin They

Sworn and subscribed to before
me at Dallas City this 18th day
of October 1859

W B Mowder
County Clerk
Wasco County Tex

I David P Thompson deputy Surveyor
do Solemnly Swear that in pursuance of
a contract with W. W. Chapman Surveyor
of the public lands of the United States
in the State of Oregon bearing date the
22nd day of July 1859 and in strict
conformity to the laws of the United States
and the instructions furnished by the
Surveyor General I have faithfully
Surveyed the Subdivision lines in
Township No. 2 North of the base line of
Range No. 28 East of the Willamette Meri-
dian in the State aforesaid and do
further Solemnly Swear that the foregoing
are the true and original field notes of such
Survey

David P. Thompson
Surveyor
Sworn and Subscribed to before me this
1st day of November 1859

Salem Oregon L. F. Carter
Not. Pub.

Surveyor General's Office,

Eugene City, January 21 1860

The foregoing field notes of the survey of the Subdivision lines of Township 2 North, of Range 28 East of the Willamette Meridian, Oregon, executed by David F. Thompson, deputy Surveyor, under his contract of the 22^d day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

A. A. Chapman
Surveyor Genl. Oregon