

470

Field Notes of the Exterior
boundaries of Township, 2 North
of Range 30 East of the Willam-
ette Meridian by David P
Thompson deputy Surveyor under
his contract bearing date the 22nd
day of July 1859.

T. W. R. & Co. E.

471

Beginning at the post the established
corner to Townships 1 & 2 North
of Ranges 29 & 30 East.

I run
chains North between Secs 31 & 36
Variation 18° 30' East

40.00 Set post for 1/4 Sec corner in mound
of Earth with charred Stake & as per
instructions

80.00 Set post for corner to Secs 30, 31, 25
& 36 in mound of Earth & as per
instructions

Land gently rolling
Soil good & no rate

August 18th 1859

12

472

N. 2. N. P. 30. E.

Chains North between Secs 25 & 30

Variation 19° 30' East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound of Earth &c as per instructions

80.00 Set post for corner to Secs 24, 25, 19, & 30 in mound of Earth &c as per instructions

Land gently rolling
Soil good rate

North between Secs 19 & 24

Variation 18° 05' East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound of Earth with pits trench &c as per instructions

80.00 Set post for corner to Secs 18, 19, 13 & 24 in mound of Earth &c as per instructions

Land gently rolling Soil good
rate

O. G. W. R. 30. E. 13 51

473

chains North between Secs 13 & 18
Variation 19° East
3460 Paviors bears N. W. & S. E.
4000 Set post for $\frac{1}{4}$ Sec corner in mound
of Earth &c as per instructions
8000 Set post for corner to Secs 12, 13,
7 & 18 in mound of Earth with
pits trench &c as per instructions
Land gently rolling Grass
Previous Soil good & $\frac{1}{2}$ rate

North between Secs 7 & 12
Variation $18^{\circ} 15'$ East
4000 Set post for $\frac{1}{4}$ Sec corner in
mound of Earth &c as per instruc-
- tions
8000 Set post for corner to Secs 6, 7, 11 & 12
in mound of Earth with pits
trench &c as per instructions
Land gently rolling
Soil good & $\frac{1}{2}$ rate
August 18th 1859

17 T. S. N. R. 30. E.

474

chains North between Secs 18 & 19

Variation 19° East

3700 Rains bears N. E. & S. W

4000 Set post for ^{14 Sec} corner in corner of

Earth & as per instructions

7400 ^{Super bottom bears E & W} Set post for corner to Townships

2 & 3 North of Ranges 29 & 30 East

in corner of Earth with pits trench

& as per instructions

Land rolling

Soil good ¹⁴ rate

From the corner to Township 283

North of Ranges 29 & 30 East I run

a range line between said Townships

Setting half mile and a mile posts at

4000 and 8000 chains

I find the length of the line

to be 6 miles 6 chains and 30

links and the falling to be 80 links

South of Township corner

List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 182 North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)
 Allen Thompson "
 Benj. Athey Axeman

We hereby certify that we assisted
 David P. Thompson deputy surveyor
 in surveying the Exterior boundaries
 of Townships Nos 1 & 2 North of the
 Base Line of Ranges Nos 28, 29, &
 30 East of the Willamette Meridian
 and that said Townships have been
 in all respects to the best of our
 knowledge and belief well and faithfully
 surveyed and the boundary monuments
 planted according to the instructions
 furnished by the Surveyor General

D. J. Fournell

Allen Thompson

Benjamin H. H. H.

Sworn and Subscribed to before
 me this 18th day of October 1859

W. C. Mowbray

County Clerk
 Wasco County Oregon

I David P. Thompson deputy Surveyor do
 Solemnly Swear that in pursuance of
 a contract with W. W. Chapman Surveyor
 of the public Lands of the United States
 in the State of Oregon bearing date
 the 22nd day of July 1859 and in strict
 conformity to the laws of the United States
 and the instructions furnished by the said
 Surveyor General I have faithfully surveyed
 the exterior boundaries of Townships Nos.
 18 & 19 North of the Base Line of Ranges 28
 29 & 30 East of the Willamette Meridian in the
 State aforesaid and do further Solemnly
 Swear that the foregoing are the true and original
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1st day
 of November 1859 at Salem Oregon
 L. C. White
 Not Pub

Surveyor General's Office,

Eugene City January 31st 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22^d day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman
Sur. Genl. of Oregon.