

Field Notes of the Survey of the
Exterior boundaries of Township 2 North
of Range 29 East of the Willamette
Meridian in the ^{1/4 State} Territory of Oregon
by David P. Thompson Deputy Sur-
veyor under his contract "No. 83"
bearing date the 22nd day of July
1859

29
489
S. 2. N. T. 29. E.

chains North between Secs 7 & 12

Variation $20^{\circ}30'$ East

3.30 Prairie area Trail bears S.W. & N.E.

4000 Set post for $\frac{1}{4}$ Sec corner in corner of Earth
 8° as per instructions

8000 Set post for corner to Secs 6, 7, 18, 12
in corner of Earth 8° as per instructions
Land gently rolling
Soil good & rate

North between Secs 1 & 6

Variation $19^{\circ}15'$ East

7.40 Indian Trail bears N.E. & S.W.

4000 Set post for $\frac{1}{4}$ Sec corner in corner of Earth
 8° as per instructions

8000 Set post for corner to Township 2 & 3 North
of Range 28 & 29 East in corner
of Earth 8° as per instructions

Variation $20^{\circ}14'$ East

Land gently rolling

Soil good & rate

August 24th 1859

From the corner to Townships 28³ North
of Ranges 288 29 East I run a
random line between said Townships
Setting, ^{temporary} half mile and mile post
at 4000 and 8000 chains

I find the Township line to be 6 miles
8 chains and 70 links and the
falling to be 400 links South of corner
The correction will therefore be 8.70 links
West and $66\frac{2}{3}$ links North per mile

491 T. 2 W. R. 29 E.

From the Established corner to Township
 283 North of Range 29830 East Quad
 S 89° 32' W on true line between Secs 18 36
 chains Variation 19° 30' East
 2800 Leave Bottom bears N. W. & S. E.
 4000 Set post for ^{1/4} Sec corner in mound of Earth
 8° as per instructions
 8000 Set post for corner to Secs 1, 2, 35 & 36
 in mound of Earth 8° as per instructions
 Land gently rolling
 Soil good & fertile

S 89° 32' W on true line between Secs 2835
 Variation 20° East
 4000 Set post for 1/4 Sec corner in mound of
 Earth 8° as per instructions
 8000 Set post for corner to Secs 2 3 34 & 35
 in mound of Earth 8° as per instructions
 Land gently rolling
 Soil good & fertile

North between Secs

389°32' W on true line between Secs 38 & 34
chains Variation 20° E

3.75 Indian Trail bears N & S

40.00 Set post for 1/4 Sec ~~Post~~ in mound
of Earth &c as per instructions

42.00 Indian Trail ~~bears~~ & Ravine bears
North & South

80.00 Set post for corner to Secs 34, 33, & 34
in mound of Earth &c as per instructions
Land gently rolling

Soil good & granite

389°32' W on true line between Secs 48 & 33
Variation 19°50' East

40.00 Set post for 1/4 Sec corner in mound of Earth
&c as per instructions

80.00 Set post for corner to Secs 45, 37, & 33
in mound of Earth &c as per instructions
Land good & granite

So

- chains 8933' ~~W on~~ true line between Secs 3832
Variation 20 $\frac{1}{4}$ ° East
- 470 Indian Trail bears N & S Spring bears
South 15.00 chains ^{dist}
- 4000 Set post for $\frac{1}{4}$ Sec corner in mound of
Earth &c as per instructions
- 8000 Set post for corner to Secs. 5. 6. 31832
Land Soil &c
Soil good @ one rate

- 8933' W on Line between Secs 6831
Variation 19 $\frac{3}{4}$ ° East
- 16.00 Indian Trail bears N & S
- 40.00 Set post for ^{$\frac{1}{4}$ Sec} corner in mound of
Earth &c as per instructions
- 80.00 Indian Trail bears N E & S W
- 8870 Intersect corner to Township 283
North of Ranges 288 29 East
Land gently rolling
Soil good @ one rate
August 25th 1859

General Description ³⁴

494

The quality of Land in this Township is good 2nd rate rolling Prairie covered with a thick growth of Bunch Grass. There are numerous Springs in this Township.

This Township will admit of considerable settlement and therefore should be subdivided.

Field Notes of the Survey of the Exterior boundaries of Township 1 North of Range 28 East of Willamette Meridian, in the State of Oregon by David P. Thompson deputy Surveyor under his contract No 83, bearing date the 23rd day of July 1859

List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 182 North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)
 Allen Thompson "
 Benj. Athey Axeman

We hereby certify that we assisted
 David P. Thompson deputy surveyor
 in surveying the Exterior boundaries
 of Townships Nos 1 & 2 North of the
 Base Line of Ranges Nos 28, 29, &
 30 East of the Willamette Meridian
 and that said Townships have been
 in all respects to the best of our
 knowledge and belief well and faithfully
 surveyed and the boundary monuments
 planted according to the instructions
 furnished by the Surveyor General

D. J. Fournell

Allen Thompson

Benjamin H. H. H.

Sworn and Subscribed to before
 me this 18th day of October 1859

W. C. Mowbray

County Clerk

Wasco County Oregon

I David P. Thompson deputy Surveyor do
 Solemnly Swear that in pursuance of
 a contract with W. W. Chapman Surveyor
 of the public Lands of the United States
 in the State of Oregon bearing date
 the 22nd day of July 1859 and in strict
 conformity to the laws of the United States
 and the instructions furnished by the said
 Surveyor General I have faithfully surveyed
 the exterior boundaries of Townships Nos
 18 & 19 North of the Base Line of Ranges 28
 29 & 30 East of the Willamette Meridian in the
 State aforesaid and do further Solemnly
 Swear that the foregoing are the true and original
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1st day
 of November 1859 at Salem Oregon
 L. C. White
 Not Pub

Surveyor General's Office,

Eugene City January 31st 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22^d day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman
Sur. Genl. of Oregon.