

Field Notes of the Survey of
Township No 1 North of Range
No. 29 East of the Willamette
Meridian by in the State of
Oregon by David P Thompson
deputy Surveyor under his
contract No. 83 bearing date
the 22nd day of July 1859

chains North between Secs 7 & 12

Variation $18^{\circ}40'$ East

4000 Set post for $\frac{1}{4}$ Sec corner in Mound of Earth &c as per instructions

Variation $19^{\circ}20'$ East

8000 Set post for corner to Secs 6, 7, 11 & 12 in Mound of Earth &c as per instructions

Some gently rolling

Soil good & moderate

North between Secs 1 & 6

Variation 20° East

4000 Set post for $\frac{1}{4}$ Sec corner in Mound of Earth &c as per instructions

8000 Set post for corner Township

1 & 2 North of Ranges 28 & 29

East in Mound of Earth &c as per instructions

Some gently rolling

Soil good & moderate

August 22nd 1859

From the corner to Township 182
 North of Ranges 28 & 29 East and
 a random line between said
 Townships setting half mile and
 mile posts at 4000 and 8000
 chains I find the line to be
 6 miles & 60 chains in length
 and the falling to be 300 lbs
 South of Township corner
 The correction will therefore be 6 chains
 West and 30 lbs North per mile

Note I rechecked the South boundary
 on the Base Line and find it
 to be 6 miles 6 chains and 69 lbs
 in length

23 O. J. A. P. J. E.
483

chain $S 89^{\circ} 39' W$ on true line between Secs 1 & 36
Variation $18^{\circ} 30'$ East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound
of Stone

56.50 Prairie bears N. W. & S. E.

57.00 Indian Trail from Anmatilla to Butter
Creek bears N. W. & S. E.

80.00 Set post for corner to Secs 1, 2, 3 & 36
in mound of Earth & as per instructions
Land hilly. Soil 2nd rate

$S 89^{\circ} 39' W$ on true line between Secs 2 & 35
Variation 20° East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound of
Earth & as per instructions

80.00 Set post for corner to Secs 2, 3, 34 & 35
in mound of Earth & as per
instructions

Land gently rolling
Soil good 2nd rate

J. W. P. 29, E. 24

484

chains $S 89^{\circ} 39' W$ on true line between Secs ³³⁸³⁴
Variation 20° East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound
of Earth 8° as per instructions

80.00 Set post for corner to Secs 3, 4, 33834
in mound of Earth 8° as per
instructions

Land good 2^{nd} rate. Rolling

$S 89^{\circ} 39' W$ on true line between Secs 4833
Variation $21^{\circ} 30'$ East

40.00 Set post for $\frac{1}{4}$ Sec corner in mound
of Earth 8° as per instructions

80.00 Set post for corner to Secs
4, 5, 32833 in mound of Earth

Land gently rolling

Soil good 2^{nd} rate

25- T. N. R. 29. E.
485

chains S 89° 39' W on true line between Secs 5 & 32
Variation 20° 30' East

40.00 Set post for ^{1/4} Sec corner in mound of earth
8° as per instructions

80.00 Set post for corner to Secs 5, 6, 31 & 32
in mound of earth 8° as per instructions
Land gently rolling
Soil good 2nd rate

S 89° 39' W on true line between Secs 6 & 31
Variation 21 3/4 East

40.00 Set post for 1/4 Sec corner in mound of
Earth 8° as per instructions

86.00 The corner to Townships 1 & 2 North
of Ranges 28 & 29 East
Variation 20° East

Land gently rolling

Soil good & ^{2nd} rate August 23rd 1859

General Description

The quality of Land in this Township is good 2nd
rate high rolling Prairie covered with Bush
Grass and will admit of some settlement and
should be subdivided

List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 18² North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)
 Allen Thompson "
 Benj. Athey Axeman

We hereby certify that we assisted
 David P Thompson deputy surveyor
 in surveying the Exterior boundaries
 of Townships Nos 1 & 2 North of the
 Base Line of Ranges Nos 28, 29, &
 30 East of the Willamette Meridian
 and that said Townships have been
 in all respects to the best of our
 knowledge and belief well and faithfully
 surveyed and the boundary monuments
 planted according to the instructions
 furnished by the Surveyor General

D. J. Powell

Allen Thompson

Benjamin H. H. H.

Sworn and Subscribed to before
 me this 18th day of October 1859

W. C. Mendenhall

County Clerk
 Wasco County Oregon

I David P. Thompson deputy Surveyor do
 Solemnly Swear that in pursuance of
 a contract with W. W. Chapman Surveyor
 of the public Lands of the United States
 in the State of Oregon bearing date
 the 22nd day of July 1859 and in strict
 conformity to the laws of the United States
 and the instructions furnished by the said
 Surveyor General I have faithfully surveyed
 the exterior boundaries of Townships Nos
 18 & 19 North of the Base Line of Ranges 28
 29 & 30 East of the Willamette Meridian in the
 State aforesaid and do further Solemnly
 swear that the foregoing are the true and original
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1st day
 of November 1859 at Salem Oregon
 L. C. White
 Not Pub

Surveyor General's Office,

Eugene City January 31st 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22^d day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman
Sur. Genl. of Oregon.