

Plotted -

167

Ex

Field notes of the subdivision
of lines in Township No 1 north
of range 29 East of the Willamette
Meridian, in the State of
Oregon, by L. F. Carter, deputy sur.
under his contract - dated 11th
day of May 1860.

Commenced May 12th 1860

Completed May 26th 1860

Index diagram

6	3	3	22	4	17	3	11	2	6	1
30	+	29	+	21	+	16	+	11	+	5
7	29	8	21	9	16	10	10	11	5	12
28	+	28	+	21	+	15	+	10	+	4
18	27	17	20	16	15	13	9	14	4	13
27	+	26	+	20	+	14	+	9	+	3
19	26	20	19	21	14	22	8	23	3	24
25	+	25	+	19	+	13	+	8	+	2
30	24	29	18	28	13	27	7	26	2	23
24	+	23	+	18	+	12	+	17	+	1
31	23	32	17	33	12	34	6	33	1	36

J. A. M. Thompson & J. P. W. Bell
do solemnly swear that I will
faithfully execute the duties of
of chairman; that I will level
the chain upon uneven ground,
and plumb the tall pins, whether
sticking or scraping the same;
that I will report the true
distance to all notable objects,
and the true lengths of all lines
that I assist in measuring, to
the best of my skill and ability

Allen M. Thompson
J. P. W. Bell

Subscribed and sworn to before me on J. 1. 1860

at 29 East. This 12th day of May 1860

L. J. Carter

Not. Pub.

I G. C. Litchfield do solemnly
swear that I will well and
truly perform the duties of
Clerk, according to instructions
given me, and to the best of my
skill and ability.

G. C. Litchfield

Subscribed and sworn to before me in

Town of E. This 12th day of May 1860

A. J. Carter

Not. Pub.

7 177 Township 1 N R 29 East

East on random line between Secs. 26 & 35

Run 19° 45' East

40.00 Set temp. gr. section post

79.70 intersect line 40 lbs south of corner

S 89° 45' W on true line between Secs 26 & 35

39.85 Set post for gr. sec. corner & built
mounds of earth as per instructions

79.70 to section corner

Land rolling soil 2^d rate

North between Sections 26 & 27

40.00 Set post for gr. sec. cor. & built
mounds of earth as per instructions

80.00 Set post for corner to sections 22, 23

26 & 27 & built mounds of earth as
per instructions

Land gently rolling soil 2^d rate

Township 1 N R 29 East

18
188

East on random line between Secs. 28 & 33

Due 20° East

40.00 Set temp gr. sec. post

80.14 intersect line 14 lks N of cor. X

N 89° 54' W on true line between Secs. 28 & 33

40.07 Set post for gr. sec. cor. & built mound
of earth as per instructions

80.14 to section corner

Land broken and stony
soil 2nd and 3rd rate

North between sections 28 & 29

0.00 Ascend hill steps S W

40.00 Set post for gr. sec. cor. & built ^{mound} + 300
of stone as per instructions

53.00 top of hill E & W + 200

80.00 Set post for corner to Secs. 20, 21

28 & 29 & built mound of earth
as per instructions

Land rough soil 2nd & 3rd rate

Township 1 N R 29 E

22

192

East on random line between secs 4 & 9

Dir. $20^{\circ}15'$ East

40.00 set temp. q. sec. cor.

80.00 intersect at corner

West on true line between secs. 4 & 9

40.00 set post for q. sec. cor. & built

mound of earth as per instructions

80.00 to section corner

And broken line $2^{\circ}30'$ rate

North on random line between secs. 4 & 5

40.00 set temp. q. sec. corner

77.40 intersect town line 93 lbs east

of post -

S 40° E on true line between sec. 4 & 5 -

37.40 set q. sec. cor. & built mound

earth as per instructions

77.40 intersect line at corner

Land partly descending to
the north said post 12° rate

General description

The quality of the land in this township is 2^d rate, except along the Bottom Fording on Butte creek, a small stream entering the township in sec 32, and leaving it in the west boundary in sec 30. There is no timber except along this stream, consisting, ^{of} cotton wood, birch, willow and alder. It is well adapted to grazing purposes, the upland being covered with grass.

List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines & corners described in the foregoing field notes of township 1 N of R 29 E of the Willamette meridian, showing the respective capacities in which they acted

A. M. Thompson	Chairman
P. W. Bell	do
J. C. Atchfield	Assessor

We hereby certify that we assisted J. F. Carter, deputy surveyor, in surveying the subdivisional lines of township No 1 N of R 29 East of the Willamette meridian, and that said Township has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Gen. General.

Allen M. Thompson

A. W. Bell

J. C. Litchfield

Subscribed and sworn to before me at

Oregon city this 12th day of June 1860

L. F. Carter

Not. Pub.

J. J. Hartie, deputy surveyor, do solemnly swear that in pursuance of a contract with W. W. Chapman Surveyor of the public lands of the United States in the state of Oregon, bearing date the 11th day of May 1860, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the subdivisional lines of Township 1 North of Range 29 East of the Willamette meridian, in the State aforesaid, and do further swear that the foregoing are the true and original field notes of such survey.

J. J. Hartie dep. sur.

Subscribed and sworn to before me at Eugene City this 26th day of June 1860

W. W. Chapman
 Secy Genl
 Oregon

Surveyor General's Office
Eugene City, July 13th 1860.

The foregoing field notes of the
Survey of the Subdivisions
of Township No 1 North of
Range No. 29 East of the
Willamette Meridian, State
of Oregon, executed by S. G.
Cartee, under his contract
of the 11th day of May 1860.
having been critically examined
the necessary corrections and
explanations made the said
field notes and the surveys
they describe are hereby ap-
proved

W. W. Chapman
Sur. Gen. of Oregon