

470

Field Notes of the Exterior  
boundaries of Township, 2 North  
of Range 30 East of the Willam-  
ette Meridian by David P  
Thompson deputy Surveyor under  
his contract bearing date the 22<sup>nd</sup>  
day of July 1859.



17 J. S. N. P. 30. E.

474

chains North between Secs 18 & 19

Variation 19° East

3700 Rains bears N. E. & S. W

4000 Set post for <sup>14 Sec</sup> corner in corner of

Earth & as per instructions

7400 <sup>Super bottom bears E & W</sup> Set post for corner to Townships

2 & 3 North of Ranges 29 & 30 East

in corner of Earth with pits trench

& as per instructions

Land rolling

Soil good <sup>11</sup> rate

From the corner to Township 283

North of Ranges 29 & 30 East I run

a range line between said Townships

Setting half mile and a mile posts at

4000 and 8000 chains

I find the length of the line

to be 6 miles 6 chains and 30

links and the falling to be 80 links

South of Township corner



O. W. P. 30. E.

15

475

S 89° 34' W on true line between Secs 1 & 36  
40.00 Set post for 1/4 Sec corner in mound  
of Earth & as per instructions  
80.00 Set post for corner to Secs 1, 2, 35  
& 36 in mound of Earth & as per  
instructions  
Land hilly  
Soil 2<sup>nd</sup> rate

S 89° 34' W on true line between Secs 2 & 35  
Variation 20° East  
40.00 Set post for 1/4 Sec corner in mound  
of Earth with pits trench & as per  
instructions  
80.00 Set post for corner to Secs 2, 3, 34  
& 35 in mound of Earth & as per  
instructions  
Land hilly  
Soil 2<sup>nd</sup> rate



16

476

D. J. A. R. 30. E.

chain  $S 89^{\circ} 54' W$  on true line between Secs 38 & 34  
Variation  $19^{\circ}$  East

4000 Set post for  $\frac{1}{4}$  Sec corner in mound of  
Earth &c as per instructions

8000 Set post for corner to Secs 3. 4. 33 & 34  
in mound of Earth &c as per instruc-  
tions

Land gently rolling,  
Soil good rate

$S 89^{\circ} 54' W$  on true line between Secs 48 & 33  
Variation  $18^{\circ} 30'$  East

4000 Set post for  $\frac{1}{4}$  Sec corner in mound  
of Earth &c as per instructions

8000 Set post for corner to Secs 4. 5. 32 & 33  
in mound of Earth &c as per  
instructions

Land gently rolling  
Soil good rate



O. G. W. R. 30. E.

17  
477

S 89° 34' W on true line between Secs 5 & 32  
chains Variation 19° 30' East

4000 Set post for  $\frac{1}{4}$  Sec corner in mound  
of earth 8° as per instructions  
of Secener bill

8000 Set post for corner to Secs 3 & 6  
31 & 32 in mound of Stone  
Lane hilly and stony  
Soil 3<sup>per</sup> rate

S 89° 34' W on true line between Secs <sup>6831</sup>  
Variation 20° 30' East

2200 Foot of hill enters bottom  
bears N W & S E

3000 Enter Timber

4000 quarter Sec corner in pond of water

Set utreap post 30 links west of  
true corner from which

(a) Birch 8 in diam bears N 3° W 17" East

(b) " 8 " " " S 70° W 18 " "

6383 Minatilla River 100 links wide runs  
N W







## List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 182 North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)  
 Allen Thompson "  
 Benj. Athey Axeman



We hereby certify that we assisted  
 David P. Thompson deputy surveyor  
 in surveying the Exterior boundaries  
 of Townships Nos 1 & 2 North of the  
 Base Line of Ranges Nos 28, 29, &  
 30 East of the Willamette Meridian  
 and that said Townships have been  
 in all respects to the best of our  
 knowledge and belief well and faithfully  
 surveyed and the boundary monuments  
 planted according to the instructions  
 furnished by the Surveyor General

D. J. Powell

Allen Thompson

Benjamin They

Sworn and Subscribed to before  
 me this 18<sup>th</sup> day of October 1859

W. C. Mowbray  
 County Clerk  
 Wasco County Oregon



I David P. Thompson deputy Surveyor do  
 Solemnly Swear that in pursuance of  
 a contract with W. W. Chapman Surveyor  
 of the public Lands of the United States  
 in the State of Oregon bearing date  
 the 22<sup>nd</sup> day of July 1859 and in strict  
 conformity to the laws of the United States  
 and the instructions furnished by the said  
 Surveyor General I have faithfully surveyed  
 the exterior boundaries of Townships Nos.  
 18 & 19 North of the Base Line of Ranges 28  
 29 & 30 East of the Willamette Meridian in the  
 State aforesaid and do further Solemnly  
 Swear that the foregoing are the true and original  
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1<sup>st</sup> day  
 of November 1859 at Salem Oregon  
 L. C. White  
 Not Pub



Surveyor General's Office,

Eugene City January 31<sup>st</sup> 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 + 2 North of Ranges 28, 29 + 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22<sup>d</sup> day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman  
Sur. Genl. of Oregon.