

Special Inst. No 2

Notes Names.

	Column	Page	Township	N. or S.	Range	E. or W.
✓ Anderson H.		193	7 N	9	W.	
✓ Botton D.		213	1 S	14	E	
458 Bylee Wm	44	131	2 N	1	W	
3254 Breggs O. M.	62	246	7 S	3	W	
Barlow J. K.	67	330	18 S	3	W	
1033 Carter Thos.		76	1 S	1	E	
6453 Dary Lewis	43	17	1 N	1	W	
7818 Davis Oli	42	22	2 N	2	W.	
✓ Davenport J. J.	37	343	21 S	10	W	
106 Field Ambrose		157	2 S	1	E	
2482 Greinsley R. D.	49	73	13 S	5	E	
5690 Gattens Wm	43	109	2 N	1	W	
84 p. 42 Gager J. D.	45	337	7 S	2	W	
Harper David	38	37	12 N	5	W	
7931 Hill James	43	101	7 N	4	W	
✓ Henderson L. P.	37	109	1 S	13	E	
✓ Hoque Thos G		258	12 S	5	W	
✓ Johnson Curtis		346	20 S	10	W	
680 Moore Robt	71	145	2 S	12	E	
✓ Martin Jos.		189	7 N	8	W.	
189 Lenox Ed. H.	42	11	1 N	1	W.	
4619 Platt Char	66	43	4 S	2	W	

Notes

IA

Names

Volume

Page

Turnovers

Nr D

Range

Dir

	Rudie Peter	38	205	1	S	14	E
8044	Revenue Fran	37	230	2	S	5	E
	Scott Norman	65	180	7	S	4	W
	Stewart James	68	309	18	S	3	W
3569	Spelaw Beth	42	323	18	S	3	W
245	White John S	41	7	1	N	1	W
	Whitney Jonas	59	2	N	31	E	
	Warren F. M.	42	283	7	N	2	W



1 B

2

10
A C

1

Fischer
Special Instr'n

Special
Instruction

1

1C 10h

~~Manuscript~~

Field notes of the Survey
of the Jonas Whitney Dona-
tion land claim situated in
Township T^o 2 North Range
E^o 31 T^o 32 East Will Mer Oregon
by Jonas F. Moody deputy
Surveyor

I, Gevas L Moody Deputy
Surveyor do Solemnly swear
that I will well and faith-
fully Survey the donation
land claim of Jonas Whitney
located in ^{the} Twp No 2 North Rge
31 & 32 East of the Mill, Mer, Ore,

Gevas L Moody
Deputy Surveyor

State of Oregon }
County of Wasco } S.S.

Subscribed and sworn to before me this
14th day of Oct. 1871

W. Davenport
U.S. Court, Dist of Ore

I J. S. Kent and Geo W Renoe
 each speaking for himself do
 solemnly swear that I will
 faithfully execute the duties of
 Chain carrier that I will level
 the Chain upon uneven ground
 and plumb the Tally pins
 whether by sticking or by drop-
 ping the same, that I will re-
 port the true distance to all
 notable objects and the true length
 of all lines that I assist in
 measuring to the best of my skill
 and ability

J S Kent
 Geo W Renoe

State of Oregon }
 County of Wasco } S.S.

Subscribed and sworn to before me
 this 14th day of Oct. 1871

W Davenport
 U.S. Com. Dist of Ore

I O Hathaway do Solemnly
Swear that I will well and truly
perform the duties of Aseman
according to the instructions
given me and to the best of my
skill and ability

O. Hathaway

Sworn and subscribed
before me this 14th day
of October 18th 1871

M. Davenport
U. S. Com. Dist. of Ore.

Begin at the S.E. Corner of said cl.
in Sec. 19 T^h 2 North Range 32 E.
16.36 Chs East of Range line between
Ranges 31 & 32. Thence

West On South bdy of cl.

Var. 19° E.

16.36 Intersect Range line bet Rgs 31 & 32
30.00 Chs South of cor. to Sec. 18. 19
13 & 24

30.50 Set post in Stone mound for cor
to claim Thence

North On the West bdy of cl.

Var. 18° 30' E

30.00 Intersect Sec line bet. Secs. 13 & 24
T^h 2 N. R. 31 E. 14.14 Chs East of
corner to Secs. 13, 24, 18 & 19

40.00 Set post in Stone mound for
cor to claim Thence

West On South bdy of cl.

Var. 18° 45' E

29.50 Set post in Stone mound for
cor to claim Thence

North Cor West bdy of cl.

Var 19° E

49.50 Set post in Stone mound
for cor to claim + Thence
East Cor North bdy of claim

Var 19° E

40.00 Set post in Stone mound for
cor to cl, + Thence

South Cor East bdy of cl.

Var 19° E

49.50 Set post in Stone mound for
cor to cl, Thence

East Cor North bdy of cl,

Var 19° 75' E

3.64 Intersect Range line 10.00 Chs North
of Cor to Secs 18, 19, 13, 7, 24

20.00 Set post in Stone mound for
cor to cl, Thence

S. 1/4 Cor East bdy of cl.

Var 19° E

10.00 Intersect Sec line bet. Secs 18 &

19 16.36 Chs East of cor to 18, 19, 13, 7, 24

8

8

40.20 To post in Stone mound for
place of beginning

~~Oct 14th 1891~~
Nov 14th 1891

We hereby certify that we assisted
 Jonas G. Moody Deputy Surveyor
 in Surveying the Donation
 Claim of Jonas Whitney in
 Tp 20 S. R. 31 E. 32 E of the
 Willamette Meridian Oregon
 and that in our opinion the work
 was done according to the instruc-
 tions furnished said J. G.
 Moody by the Sur. Genl of Oregon.

Geo. W. Penoe Chairman
 J. S. Kent "
 O. Hathaway Assman

State of Oregon }
 County of Wasco } S.S.

Subscribed and sworn to
 before me this 1st day of
 December 1891

A. Holland
 Clk

I Jonas F. Moody deputy Surveyor
do Solemnly swear that I
have surveyed the Donation
land of Jonas Whitney located
in Tp. 2 North Rge. 31 T32 East
Till, Mer. Oregon. and that said
Survey has been executed in accor-
dance with the instructions
furnished by the Sur. Genl.

Jonas F. Moody
Deputy Surveyor

State of Oregon }
County of Wasco } S.S.

Subscribed and sworn to before me
this 29th day of July. 1873

~~Jonas F. Moody~~

A. Holland

Co. Clerk.

County of Marion
State of Ohio

vs.

Subscribed and sworn to before me a
justice of the peace on this 11th day of July 1871.

W. C. Lewis J. P.

371E