

Washington Transcripts made -

370

D. H. Murphy

3

Field notes of the survey of the
subdivision lines of Township
No 2 North of the base line of Ra-
nge No 31 East of the Willamette
Meridian in the State of Oregon
by Josiah A. Burnett, deputy
Surveyor under his contract No
92 bearing date the 12th day of
September 1860,

Commenced, ^{Oct.} 30th 1860.

Completed Oct. 28th 1860.

Rec'd Nov 19th 1860

Index

Referring the lines to the pages of the field notes
 To N R B. E. Williams's meridian

6 41	42	5 40	31	4 30	24	3 23	17	2 16	9	1	8
7 34	40	8 38	30	9 29	33	10 22	16	11 14	5	12	7
18 37	37	17 36	28	16 28	21	15 20	13	14 13	5	13	4
14 35	35	20 34	27	21 26	20	22 19	12	23 11	4	24	3
30 33	34	24 32	26	28 25	19	27 18	11	26 10	2	25	2
31 32	32	32 33	25	33 33	17	34 34	10	35 35	1	36	

[Faint handwritten notes at the bottom of the page, likely bleed-through from the reverse side.]

T₂ N R 31 E

Field notes of the subdivisions lines
in Township No 2 North Range 31
East, Willamette meridian

Subdivisions commenced October
20th 1800,

From the corner to Sec's 1, 2, 35 and 36
on the South Boundary of the Town-
-ship, I Run,

North between Sec's, 35 and 36

4000 Set post for 1/4 Sec. cor. drove chain
stake and raised mound with
trench as per instructions

8000 Set a post for cor to Sec's, 25, 26,
35 and 36, drove chain stake and
raised mound with trench as
per instructions.

Land Broken & Stony

East on a random line between
Sec's, 25 and 36,

L N R 31 E

Variation 1730' E

40.00 Set Temporary 1/4 Sec cor

79.84 Intersect East boundary of the Township 44 Ms North of the corner to Sec's 25 and 36, from which corner I Run

N 89 41 W on a true line between Sec's 25 and 36

39.92 Set post for 1/4 Sec. cor, drove charred Stake and raised mound with trench as per instructions

71.00 To a Dry Ravine course North,

79.84 The corner to Sec's 25, 26, 35 and 36

Land gently rolling grass hills
2^d rate soil

North between Sec's 25 and 26

40.00 Set a post for 1/4 Sec. cor, drove charred Stake and raised mound with trench as per instructions

40.20 To a Dry Ravine, course N 20 W

42.50 Foot of Stony hills, bears N 20 W

T2 N R 31 E.

and SE

4800 Enter broken Ravines (Small) going West

8000 Set post in Stony ravine for corner to Sec's. 23, 24, 25 and 26, and run a Stone monument as per instructions. Land South half pretty rolling 2nd rate soil. North 1/2 broken & Stony hills.

East on a Random line between Sec's 24 and 25

Variation, 20° 45' E.

4000 Set Temporary 1/4 Sec, cor.
7988 I intersect East boundary of Township, at the past. corner to Sec's 24 and 25, from which come @ Run.

West on a true line between Sec's 24 and 25,

3994 Set apart for 1/4 Sec cor, drove around stake and raised monument

4 374

T 3 N R 31 E

with trench as per instructions
1988 The corner to Sec's. 23, 24, 25 & 26
Land Broken and Stony

North between Sec's 23 & 24
2000 Loose Stony Ruins and other
grass slopes
4000 Set post for $\frac{1}{4}$ Sec, cor, drove
churned Stake and raised
mound as per instructions
8000 Set apart for corner to Sec's,
13, 14, 23 and 24, and raised
stone mound as per instruc-
-tions.

Land. good 2nd rate except
2000 chs South end of line.

Custom Random line between
Sec's. 13 & 24,

Variation $18^{\circ}30' E$

4000 Set Temporary $\frac{1}{4}$ Sec, cor,
1950 Interspersed East boundary of

T. N. R. 31 E

of the Township 12 M. North of
the corner, to Sec's. 13 and 24
From which corner Run
N 89° 55' W on a true line between
Sec's. 13 and 24,

0.50 Birch Creek 20 M. wide (at this time
dry) course North,

12.00 Leave Prairie Bottom, bearing N
and S.

15.50 Mr. Whitney's fence bearing N 48

39.75 Set Post for 1/4 Sec. cor. drove char-
red stake and raised mound
with trench as per instructions

79.50 The corner to Sec's. 13, 14, 23 and 24
Land pretty rolling grass hills, except
-ing Creek Bottom, which is 1st rate
soil.

North between Sec's 13 and 14

21.50 Indian Trail bearing N. W. & S. E

40.00 Set post for 1/4 Sec. cor. drove charred
stake and raised mound as per

6 376

T 2 N R 31 E

instructions

- 4725 A Bluff 30 feet high bearing E & W
4750 Foot of Bluff bearing E & W and
Entena Amaticas River bottom
4780 Entena Arica bearing E & W
5200 A House bears East 1000 chsdist
7800 ~~Left~~ bank of the Amaticas
River, 150 lbs wide, Rapid current
low banks, course West,
8000 Set post for corner to Sec's. 11,
12, 13 and 14, from which
A Cotton-wood 8 in dia bears N 30 E
15 lbs dist,
A Cotton-wood 4 in dia bears N 12 W dist
no other tree convenient. I therefore
Dug track as per instructions
Lana, River bottom 1st date,
the balance 2^d date soil

July 1377

T2 N R31 E

Easton Run down line between Sec's
12 and 13

Variation. 21°30' E

40.00 Set Temporary 1/4 Sec. cor.
74.50 Intersect East boundary of Iron
= ship 78 Ws North of the corner to
Sec's, 12 and 13, from which corner
down.

N 89° 27' W on a true line between
Sec's 12 and 13

39.75 Set post for 1/4 Sec. cor. drove charred
Stake and raised mound with
trench as per instructions

79.50 The corner to Sec's, 11, 12, 13 and 14
Land rolling 2nd rate soil

North between Sec's, 11 and 12,

2.00 Lower River bottom bearing E & SW

12.00 Foot of hill bearing E & SW

40.00 Set post for 1/4 Sec. cor. drove charred
Stake and raised Stone mound
with trench as per instructions

8 378

T2 N R 31 E

8000 Set post for corner to Sec's 12, 11
and 12. Drive around stake
and around stone mound with
touch as per instructions.
Land rolling grass hills 2^d rate
soil.

Oct 27th 1860

East on Random line between Secs
1 and 12

Variation 20.00' E

4000 Set Temporary 1/4 Sec, cor,
79.86 Intersected East boundary of
Township. 80 Mts North of the
corner to Sec's 1 and 12, from
which corner I Run

N 89.26' W on true line between
Secs 1 and 12

2200 A Wagon Road from Fort Dull
to Fort Walla Walla bears NW, SE

3493 Set a post for 1/4 Sec, cor, drive ch-
around stake and raise mound
with touch as per instructions

T. N. R. 31 E

79.86 The corner to Sec's. 1, 2, 11 and 12
Land level 2^d rate Soil.

North on a Random line between
Sec's 1 and 2

40.00 Set Temporary 1st Sec, cor,

80.30 Intersect the North boundary of
the Township 17th N East of the
corner to Sec's 1 and 2, from which
corner I Run.

50° 07' W on a true line between
Sec's. 1 and 2,

21.20 a Road from Wella Wella to Duffin bearing E & W
40.30 Set a post for 1st Sec, cor, Assoc. chard
Stake and raised Ground with
trench as per instructions

80.30 The corner to Sec's 1, 2, 11 and 12,
Land level 2^d rate Soil

Lat R 31 E

North between Sec's 34 and 35

- 4000 Set apart for $\frac{1}{4}$ Sec. cor. drove
churned Stake and raised mound
with trench as per instructions
- 8000 Set apart for corner to Sec's 26, 27, 34
and 35. Drove churned Stake and
raised mound with trench as per
instructions.

Land rolling 2nd Rate Soil

East on a Random line between Sec's
26 and 35

Variation, 20° 15' E

- 4000 Set Temporary $\frac{1}{4}$ Sec. cor.
7969 Intersected N 8 line 68 lbs North of
the corner to Sec's 25, 26, 35 and 36
from which corner I Run
N 89° 30' W on a True line between
Sec's 26 & 35.
- 3984 Set post for $\frac{1}{4}$ Sec. cor. drove churned
Stake and raised mound with

T₃ N R 31 E

trench as per instructions
 79.69 The corner to Sec's. 26, 27, 34 and 35
 Land rolling grass hills 2nd rate
 soil

1890 North between Sec's 26 and 27
 To a Dry Ravine Course N.E.
 40.00 Set a post for 1/4 Sec. cor. drove char-
 -ed stake, and raised mound with

trench as per instructions

42.50 To a Dry Ravine Course East
 80.00 Set a post for corner to Sec's. 22, 23,
 26 and 27, drove charred stake
 and raised mound with trench
 as per instructions

Land, broken 2nd & 3rd rate soil

East on a Random line between Sec's
 23 and 24,

Variation 20.00' E

40.00 Set a Temporary 1/4 Sec. cor.

To N R 31 E

7975 Intersection ^{N48} line 62 links north of the
corner to Sec's. 23, 24, 25 and 26 from
which corner I Run.

N 89° 34' W On a true line between
Sec's. 23 and 26

20.00 To a Dry ravine corner N E

3487 Set a post for 1/4 Sec. cor. drove
stake and raised stone mound
as per instructions.

7975 The corner to Sec's 22, 23, 26 & 27
Lined rolling 2nd rate soil

North between Sec's 22 and 23

41.00 Set a post for 1/4 Sec. cor. drove
churned stake and raised mound
as per instructions.

80.00 Set a post for corner to Sec's
14, 15, 22, and 23 drove churned
stake and raised mound
with truck as per instructions
Lined rolling grass hills 2nd rate soil

G 2 N R 31 E

East on a Random line between
See's 14 and 23

Variation 2,36' E

40.00 Set Temporary 1st Sec, cor,
79.80 Intersection N48 line 50 Mts North
of the corner to See's, 13, 14, 23 and
24 from which I Run.

N 89 39 W on a true line between
See's 14 and 23

21.00 To a Deep Rocky Ravine runs N.W.

39.90 Set a post for 1st Sec, corner drove
chard stake and raised mound with
the trees as per instructions.

79.80 The corner to See's, 15, 14, 23 and 22.
Land West half good 2^d, out soil
East half broken.

North between See's 14 and 15

6.25 Go the Top of a Bluff ^{300 feet high} on the
South and Left bank of the uninter-
ah river, bearing E & W, I offset
West, 1200 chs dist, thence I on offset line

14 384

T. N. R. 31 E

1475 chains

Offset East 12,000 chs dist and again
=ed ~~same~~ line. At the edge of River

21,00 bottom, bearing E & W

25,00 Left bank of Annetinus River
2000 chs wide, shallow, rapid current
runs West

27,00 Enter Mr. Combs's field bearing E & W

38,00 Leave field bearing E & W.

39,00 Leave River bottom and enter up
-lands bearing bearing E & W

40,00 Set a post for 1/4 Sec. Cor, drive chain
stake and raise a mound, with
trunk as per instructions

8000 Set a Post for cor to Sec's. 10, 11, 14
and 15, drive chain stake and
raise a mound with trunk as
per instructions

Easton Random line between Sec's
11 and 14

Variation 19° 30' E

40,00 Set a Temporary 1/4 Sec. cor,

L. A. R. 31 E

- 80,14 Intersected A & B line 65 Mts North of the corner to Sec's, 11, 12, 13 and 14 from which corner I Run, N 89° 32' W on a true line between Sec's, 11 and 14.
- 2,75 ~~Right~~ bank of Matallah river 75 Mts wide, runs N 30° W. Rapid current, low Banks.
- 2,700 Left bank of Matallah River 70 Mts wide runs S, W, shallow rapia current, low banks.
- 4007 Set post for 1/4 Sec. cor, from which A Cotton, Wood, 4 in dia bears N 75° W 7 Mts dist
" " " " 12 " " bears South 7 Mts dist
- 42,00 Foot of Bluff, and a large river bottom being S W + N E,
- 53,50 Top of Bluff, being N E, and S W,
- 5700 Trail bearing S + N W
- 80,14 The corner to Sec's, 10, 11, 14 and 15, Land East half 2^d Rate bottom land, West half broken & Stony Timber Balsm & Cotton Wood

16 386

L 2 N R 31 E

North between Sec's 10 & 11.

40.00 Set post for $\frac{1}{4}$ Sec. cor. and raised
stone mound, as per instructions.

50.75 A Trail bearing N. 74 S E.

80.00 Set a post for corner to Sec's 2, 3,
10 and 11. Drive chain stake and
raised mound with trench
as per instructions.

Land Rolling grass hills, 2^d rate
soil.

East on Random line between Sec's
2 and 11.

Variation $91^{\circ} 30' E$

40.00 Set Temporary $\frac{1}{4}$ Sec. cor.

80.00 Article of A & S line 88 $\frac{1}{2}$ miles North
of the corner to Sec's 1, 2, 11 and 12
from which corner I Run
A 89 $\frac{1}{2}$ $\frac{1}{2}$ miles North on a true line between
Sec's 2 and 11.

40.00 Set post for $\frac{1}{4}$ Sec. cor. Drive chain
stake and raised mound with

T 2 N R 31 E

= trench as per instructions
8000 The corner to Sec's. 2, 3, 10 and 11
Land selling. 2^d and 3^d rate Soil

North on a Random line between Sec's
2 and 3.

4000 Set temporary 1/4 Sec. cor.
8060 Intersect the North. boundary
of Township 50 Ws East of the
corner to Sec's 2 and 3, from which
corner. I Run

S 22 E on a true line between Sec's
2 and 3

1700 To Point from Walla Walla to Dunes, bearing E 4 W
4060 Set apart for 1/4 Sec. cor. drive char-
= ed stake and raised mound with
trench as per instructions

8060 The corner to Sec's. 2, 3, 10 & 11,
Land sold 2^d rate Soil

Oct. 22^d 1860.

North between Sec's. 33 and 34

4000 Set apart for 1/4 Sec. cor. drive

18 388

To N R 31 E

Chama Stake on a raised mound
as per instructions

4375 To a Dry Run in course N. E.

80.00 Set apart for corner to Sec's. 27. 28

34 and 35 above Chama Stake and
raised mound with trench as per
instructions.

Lean a stoney grass hills. poor soil

East on Random line between Sec's
27 and 34,

Variation. 20' 00" E

40.00 Set Temporary 1/4 Sec. cor.

80.60 Intersected N & S line 25' N. South
of the corner to Sec's. 26. 27. 34 and 35

from which corner I Run

589' 49" West on a true line between
Sec's. 27 and 34

4030 Set apart for 1/4 Sec. cor. above Chama
Stake, and raised mound as per inst-
-ructions

80.60 The corner to Sec's. 27. 28. 33 and 34

T2 N R 31 E

Land 3d rate soil

North between Sec's 27 and 28.

4000 Set a post for 1/4 Sec. cor, drove
charred stake and raised mound
with trench as per instructions

8000 Set post for corner to Sec's. 21, 22,
27 and 28, drove charred stake and
raised mound with trench as
per instructions.

Land broken & stony

East on a Random line between
Sec's. 22 and 27

Variation, 20° 15' E

4000 Set Temporary 1/4 Sec. cor,

8040 Intersection N & S line 22th, South
of the corner to Sec's. 22, 23, 26 & 27
from which corner I Run,
889° 37' W on a true line between
Sec's. 22 and 27

4020 Set post for 1/4 Sec. cor, drove

20 390

T 2 N B 31 E

chard Stake and raised Stone
monument as per instructions
61,90 To a Dry Run corner North
8040 The corner to Sec's. 21, 22, 27 & 28
Land rolling 2^d rate soil

North bottom Sec's. 21 and 22,
4000 Set post for 1/4 Sec, cor, drove
chard Stake and raised monument
with trench as per instructions
8000 Set post for corner to Sec's. 15, 16
21 and 22, drove chard Stake and
raised monument with trench as
per instructions
Land broken hills & stony.

East on Random line bottom Sec's
15 and 22,

Variation. 1945' E

4000 Set Temporary 1/4 Sec, cor,
80,23 Intersect N & S line 13 Ws North of
the corner to Sec's. 14, 15, 22 and 23

T₂ N R 31 E

from which corner Run,
N 89° 55' W on a true line between
Sec's. 15 and 22,

4011 Set a post for $\frac{1}{4}$ Sec. cor. Arrowhead
stake and raise mound with
mark as per instructions.

78.23 To a Deep Stony Ravine course
North,

8023 The corner to Sec's. 15, 16, 21 & 22
Land broken 2^d & 3^d rat Soil

North between Sec's 15 and 16

1900 Foot of hill, & enter Matillah
River bottom, bearing E & W

40.00 Set a post for $\frac{1}{4}$ Sec. cor. from which
A Balm Giliad 9 in dia bears S 45° W
105 lbs dist

A Balm Giliad 12 in dia bears N 19° E 30 lb
lbs dist.

48.00 Left bank of Matillah River, ~~from~~
100 lbs wide runs West

49.00 Foot of hill bearing E & W

22 342

T 2 A R 31 E

8000 Set apart for cor, to Sec's 9, 10, 15.
and 16. drove stake and raised
mound with much as per instr-
-uctions

Found Sandy Soil

~~Timber~~ Balsam Guttata timber
on the river,

Eastern Random line between
Secs. 10 & 15.

Variation. $23^{\circ}30'$ E

4000 Set Temporary 1/4 Sec, cor,

8050 Intersection T 4 S line. 13 Ws North of
the corner to Sec's, 10, 11, 14 & 15, from
which corner I Run,

N 89.57 W on a true line between
Sec's 10 & 15

3850 To a Dry Ravine corner, South

4025 Set post for 1/4 Sec, cor, drove chased
stake and raised mound with much
as per instructions

8050 The corner to Sec's, 9, 10, 15 & 16.

T2 N R31 E

Land rolling 2^d and 3^d rat Soil

North bottom Sec's 9 & 10

40.00 Set post for 1/4 Sec. cor. and raised
stone mound as per instructions

80.00 Set post for corner to Sec's. 3, 4, 9
and 10, drove charred stake and
raised stone mound. with mound
as per instructions

Land broken grass hills 2^d & 3^d
rat Soil

East on Random line between
Sec's 3 and 10

Variation 2,000 E

40.00 Set Temporary 1/4 Sec. cor.

80.50 Intersected N & S line 18 1/2 miles North
of the corner to Sec's. 2, 3, 10 & 11
from which I Run.

N 89° 52' W on a true line between
Sec's 3 and 10

40.25 Set apart for 1/4 Sec cor drove

24 394

T 2 N R 31 E

Chumbe Stake and raised mound
and with trench as per instructions

8050 The corner to Secs. 3, 4, 9 & 10
Land rolling prairie upland
2d rate soil

North on a Random line between
Sec's 3 and 4, ~~Variation~~

4100 Set Temporary 1/4 Sec. cor.

8215 Intersection North boundary of
Township 96 Ns East of the
corner to Sec's. 3 and 4, from
which I Run

S 041° E on true line between
Sec's. 3 and 4

1915 Road from Dallas to Walla Walla

3715 Top of Table lands corner E & W

4215 Set post for 1/4 Sec. cor. Woodchard
Stake and raised mound with
trench as per instructions.

8215 The corner to Sec's. 3, 4, 9 & 10

25
395

To N. R 31 E

Land North $\frac{1}{2}$ live 2^d rate
Soil, South $\frac{1}{2}$ broken & stony

North between Sec's 32 and 33

4000 Set post for $\frac{1}{4}$ Sec. cor. drove
and stake and raised mound
with trench as per instructions

8000 Set a post for corner to Sec's 28, 29
32 and 33, drove chain stake and
raised mound as per instructions
Land rolling poor stony hills

East on a Random line between Sec's
28 and 33,

Variation $21^{\circ}30'$ E

4000 Set Temporary $\frac{1}{4}$ Sec. cor.

8030 Intersection N & S line 80 lbs North of
the corner to Sec's 27, 28, 33 and 34
from which corner I Run
 $N 89^{\circ}23'$ W on a true line between
Sec's 28 & 33,

26 396

T2 N R31 E

4015 Set post for 1/4 Sec, cor, drove charred stake and raised mound with trench as per instructions

8030 The corner to Sec's. 28, 29, 32 & 33
Land poor stony grass hills

North between Sec's 28 and 29

4000 Set post for 1/4 Sec, cor, and raised stone mound as per instructions

7530 To a Deep Dry Ravine about N.E.

8000 Set post for corner to Sec's. 30, 31, 28 and 29. drove charred stake and raised mound ^{with trench,} as per instructions. Land Broken & stony.

East on a Random line between Sec's. 21 & 28

Variation 18.15 E

4000 Set Temporary 1/4 Sec, cor.

8020 Intersect N & S line 70 Yds North of the corner to Sec's. 21, 22, 27 & 28, from which come 2 Run.

T 2 N R 31 E

N 89° 30' W on a true line between
Sec's. 21 and 28

40.10 Set post for 1/4 Sec. cor. drove char-
-red stake and raised ~~stone~~ mound
with trench.
As per instructions

5700 To a Deep Dry Ravine course
North.

7920 To a Shup Dry Ravine course
N.E.

8020 The corner to Sec's. 20, 21, 28 and 29
Land Rolling 2nd rate soil.

North between Sec's 20 & 21

44.00 Set post for 1/4 Sec. cor. drove char-
-red stake and raised mound
with trench as per instructions

44.50 To a Shup Rocky Ravine course
N.E.

80.00 Set a post for corner to Sec's. 16
17, 20 and 21, drove charred stake and
raised mound with trench as per
instructions. Land Broken 2nd rate soil

28 398

T₂ N R 31 E

East on a Random line between
Sec's 16 & 21

Variation 1945' E

4000 Set Temporary 1/4 Sec cor

8050 Intussetico N & S line 4000' North
of the corner to Sec's, 15, 16, 20 & 22.

From which corner I Run

N 89 45' West on a ~~Random~~^{True} line
between Sec's, 16 & 21.

4025 Set post for 1/4 Sec. cor, and raised
stone monument as per instructions

4650 To a deep Rocky Ravine course
North.

8050 The corner to Sec's, 16, 17, 20 & 21.

Land broken 2^d rate some stone

North between Sec's 16 & 17

2400 Foot of steep hill and enter River
bottom. Course E & W

3150 To the Left bank of the ~~mountain~~
river, 1250' wide, course West,

4000 Set a post for 1/4 Sec. cor, drove charred

T₂ at R 31 E

and raised mound with trench
as per instructions

4600 Leave River bottom and begin
to ascend hill being E & W.

8000 Set a post for corner to Sec's. 8, 9, 16 &
17. drove chains stake and raised
mound, with trench as per instructions
Lava. 1st 2^d and 3^d rate. soil
Climb on River Basin Gillies.

East on a Random line between
Sec's. 9 and 10

Variation, 17° 30' E

4000 Set Temporary 1/4 Sec. cor.

8040 Intersected N & S line. 35 lbs North
of the corner to Sec's. 9, 10. 15 & 86
from which corner I Run.

N 89° 43' W On a true line between
Sec's. 9 & 10

1250 To a Deep Dry Ravine corner South

4020 Set post for 1/4 Sec. cor. and raised
stone mound, as per instructions

30 400

T. N. R. 31 E

5725 To a deep stony ravine (long) corner
South,

8040 The corner to Sec's. 8, 9, 16 and 17
Land Broken grass hills

North between Secs 8 & 9

4000 Set post for 1/4 Sec. cor. and raise
stone mound, after instructions

8000 Set apart for corner to Sec's. 4, 5, 8
and 9 drove charred stake and
raised mound of stone
Land broken grass hills

East on Random line between
Sec's. 4 and 9

Variation $17^{\circ}30'$ E

4000 Set Temporary 1/4 Sec. cor.

8000 Intersected N & S line 35 Rs North
of the corner to Sec's. 3, 4, 9 and 10
from which corner I Run
 $N 89^{\circ}45'$ W on a true line between Sec's
4 and 9,

T 2 N R 31 E

650 To a Deep Dry Ravine corner South
 40.00 Set post for 1/4 Sec, cor, and raised
 stone mound as per instructions
 80.00 The corner to Sec's. 4, 5, 8 and 9
 Linn High Prairie, 2^d rate soil

North On a Random line between
 Sec's. 4 and 5.

40.00 Set Temporary 1/4 Sec, cor,
 82.80 Intersected North boundary
 of Township 170 Ws East of
 the corner to Sec's. 4 and 5.
 from which corner I Run
 S 13' E on a true line between
 Sec's. 4 and 5.

42.80 Set post for 1/4 Sec, cor, drove char-
 -ea Stake and raised mound
 with trench as per instructions

82.80 The corner to Sec's. 4, 5, 8, and 9
 Linn rolling Table land 2^d rate
 soil.

Oct 24th 1860

32

402

T & N R 31 E

North bottom Sec's 31 & 32

Var. 2000' E

40,000 Set post for $\frac{1}{4}$ Sec. Cor drove ch
arrid Stake and russia mound
as per instructions

73,000 To a Ravine runs N. E.

80,000 Set post for cor to Sec's. 29. 30. 31 & 32
drove char'd Stake and russia mo
=und, ^{with truck} as per instructions,

Land Rolling 2^d rate soil

Easton Random line between
Sec's. 29 and 32.

Variation 20,00' E

40,000 Set Temporary $\frac{1}{4}$ Sec. cor,

79,500 Intersected T & S line 72 lbs north
of the corner to Sec's. 28. 29. 32 & 33
from which corner Run
N 89^o 29' W on a true line between
Sec's 29 & 32.

3800 To Dry Ravine course N

3975 Set post for cor to $\frac{1}{4}$ Sec drove

T 2 N R 31 E

shamda stake and raised mound
with trunk
as per instructions

79.50 The corner to Sec's. 29, 30, 31 & 32
Land Broken 3rd rate grass
land,

West on Random line between Sec's
30 & 31.

40.00 Set Temporary 1/4 Sec. cor,
89.36 Intersected West boundary of Towns
-hip 98 lbs South of the corner
to Sec's, 30 & 31 from which cor-
-ner is Run

589' 18" E on a true line betw
een Sec's 30 & 31.

49.36 Set post for 1/4 Sec. cor, drove ch
-anna stake and raised mound
with trunk
as per instructions

89.36 The corner to Sec's 29, 30, 31 & 32
Land Rolling grass hills 2nd rate soil

34 404

T. N. R. 31 E

North between Sec's 29 & 30

4000 Set post for 1/4 Sec. cor. above
chance stake and raised mound
= and with trench as per instr
= uctions,

5000 Enter Broken hills

8000 Set post for corner to Sec's. 19,
20, 29 and 30, and raised stone
mound, as per instructions

East on Random line between
Sec's 20 & 29

Variation, 1400' E

4000 Set Temporary 1/4 Sec. cor.

8000 Intersected T & S line 700' North
of the corner to Sec's. 20, 21, 28,

and 29. from which corner Run
N 89° 30' West on a true line between

Sec's 20 & 29

4000 Set post for 1/4 Sec. cor. above chance
stake and raised mound with trench
as per instructions

T 2 N. R 31 E

80.00 The corner to Sec's. 19. 20. 29 & 30
Lena broken & Stoney.

West on a Random line between
Sec's. 19 & 30

40.00 Set Temporary 1/4 Sec. cor.

89.20 Intersected West boundary of
Township 139 Ms South of the
corner to Sec's 19 & 30. from which
corner I Run.

889.01' On a true line between Sec's
19 & 30.

44.20 Set a post for 1/4 Sec. cor. drove
diamond stake and raised mound
with trench as per instructions

89.20 The corner to Sec's. 19. 20. 29 & 30
Lena gently rolling 2nd rate Soil

North between Sec's 19 & 20

40.00 Set post for 1/4 Sec. cor. drove
diamond stake and raised mound
with trench,
as per instructions

86 406

L N R 31 E

8000 Set a post for Corner to Secs
17, 18, 19 and 20 drove chain
stake and raised stone mound
and as per instructions
Lima broken and Stony

Cast on a Random line between
Sec's 17 and 20

Var. 2100' E

4000 Set Temporary 1/4 Sec, cor,
79.87 Intersected N 48 line 80 Mts North
of the corner to Sec's, 16, 17, 20 & 21
from which corner I Run
N 89° 25' West on a true line between
Sec's, 17 & 20.

39.93 Set a post for 1/4 Sec, cor, drove char-
=er stake and raised mound
with trench as per instructions
79.87 The corner to Sec's, 17, 18, 19 & 20
Lima Broken 3^d rate Soil

2 N R 31 E

37
407

Weston Random line between
Sec's. 18 & 19

- 4000 Set temporary $\frac{1}{4}$ Sec. cor.
8980 Intersicula West boundary
of Township 206 Ns South
of the corner to Sec's. 18 & 19
from which corner I Run,
S88°2' Conatum line between
Sec's. 18 & 19
- 4980 Set post for $\frac{1}{4}$ Sec. cor. drove ch
-anna stake and raised mound
with trench as per instructions
- 6000 To a deep Ravine course North
8980 The corner to Sec's. 17, 18, 19 & 20
Land rolling $2\frac{1}{4}$ & $3\frac{1}{4}$ rat Soil

North between Sec's. 17 & 18

- 4000 Set post for $\frac{1}{4}$ Sec. cor. drove ch
-anna stake and raised mound
with trench as per instructions
- 7000 Lower replum and enter bottom
bearing E & W,

38 408

Lot R31 E

7450, Left bank of Mattawan River
7500 wide runs West.

7800 Leave timber bottom & enter uplands
bearing E & W

8000 Set post for corner to Sec's. 7, 8, 17 & 18
drove chain stake and raised mound
-nd with much as per instructions
Lined (Except River bottom) broke
river bottom 1st and 2^d rate soil

Oct 25th 1860.

Corner at Random line between Sec's
8 and 17

Mar 22nd 30' E

4000, Set Temporary 1/4 Sec. cor.

7972 Intersecting N & S line 7000 North of
the corner to Sec's. 8, 9, 16 & 17 from
which corner Run.

N 89^o 30' West on true line between Sec's

Left bank
2500 Mattawan River 15000 wide runs N, W,

3986 Set post for 1/4 Sec. cor. drove chain

stake and raised mound with much

To N R 31 E

34
409

as per instructions

77.00 Left bank of Matillak River, 100
kms wide runs S, W,

79.72 The corner to Sec's. 7, 8, 17 & 18
Land level 1st run S. a. s. good for
farming purposes.

Weston Random line between Sec's
7 & 18

46.00 Set Temporary 1/4 Sec. cor.

87.00 Intersected West boundary of Town
ship 250kms South of the corner
to Sec's. 7 & 18.

58813' E on a true line between
Sec's. 7 & 18

18.00 Enter River bottom. Bearing NWSE

23.30 Left bank of Matillak river 60kms
wide runs NWSE.

47.00 Set post for 1/4 Sec. cor. drove char-
-ed stake and a v. iron mound
with trench as per instructions

52.75 Leave River bottom and enter upland

T. N. R. 31 E

bearing N. W. & S. E

8700 The corner to Sec's. 7, 8, 17 and 18

Land 1st and 2^d rate soil

Timber Balsam, Yellow Cedar

grove of this line ^{because} Brass Willows & vines
Noted at 8700 ^{guide} because error in meridian

North bottom Sec's 7 & 8

350 Foot of Stony hill bearing E & W

4000 Set post for 1st Sec. cor. drove chainstake and raised monument with
as per instructions

5000 Summit of hill bearing E & W

8000 Set a post for corner to Sec's. 5, 6, 7 & 8
drove chain stake and raised ^{as per instructions} monument with
Land broken - hills 2^d & 3^d rate soil

Easton Random line between Sec's

5 & 8

Variation 2100' E

4000 Set Temporary 1st Sec. cor.

7980 Intersection N & S line 5000 North

of corner to Sec's. 4, 5, 8 and 9 from

which corner I Run

L N R B / E

41
411

N 89° 39' W. on a true line between Sec's
548

3990 Set post for 1/4 Sec, cor, drove chamo
stake and raised mound with
trench as per instructions

74.80 The corner to Sec's 5, 6, 7 & 8
Land Rolling 3^d/₄ out Soil

Weston Random line between Sec's
647,

40.00 Set a post for Temporary 1/4 Sec, cor,
85.92 Intuseta West boundary of Tow
nship. 228 Yds South of the corner
to Sec's. 647, from which corner
I Run

S 88° 23' E on a true line between
Sec's, 647

45.92 Set post for 1/4 Sec, cor, and raised
stone mound as per instructions

85.92 The corner to Sec's. 5, 6, 7 and 8

Land Broken & Stony,
Note. dist 85.92 chs caused by error in meridian

42 412

To N R 31 E

North on a Random line between
Sic's 540

4000 Set Temporary 1/4 Sec. cor.

8387 Intersected North boundary of
the Township. 224 Rs East of the
corner to Sic's 540 from which
run Run.

$51^{\circ}36'$ E on a ~~Random~~ line between
Sic's 540.

4387 Set post for 1/4 Sec cor above
marked stake and raised mound
with trench as per instructions

8387 The corner to Sic's, 5, 6, 7 & 8
Lund Lovell 2^d rate Sic's

General Description

The quality of the land in this Township is about an average. There is a very fine ^{part} portion of good first rate soil, situated on both sides of the Matilah river, also a large amount of good second rate soil. The uplands is fine grazing land being covered with rich bunch grass.

The Matilah River is a beautiful stream of water, rapid current, low banks, and averages about 200 yds in width, at low water.

Timber Balsam Gilled, Birch & Cotton wood.

List of names

A list of the names of the individuals
 - men employed to assist in running
 measuring or marking the lines and
 corners described in the foregoing full
 - led notes of Township No 2 North
 of the base line and of Range No 31
 East of the Willamette meridian
 showing the respective capacities
 in which they acted.

M. O. C. Murphy Compassman

Walter Paulding Chairman

Patrick Callahan " "

Thomas White Area man

We hereby certify that we assisted Josiah A
 Burnett, deputy surveyor in surveying the
 subdivisions lines in Townships No. 2 North
 of the base line of Range No. 31 East the
 Willamette meridian, and that said Town-
 ships has been in all respects, to the best
 of our knowledge and belief, well and
 faithfully surveyed, and the boundary
 monuments planted according to the
 instructions furnished by the surveyor General

M. C. Murphy, Compassman
 Walter Paulding Chaminan
 Patrick ^{his} Callahan Chaminan
 Thomas White ^{Justice} Freeman

Subscribed and sworn to before me ^{by} the above
 named persons, this the 30 day of October 1860

S. B. Hodgeon
 Justice of the Peace
 for, Wasco County Oregon

I Josiah A. Bennett deputy Surveyor do solemnly swear that in pursuance of a contract with W. W. Chapman Surveyor of the public lands of the United States in the State of Oregon bearing date the 12th day of September 1860 and in strict conformity to the laws of the United States and the instructions furnished by the Chief Surveyor General I have faithfully surveyed the Subdivision lines in Township 2 North of the base line of Range N^o 31 East of the Williams-ette meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

J. A. Bennett
Dept. Sur.

Subscribed and sworn to before
me this 21. Nov. 1860

W. W. Chapman
Sur Genl.

In

Sur. General's Office

Eugene City, Decr. 5th 1860.

The foregoing field notes of the surveys
of the subdivisions of Township No. 2 N.
R. 31 East of the Willamette Meridian
Oregon - executed by Josiah A. Barnett
under his contract No. 92, bearing
date the 12th day of September - 1860 -
having been critically examined, the
necessary corrections and explana-
tions made, the said field notes
and the surveys they describe are
herely approved.

W. W. Chapman
Sur. Genl. of Oregon