

71³

Between Ranges 33 and 34
East Township 1 N. Will. Mer.

chs. North on East boundary of Sec. 12.
Var. 21° E.

180.00
40.00
24.00 Brook, 6 lks wide, flows East 100

40.00
-00.00 Set Bassalt Stone 14+14+12 for 1/4
Sec. corner. 75-

80.00
80.00 Set Bassalt Stone 16+14+12 for
corner to Secs 1, 12, 6 & 7.

Land Kelly, Soil 2^d rate, good grass.

North on East boundary of Sec. 1.
Var. 21° 30' East.

40.00
70.00 Set Bassalt Stone 16+14+12 for
1/4 Section corner 75-

80.00
80.00 Set Bassalt Stone, 18+16+14
for corner to Townships 1 & 2
North Ranges 33 & 34. East
Willamette Meridian.

Land Kelly, Soil 2^d rate
Good grass.

May 1st 1871.

Between Ranges, 33 + 34. E. Mill me

chs.

Township 2 N. R. 33. East.

88

at ✓

North on East boundary of Sec. 36
Var. 21° East.

4000
4000
8000

Set Stone 14 + 12 + 10 for 1/4 Sec. corner

Set Stone 18 + 16 + 14 for corner to Secs

25, 36, 30 + 31.

Land stony, Soil 2^d rate.

Some grass.

(8713)

North on East boundary of Sec. 35.

Var. 21° 30' East

40,00
40,00
80,00

Set Stone 14 + 14 + 12 for 1/4 Sec. cor.

Set post and made stone mound
for corner to Secs 24, 25, 19 + 30 75

Land sloping north, Soil
1st rate. Good grass.

89 Return Rd 33 + 34 E, T2 N.

chs. North on East boundary of Sec. 24.

Var. 21° East

15.70 Brook, 8 lbs, flows N.E.

4000 Set post and Earth mound for ¹⁴ Sec. corner.

8000 Set post and made mound of Earth for corner Secs 13, 24, 18, 19.

Land level. Soil 1st rate -
Good grass.

North on East boundary of Sec. 13¹³

Var. 21° East

16.24 La Grand and Pendleton road
Course E & N.

4000 Set post and made mound
of Earth for ¹⁴ Sec. Cor.

8000 Set post and made mound
of Earth for corner to Secs
7, 12, 13 + 18

Land level. Soil 1st rate -
Good grass.

Between R.s. 33 & 34. E. T 2 N.

90

chs.

North on East Boundary of Sec. 12.
Variation 21° East.

8.00

8.00

Wagon road, course E & W.

23.50

20.00

Umatilla river, course W.

40.00

40.00

Set Stone 16 + 14 + 8 for 14 S. cor.

80.00

8.00

Set post and made mound of Earth
for Connection Secs 1, 12, 6 & 7.
Land level, Soil 1st rate

North on East Boundary of Sec. 1.

Variation 21°

40.00

40.00

Set post and made stone mound
for 1/4 Sec. Corner

80.00

8.00

Set post and made mound of
Earth for corner Tps 2 & 3 North
Ranges 33 & 34. East.

Land rolling. Soil 1st rate

Good grass

May, 19, 1871

1244

Surveyor General's Office
Eugene City Nov 11th 1871

The foregoing field notes of the Survey
of the Exterior lines of S 1st Rgs
33, 34 & 35 East, and S 2nd Rgs 33 & 34
Co Will Mer Oregon executed by
G. F. Moody deputy under his
contract bearing date the 23rd day
of April 1871 having been critic-
ally examined the necessary
explanations and corrections
the said field notes and the Sur-
veys the describe are hereby
approved

W. H. Bell

Sur Gen^l

I Genas F. Moody, having
 been appointed Deputy Surveyor, of the
 lands of the United States in Oregon,
 do solemnly swear that I will well
 and faithfully, and to the best of my
 skill and ability, execute the duties
 confided to me, pursuant to a con-
 tract with W. H. Odell, Surveyor
 General, of the public lands in Oregon,
 bearing date 23 day of April 1871,
 according to the laws of the United
 States and the instructions received
 from the said Surveyor General.

J. G. Moody

Sworn and Subscribed before me
 This 29th day of April 1871
 W. Davenport
 Coroner of the U.S. Circuit Court
 for the District of Oregon

I, M. A. Moody, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the pins upon uneven ground, and plumb the lally pins, whether by sticking or dropping the same; that I will report the true distance to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

M. A. Moody

Sworn and Subscribed before me }
 this 29th day of April 1871 }
 Wm. Davenport }
 Counselor of the U.S. Circuit Court }
 for the District of Oregon }

A. E. G. Condon, do solemnly swear
that I will well and truly perform the
duties of a juror, according to
instructions given me, and to the
best of my skill and ability.

E. G. Condon

Sworn and Subscribed before me
This 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon

J. E. Henderson do solemnly ²⁹⁸
swear that I will faithfully execute
the duties of chain carrier; that I
will level the chain upon uneven
ground, and plumb the lally
pins, whether by striking or dropping
the same; that I will report the
true distance to all notable
objects, and the true length of all
lines that I assist in measuring,
to the best of my skill and
ability.

C. H. Henderson

Sworn and Subscribed before me
this 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon