

Obs. Field notes of the Survey of the Exterior  
Lines of Township No. 3 North of Range  
No. 35, East of the Willamette Meridian  
Oregon, by Genas F. Moody under  
his contract No. 164. Bearing date, the  
4<sup>th</sup> (fourth) day of October, A.D. 1871.

Begin at the Established Corner to Tps  
2 & 3 North Ranges 34 & 35 East.  
East on South Boundary of Sec. 31.  
N. 22° E.

40.00 Set Stone 14 + 15 + 9 for '4 Sec. cor. facing  
West.

17.40 Enter Timber

80.00 Set post for corner Sections 31, 32  
5 & 6. in edge of Tomalleta River  
The Land along this line is  
hilly, soil stoney. Good grass.



Township 3 North

Range 35 East

Chs. East on South Boundary of Sec.  
32.

N. 21° 30' East.

24.00 Edge of Umatilla River

40.00 Set post and made mound of  
stone for  $\frac{1}{4}$  Sec. cor.

46.00 Leave timber and pass over  
foothills.

47.50 Stage Road course N. & S.

80.00 Set post and made stone mound  
for cor. to Secs 32, 33, 4 & 5.

Land broken and stony. Soil  
good 2<sup>d</sup> rate. Timber consists  
of Balw, Pine &c. Some  
undergrowth.



of the Millanette

Meridian.

5

3.

Chs. East on South Boundary of Sec.  
33.

Var.  $19^{\circ}30' E.$

40.00 Set Stone 17 + 14 + 9 for  $\frac{1}{4}$  Sec. cor.  
on Hill facing toward South,  
80.00 Set Stone, 18 + 10 + 10 for cor. to Secs.

33, 34, 3 & 4.

Land broken and Stony, Soil  
2<sup>d</sup> rate

East on South boundary of Section  
34.

Var.  $21^{\circ} E.$

23.50 Enter timber in River bottom  
30.50 Umatilla River 250 lks wide  
flows South West.

40.00 Set post and made stone mound  
for  $\frac{1}{4}$  Sec. cor.

70.00 Leave timber

80.00 Set post and made stone mound for  
cor. to Secs. 34, 35, 2 & 3.



Township 3 North Range 35 East

chs East on South boundary of  
Section 35.

N. 20°30' E.

4000 Setpost and made Stone mound  
for  $\frac{1}{4}$  Sec. cor.

8000 Set. Stone 17 + 14 + 12 for cor. to  
Secs. 35, 36, 1 + 2.

Land Hilly, Soil 2<sup>d</sup> rate.

East on South boundary of  
Sec. 36.

N. 21° E.

15000 Brook, 12 chs, flows North. 100.

40000 Setpost and made mound of  
Earth for  $\frac{1}{4}$  Sec. corner.

8000 Setpost and made mound  
of Earth for corner to Secs  
2 + 3 North, Ranges 35 + 36  
East of the Willamette  
Meridian.

Land hilly, Soil 2<sup>d</sup> rate.



24  
Township

Range

U. S. Surveyor General's Office  
Oregon City June 21<sup>st</sup> 1872

The foregoing field notes of the survey of Ex-  
termin lines of T 3 N. R 35 E # and  
T 21 N. Ranges 34<sup>th</sup> and 35 East Will  
Mer and the Subdivisional lines  
of T 4 N Rqs 34<sup>th</sup> and 35 E Will  
Mer Oregon executed by J. B.  
Moody deputy Surveyor under con-  
tract No 164 bearing date Oct  
24<sup>th</sup> 1871 having been critically  
examined the necessary cor-  
rections and explanations  
made the said field notes and  
the surveys they describe are  
herby approved

W. H. Bell  
Surveyor



" I, Genas F. Moody, having been appointed a deputy Surveyor of the lands of the United States in Oregon, do solemnly swear that I will well and faithfully, and to the best of my skill and ability execute the duties confided to me pursuant to a contract with W. H. Odell, Surveyor General of public lands in Oregon, bearing date the 4<sup>th</sup> day of October 1871, according to the laws of the United States and the instructions received from the said Surveyor General.

G. F. Moody

Sworn and Subscribed before me  
this 14<sup>th</sup> day of October 1871  
W. Davenport  
U.S. Comm<sup>r</sup> Dist of Oregon



J. J. Kent, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the chain upon uneven ground, and plumb the tally pins, whether by striking or dropping the same; that I will report the true distances to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

J. J. Kent

Sworn and Subscribed before me  
 This 14<sup>th</sup> day of October 1871  
 M. Davenport  
 U.S. Commr. Dist. of Oregon.



I. O. Hathaway do solemnly  
swear that I will well and truly  
perform the duties of Axeman  
according to the instructions given  
me, and to the best of my skill and  
ability

O Hathaway

Sworn and Subscribed before me  
This 14<sup>th</sup> day of October 1871

M. Davenport  
U.S. Commr. Dist. of Oregon.



I, Geo. W. Renne, do  
 solemnly swear that I will faithfully  
 execute the duties of chain carrier; that  
 I will level the chain upon uneven  
 ground, and plumb the tally pins,  
 whether by striking or dropping the  
 same; that I will report the true  
 distances to all notable objects, and  
 the true length of lines that I assist  
 in measuring, to the best of my skill  
 and ability.

Geo. W. Renne

Sworn and Subscribed before me  
 this 14<sup>th</sup> day of October 1871  
 W. Davenport  
 U.S. Comm. Dist. of Oregon



I Edward Gariopy, do solemnly swear that I will well and truly perform the duties of Axeman, according to the instructions given me, and to the best of my skill and ability.

E. Edward Gariopy

Sworn & Subscribed before me  
 This 14th day of October 1871  
 W. Davenport  
 U.S. Commr. Dist. of Oregon.