

FIELD NOTES

Of the survey of the *Subdivisional*
 Lines of *Township 2 North*
Range 35 East Willamette Meridian, Oregon,
 as surveyed by *Asst. Currier and Joe Holand*
 U. S. Deputy Surveyor, under his Contract No. _____
 dated *May 4th*, 1887

Survey commenced, *Sept 7th*, 1887

Survey completed, *" 12th*, 1887

NAMES AND DUTIES OF ASSISTANTS.

<i>J. D. Medley</i>	, Compassman. <i>Chairman</i>
<i>Wm. N. Medley</i>	, <i>Chairman.</i>
<i>Frank Belshaw</i>	, <i>Chairman.</i>
<i>Guy Davis</i>	, <i>Chairman.</i>
<i>L. P. Wooley</i>	, Compassman. <i>Chairman.</i>
<i>B. B. Crownor</i>	, <i>Axman.</i>
<i>J. R. Hadley</i>	, <i>Axman.</i>
	, <i>Flagman.</i>

PRELIMINARY OATHS OF ASSISTANTS.

We, J. S. Medley, W. H. Medley, Frank Belshaw, Guy Davis

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the Subdivisional lines of T 2 North Range 35 East Willamette Meridian, Oregon.

J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Belshaw, Chainman.
Guy Davis, Chainman.

Subscribed and sworn to before me this 7th day of Sept, 1887

[SEAL.] James P. Currier U.S. Deputy Surveyor

We, B. B. Crowner and J. M. Hadley do solemnly swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Subdivisional lines of T 2 North Range 35 East Willamette Meridian, Oregon.

B B Crowner, Axman.
J M Hadley, Axman.

Subscribed and sworn to before me this 7th day of Sept, 1887

[SEAL.] James P. Currier U.S. Deputy Surveyor

INDEX

Referring the Lines to the Pages of the Field Notes.

T. *2 North* R. *35 East* Will. Mer.

6	68	5	51	4	38	3	26	2	12	1
67	66	50	37	25	11					
7	65	8	49	9	36	10	24	11	10	12
64	63	48	35	23	9					
18	62	17	47	16	33	15	22	14	7	13
61	60	45	32	21	6					
19	58	20	44	21	31	22	19	23	5	24
57	56	43	30	18	4					
30	55	29	41	28	29	27	16	26	3	25
54	53	40	28	15	2					
31	52	32	39	33	27	34	14	35	7	36

Meanders of _____, Pages _____ to _____

Meanders of _____, Pages _____ to _____

12342

Subdivision of T. 2 North R. 35 East.

Willamette Meridian, Oregon.

(8093-10 M.)

3.75 chs. S. of North Secs. 6 & 7
 S. 2. N. R. 35. E. Set a
 Stone 7x8x9 ins. 6 ins. in the
 ground for bloning Nor. to
 Secs. 1 & 2 marked C. S. on
 S. face, with 5 notches on
 S. & 1 on N. edge raised
 a mound of Stone 2 ft. high
 with 4 1/2 ft. base over it,
 Pits impracticable.

Land very rough and
 mountainous 79.36 chs.

Soil 3rd rate & rocky.

North on true line bet. Secs. 1 & 2
 Va. 20° 45' East.

12.70 Gulch course W. — 50

Ascend

40.00 Set a post 3 ft. long 3 ins.
 square 24 ins. in the ground

Subdivisions of T. 2 North R. 35 East
Willamette Meridian, Oregon.

For $\frac{1}{4}$ Sec. Cor marked $\frac{1}{4}$ D. on
N. face from which
A line 6 ins. diam. bears N. 45° E.
23 lks. dist. marked $\frac{1}{4}$ D. B. D.
A line 18 ins. diam. bears N. 75° W.
1.06 chs. dist. marked $\frac{1}{4}$ D. B. D.

60.00 Creek 20 lks wide, course N. E.
73.00 Intersect Township line 40 lks.

N. of Cor. to Secs. 35 $\frac{1}{4}$ & 36 D.
3 N. R. 35, E. $\frac{1}{4}$ Set a stone
7 x 9 x 12 ins. 8 ins. in the ground
for closing Cor. to Secs. 1 $\frac{1}{4}$ & 2
marked C. B. on N. face. With
1 notch on E $\frac{1}{4}$ & 5 on N. edge
and raised a mound of stone
2 ft. high with $4\frac{1}{2}$ ft. base on it.
Pits impracticable.

Land rough, ^{mostly timber} & brushy. 73.00 chs
Pine timber in places.
Thin grass. Soil $4\frac{1}{2}$ ft. rain.

Subdivisions of T. 2 North R. 35 East
Willamette Meridian, Oregon.

(8093-10 M.)

- North on true line bet. Secs. 2 & 3
Va. $21^{\circ} 15'$ East
- 30.00 Gulch corner N. E. - 100
- 40.00 Set a Stone $8 \times 15 \times 21$ ins. 14 ins.
in the ground for $\frac{1}{4}$ Sec. Cor.
marked $\frac{1}{4}$ on N. face. And
dug pits $18 \times 18 \times 12$ ins. N. & S.
from Stone $5\frac{1}{2}$ ft. dist. And
raised a mound of Earth $1\frac{1}{2}$ ft.
high with $3\frac{1}{2}$ ft. base over it
- 60.40 Duce & Indian farm
- 73.20 Intersect Township line 10 kts. E.
of Cor. to Secs. 34 & 35. T. 2 N.
R. 35. E. And set a post 4 ft.
long & 4 ins. square 24 ins. in the
ground for crossing Cor. to Secs.
2 & 3 marked D. 2 N. R. 35. E. 16.
On S. S. 2 on E. & S. 3. on
N. faces with 2 notches on E. &
raised stone mid. around it.
4 on N. edges. Land rolling. Soil
1st rate. Good grass. *Diuris purpurea*

Subdivisions of T. 2 North R. 35 East
 Willamette Meridian, Oregon.

(8093-10 M.)

North on true line bet. Secs. 3 & 4
 Va. 20° East.

- 3.75 Gulch Course E. - 20
 40.00 Set a post 3 ft. long 3 ins.
 square 24 ins. in the ground
 for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. on
 N face. from which
 a line 8 ins. diam. bears N. 35° E.
 1.33 chs. dist. marked $\frac{1}{4}$ S. B. D.
 a line 10 ins. diam. bears N. 6° W.
 64 lbs. dist. marked $\frac{1}{4}$ S. B. D.
- 42.50 Ravine Course E. - 10
- 50.00 Wagon Road .. E & W.
- 53.00 O.R. & N. Railroad Course East & West
- 60.00 Slough of Water, Course N.
- 64.50 Umatilla River 1.25 chs. wide, ^{Course} N.
- Ascend steep bluff and
 leave river bottom
- 72.75 Intersect Township line 80 lbs.
 East of cor. to Secs. 33 & 34
 D. 3. N. R. 35. E. and set a stone
 8 x 10 x 12 ins. 8 ins. in the ground

Subdivision of T. 2 North R. 35 East
Willamette Meridian, Oregon.

for closing cor. to Secs. 3 & 4 marked
C.C. on S. face with 3 inches on
E. & W. Edges & raised a mound
of stone 2 ft. high with 4 1/2 ft.
base over it. Pines impracticable
Land mountainous & river bottom brush

& cottonwood in bottom 72.75 chs
From the cor. to Secs 4-5-32 & 33 on S. bdy. of
Township 20 N.
North of true line bet. Secs 32 & 33
Va 22° 30' East.

Ascend gradual slope of mountain
39.00 Small Gulch — 20

Ascend
40.00 Set a stone 8x10x12 ins. 8 ins.
in the ground for 1/4 Sec. cor.
marked 1/4 on N. face from which
a Pine 14 ins. diam. bears South
75° W. 1.07 chs. dist marked 1/4 S. B. D.
No other trees within limits.

Raised a mound of stone alongside
57.00 Wagon Road or Old Stage Road

78.75 Common course W. — 100

Subdivisions of T. 2 North R. 35 East 381
Willamette Meridian, Oregon.

North out true line bet. Secs. 4 & 5
Va. 19° East.

- 3500 Descend Steep Bluff
- 3650 River bottom (Umatilla)
- 4000 Set a Stone 12x12x14 ins. 9 ins.
in the ground for 1/4 Sec. cor.
marked 1/4 on N. face from which
A Balm 10 ins. diam. bears N. 10° E.
33 lks. dist. marked 1/4 S. B. D.
- 4150 A Balm 14 ins. diam. bears S. 20° W.
96 lks. dist. marked 1/4 S. B. D.
- 4325 Wagon Road course E & W
- 4400 O.R. & N. Railroad E & W
- 4400 Wagon Road course N.
- 5200 Touch the River Umatilla
- 6550 Umatilla River 150 chs. wide course N.W.
- 72.83 Intersect Township line 150 chs. East of
cor. to Secs. 32 & 33 @. 3. N. R. 35. E.
Set a Stone 7x8x9 ins. 6 ins. in the ground
for closing cor. to Secs. 4 & 5 marked
C.F. on S. face with 4 notches

Subdivisions of T. 2 North R. 35 East

Willamette Meridian, Oregon.

(8093-10 M.)

On E. $\frac{1}{4}$ 2 on N. edges raised a mound
 of $\frac{1}{4}$ stone 2 ft. high with $4\frac{1}{2}$ ft.
 base over it. Pits impracticable
 Land rolling soil in bottom good ^{1st rate}
 Heavy Balu $\frac{1}{4}$ Pine timber ^{7283 cho} Good grass

From the corner to Secs 5 + 6 - 31 and 32
 on S. edge of Township I run
 North on true line bet. Secs. 31 $\frac{1}{4}$ & 32
 Va. $22^{\circ}30'$ East.

33.50 Gulch or canon course N. - 400

40.00 Set a stone $12 \times 10 \times 8$ ins. 8 ins. in the
 ground for $\frac{1}{4}$ Sec. cor. marked
 $\frac{1}{4}$ on N. face from which
 a 4 in diam. bears East 30 lks. dist.
 marked $\frac{1}{4}$ D. B. D. $\frac{1}{4}$ & Q
 4 in 16 ins. diam. bears N. 40° (N. 50
 lks. dist. marked $\frac{1}{4}$ D. B. D.

55.00 Summit of ridge course N. + 300

80.00 Set a stone $9 \times 10 \times 12$ ins. 8 ins. in the
 ground for cor. to Secs. 29-30-31 & 32
 marked with 5 notches on E. $\frac{1}{4}$ / on S.

Subdivisions of T. 2 North R. R35 East
Willamette Meridian, Oregon.

(8093-10 M.)

North bet secs 5th and 6th
Pa 21° East.

4000 Set stone 9x8x7 ins 6 ins in the
ground for 4th sec. cor. marked 1/4 on
W. face dug pits 18x18x12 in N. and S. of
stone 5 1/2 ft. diam. raised mound of earth
1 1/4 ft high 3 1/2 ft base over it

4066 Enters field E & W.

5600 Bluff rock E & W center bottom 70

5934 O. R. R. E. & W.

7354 Intersect N. bdy Township 143 Sks
E of cor to secs 31th and 32th T. 3 N. R. 35 E
and set stone 10x10x8 ins 6 ins in
the ground for closing cor. marked
35 on E + 36 on W. faces
C. C. on S. face with 5 notches on
End notch on W. ~~edge~~ and raised
mound of stone over it
Sand rolling & bottom

Soil 2nd rate Brushnd
Heavy Timber pine & Balsam in bottom 1754 ch
Sept. 12th 1887

Subdivision of T. 2 North R. 35 East
Willamette Meridian, Oregon.

In accordance
with the requirements of the
manual of surveys. we have care-
fully used the adjustment of
our instruments by taking the
latitude daily - weather permitting -
during the progress of the surveys
represented by the foregoing field
notes and in all cases they were
found to be in correct adjustment.

James P. Currier
James E. Holand
U. S. deputy Surveyor

PAGES 402-403 ARE BLANK!

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by James P. Currin and
James P. Holland, U. S. Deputy Surveyor, to assist in
running, measuring, and marking the lines and corners described in the
foregoing field notes of the survey of the
Subdivisions lines of Township 2 North
R 95 East Willamette Meridian, Oregon,
showing the respective capacities in which they acted:

- L. F. Woolley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Crommel , Axman.
- J. R. Hadley , Axman.
- , Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted James P. Currin and
James P. Holland, U. S. Deputy Surveyor, in surveying
all those parts or portions of the
Subdivisions of T 2 North
Range 95 East Willamette Meridian, Oregon,
as represented in the foregoing field notes as having been surveyed by
him and under his direction; and that said survey has been in all respects,
to the best of our knowledge and belief, well and faithfully surveyed,
and the corner monuments established, according to the instructions
furnished by the U. S. Surveyor General of Oregon.

- L. F. Woolley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Crommel , Axman.
- J. R. Hadley , Axman.
- , Flagman.

Subscribed and sworn to before me this 12th day of
Sept., 1887.

[SEAL.]

James P. Currin
U. S. Deputy Surveyor

FINAL OATH OF DEPUTY SURVEYOR.

Mr. Jos. P. Curran and Jos. Noland, United States
Deputy Surveyor, do solemnly swear that in pursuance of instructions

received from *Douglas H. Taylor*, U. S.

Surveyor General for Oregon, bearing date of the *14th*

day of *May*, 188*7*, I have well, faithfully,

and truly, in ^{our}my own proper person, and in strict conformity with the
instructions furnished by the U. S. Surveyor General for Oregon, the
Surveying Manual, and the laws of the United States, surveying all

those parts or portions of *Township 2 North*

Range 35 East

Willamette Meridian, in the State of Oregon, as are represented in the
foregoing field notes as having been surveyed by ^{us}me and under ^{our}my

directions; and ^{we}I do further solemnly swear that all the corners of said
survey have been established and perpetuated in strict accordance with

the Surveying Manual, printed instructions, the special written instruc-
tions of the U. S. Surveyor General for Oregon, and in the specific man-
ner described in the field notes, and that the foregoing are the *true* field

notes of such survey, and should any fraud be detected ^{we}I will suffer the
penalty of perjury under the provisions of an act of Congress approved

August 8, 1846.

James P. Curran
James E. Noland U. S. Deputy Surveyor. S

Subscribed and sworn to before me this *Fifteenth*

day of *February*, 188*8*

W. Woodcock

Notary Public

for Oregon

Office of U. S. Surveyor General,

Portland, Oregon, ^{July 26th}, 1888.The ~~following~~ ^{foregoing} Field Notes of the Survey of theSubdivisional lines of
Township 2 North Range
35 East Will. Mer. Oregonexecuted by James P. Currier and James E. Nolan
^{Special} U S Dept Surveyors.
under his Contract No., dated May4th, 1887, having been critically examined,
the necessary corrections and explanations made, the
said Field Notes and the survey they describe, are
hereby approved.

Douglas W. Taylor.

Surveyor General.