

109
Between Ranges 35^{and} 36. T. N.

chs. North on East boundary of Sec. 1.
Var. $21^{\circ}30'$ East.

4000 Set post for $\frac{1}{4}$ Sec. corner, from which,
A. Pine 38 in diam bears $S 10^{\circ} N. 175$ lks

8000 Set post for corner to Townships 1. & 2
North, Ranges, 35^{and} 36. East. Will
Meridian from which:-

A. Fir 20 in diam bears $S 80^{\circ} N. 30$ lks
do do 18 do do do $N 10^{\circ} N. 20$ "

Land mountainous, Soil 2^d rate
some grass, But little timber on
this line.

May, 15th 1871.

North Boundary, T 1 N. R 35 East.

110

chs.

West on random line on North
Boundaries of Secs 1, 2, 3, 4, 5, 6.

Var. $21^{\circ}30'$ East.

I set temporary half mile and mile
posts and at 5 miles 78 chains
and 75 links to a point
2 chains and 30 links North
of corner to Townships 1 and 2
North, Ranges 34 and 35 East
Willamette meridian.

North $89^{\circ}44'$ East on true line on
North boundary of Sec. 6.

Var. $20^{\circ}00'$ East.

38.75

Set post for '4 Sec. corner, from which

A. Pine 24 in diam bears $S10^{\circ}N 44$ lks

78.75

Set post for corner to Secs 5, 6, 31, 32,

from which:-

A Pine 40 in diam, bears $N62^{\circ}W 41$ lks

do do 14 do do do $S80^{\circ}E 70$ lks.

Land mountainous, Soil good 2^d rate
good grass. Pine and fir timber.

111 North Boundary, T 1 N. R 35 East.

chs. North $89^{\circ}44'$ East on true line
line on north boundary of Sec. 5.

Var. 21° East.

4000 Set post for $\frac{1}{4}$ Sec. corner, from which

Aspens 12 in diam bears S 85° W. 40 lks

4075 Wagon road, corner N + S.

71.00 Brook, 6 lks. wide, flows S.E. 175 175

8000 Set post and made stone mound for
corner to Secs 4, 5, 32, 33.

Land mountainous. Soil good
2^d rate. Good grass. Pine timber.

May 16. 1871

North $89^{\circ}44'$ East on true line on
north boundary of Sec. 4.

Var. 21° East.

4000 Set post and raised stone mound
for $\frac{1}{4}$ Sec. corner.

8000 Set post and raised stone mound for
corner to Secs. 3, 4, 33, + 34. 270 270

Land mountainous. Soil
2^d rate. Good grass.

North Boundary. T1N R 35 E 12

chs. North 89°44' East on true line on north boundary of Sec. 3.
 Var. 20°30' East.

17.10	Brook, 14 lks. wide flows N	140
40.00	Set post and made stone mound for 1/4 Sec. corner.	+ 340
80.00	Set post and made stone mound for corner to Secs 2, 3, 34, 35	200

Land Mountainous. Soil 2^d rate. Good Grass. But little timber.

North 89°44' East on true line on north boundary of Sec. 2.

Var. 21°30' East.

18.00	Brook, 6 lks wide, flows N.W.	100
40.00	Set Bassalt stone 14+14+10 for 1/4 Section corner.	+ 240
80.00	Set post and made stone mound for corner to Secs 1, 2, 35, 35 ³⁶	

Land Mountainous. Soil 2^d rate. Good grass.

113 North Boundary, T1 N. R 35 E.

chs. North $89^{\circ}44'$ East on true line

line on north boundary of Sec. 1.

Var. 21° East

4000 Set Bassalt stone 18+18+9 for
 $\frac{1}{4}$ Sec. corner

8000 Tolocome to Townships 1+2
north, Ranges 35+36 East
Willamette Meridian.

Land Mountainous. Soil 2^d
rate. Good grass. Some Pine
timber.

May 17, 1871

1244

Surveyor General's Office
Eugene City Nov 11th 1871

The foregoing field notes of the Survey
of the Exterior lines of T 1 N R 30
33, 34 & 35 East, and T 2 N R 30 & 34
E Will Mer Oregon executed by
G. F. Moody deputy under his
contract bearing date the 23^d day
of April 1871 having been critic-
ally examined the necessary
explanations and corrections
the said field notes and the Sur-
veys the describe are hereby
approved

W. H. Bell
Sur Gen^l

I Genas F. Moody, having
 been appointed Deputy Surveyor, of the
 lands of the United States in Oregon,
 do solemnly swear that I will well
 and faithfully, and to the best of my
 skill and ability, execute the duties
 confided to me, pursuant to a con-
 tract with W. H. Odell, Surveyor
 General, of the public lands in Oregon,
 bearing date 23 day of April 1871,
 according to the laws of the United
 States and the instructions received
 from the said Surveyor General.

J. G. Moody

Sworn and Subscribed before me
 This 29th day of April 1871
 W. Davenport
 Coroner of the U.S. Circuit Court
 for the District of Oregon

I, M. A. Moody, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the pins upon uneven ground, and plumb the lally pins, whether by sticking or dropping the same; that I will report the true distance to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

M. A. Moody

Sworn and Subscribed before me }
 this 29th day of April 1871 }
 W. Davenport }
 Commissioner of the U.S. Circuit Court }
 for the District of Oregon }

A. E. G. Condon, do solemnly swear
that I will well and truly perform the
duties of a seaman, according to
instructions given me, and to the
best of my skill and ability.

E. G. Condon

Sworn and Subscribed before me
This 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon

J. E. H. Henderson do solemnly ²⁹⁸
swear that I will faithfully execute
the duties of chain carrier; that I
will level the chain upon uneven
ground, and plumb the lally
pins, whether by striking or dropping
the same; that I will report the
true distance to all notable
objects, and the true length of all
lines that I assist in measuring,
to the best of my skill and
ability.

C. H. Henderson

Sworn and Subscribed before me
this 29th day of April 1871
M. Davenport
Clerk of the U.S. Circuit Court
for the District of Oregon