

FIELD NOTES

Of the survey of the *Subdivisional*
Lines of Township *2 South Range 30*
East Willamette Meridian, Oregon.

Executed by *Geo. S. Peshin*

U. S. Deputy Surveyor, under his Contract No *293*

dated *Aug 12* 1878

List of the names of the persons employed to assist in running, measuring and marking the lines of the foregoing survey.

Frank H. Carney Chainman.

Robert Alexander Chainman.

Chainman.

Herman D. Gradow Axeman.

Axeman.

Compassman.

Flagman.

2

2

PRELIMINARY OATHS OF ASSISTANTS.

WE, Frank H. Carney and
Robert Alexander

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain upon uneven ground, and plumb the tally pins, whether by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines, that we assist in measuring, to the best of our skill and ability.

Frank H. Carney Chainman.

Robert Alexander Chainman.

Chainman.

Subscribed and sworn to before me, this 2th
day of September 1878

J. S. Thompson Justice of Peace

WE, Hereward D. Gradon and

do solemnly swear that ~~we~~ I will well and truly perform the duties for which ~~we~~ I have been ~~generally~~ employed according to instructions and to the best of ~~my~~ skill and ability.

Hereward D. Gradon,
Aveman & Mound-builder

Subscribed and sworn to before me, this 2th
day of September 1878

J. S. Thompson Justice of Peace

INDEX.

Referring the lines to the pages of the field notes.

Town. *2. S.* Range *30 E.* Willamette Meridian.

6	<i>66</i>	5	<i>50</i>	4	<i>36</i>	3	<i>25</i>	2	<i>15</i>	1
<i>65</i>	<i>64</i>	<i>48</i>	<i>35</i>	<i>24</i>	<i>14</i>					
7	<i>63</i>	8	<i>47</i>	9	<i>34</i>	10	<i>28½</i>	11	<i>13</i>	12
<i>62</i>	<i>61</i>	<i>45</i>	<i>33</i>	<i>23</i>	<i>12</i>					
18	<i>60</i>	17	<i>44</i>	16	<i>32</i>	15	<i>22</i>	14	<i>11</i>	13
<i>59</i>	<i>58</i>	<i>43</i>	<i>31</i>	<i>21</i>	<i>10</i>					
19	<i>57</i>	20	<i>42</i>	21	<i>30</i>	22	<i>20</i>	23	<i>9</i>	24
<i>56</i>	<i>55</i>	<i>41</i>	<i>29</i>	<i>19</i>	<i>8</i>					
30	<i>54</i>	29	<i>40</i>	28	<i>28</i>	27	<i>18</i>	26	<i>7</i>	25
<i>53</i>	<i>52</i>	<i>38</i>	<i>27</i>	<i>17</i>	<i>6</i>					
31	<i>51</i>	32	<i>37</i>	33	<i>26</i>	34	<i>16</i>	35	<i>5</i>	36

Subdivisions of Township No. 2 South Range 30
East Willamette Meridian, Oregon.

East on a random line
between Sec. 25 and 36
Pa. $19^{\circ} 45'$ East

40.00 Set temporary $\frac{1}{4}$ Sec. cor.

80.52 Intersected East Boundary 42 lks
South of Stone, corner to Sec.
25 and 36 from which cor. Run
 $S 89^{\circ} 42'$ West on a true line
between Sec. 25 and 36

Pa. $22^{\circ} 57' E$

6.00 Spring branch course North -50
Spring about 2 chs South

7.50 House due South 2 chs

15.00 On table-land + 70

40.26 Set Stone $14 \times 7 \times 6$ for $\frac{1}{4}$ Sec. cor.

80.52 The cor. to Sec. 25. 26. 35 and 36

Land. South 65 chs level; soil
excellent 2nd rate; good for wheat
and other grain; good grass.
Sec. 36 is nearly all good land

Subdivisions of Township No. 2 South Range 30
East Willamette Meridian, Oregon.

7

7

North between Sec. 25 and 26

Bear 19° 45' East

4000* Set Stone 14 x 10 x 8 on level
for 1/4 Sec. cor.

8000 Set Stone 15 x 8 x 5 on north - 30
descent for cor. to Sec. 23. 24
25 and 26 dug pits and
drove pine stake as per
instructions

Land surface nearly level
soil, extra 2nd rate - good
wheat land; good bunch
grass

* All the stones used for setting
corners in this township are
of the same kind viz: Ferrugi-
nous Basalt - very hard,

East on a Random line between sec. 24 and 25

wa. $21^{\circ} 45'$ East

40.00 Set temporary $\frac{1}{4}$ sec. cor.

79.90 Intersected East Boundary 66 lks
south of stone corner to sec. 24 and
25 from which cor. I run
S. $89^{\circ} 32'$ West on a true line
between sec. 24 and 25

wa. $20^{\circ} 04'$ East

5.00 On table land + 20

25.00 begin to descend

36.00 Ravine opens to north - 80

39.95 Set Stone $14 \times 8 \times 6$ for $\frac{1}{4}$ sec. cor. + 50

45.00 On table land + 30

79.90 The cor. to sec. 23. 24. 25 and 26 - 30

Land: surface partly level; soil
on benches extra 2nd rate. hill-
sides 2nd and 3rd rate. good grass

Sec. 25 is nearly all good
wheat land & mostly level

North between sections. 23 and 24

ba. $21^{\circ} 45'$ East

40.00 Set Stone $18 \times 10 \times 8$ on level + 30

for $\frac{1}{4}$ Sec. Cor.

80.00 Set Stone $18 \times 12 \times 5$ on

level for cor. to Sec. 13, 14,

23, and 24 dug pits and

drove pine Stake as per
instructions

Land: Surface along this
mile is undulating; Soil
mostly excellent second rate
and good for wheat,
good bunch grass

East on a random line between sec. 13 and 24

Pa. 21° East

40.00 Set temporary $\frac{1}{4}$ Sec. cor.

80.10 Intersected East Boundary
44 lks south of stone cor. to sec.
13 and 24 from which cor. I run
 $S. 89^{\circ} 41'$ West on a true line
between sec. 13 and 24

Pa. $21^{\circ} 26'$ East

5.00 Foot of hill S.E. & N.W. - 40

25.00 Across bottom

40.00⁵ Set Stone $18 \times 14 \times 5$ on East +100
hillside for $\frac{1}{4}$ Sec. cor.

80.10 The cor. to sec. 13. 14. 23 and 24 + 40

Land: Surface partly broken
Soil, greater part extra 2nd rate
some 3rd rate. good for
grain, good bunch grass
About $\frac{1}{2}$ of sec. 24. is
level table land

Sept 2^d 1878

North between Sec. 13 and 14

Pa. 21° East

Gradually descending

36.00 steep descent - 80

40.00 Set Stone $15 \times 8 \times 5$ on north - 50

hillside for $\frac{1}{4}$ Sec. cor.

44.00 Foot of hill. Small valley N.W. & S.E. - 50

52.00 Begin to ascend

76.00 Top of hill + 200

80.00 Set Stone $17 \times 10 \times 6$ for cor.

to Sec. 11, 12, 13 and 14, dug pits and drove pine stake as per instructions

Land: Surface broken. Soil part 2nd and part 3rd rate & stony good grass.

12

12 Subdivisions of Township No. 2 South Range 30
East Willamette Meridian, Oregon.

East on a random line between sec. 12 & 13

Pa. 19° East

40.00 Set temporary $\frac{1}{4}$ sec. cor.

80.04 Intersected East Boundary 70 lks
South of stone cor. to sec. 12 and 13
from which cor. I. run
 $S. 89^{\circ} 30'$ West on a true line
between Sec 12 and 13

Pa. $21^{\circ} 20'$ East

40.02 Set Stone $20 \times 10 \times 6$ for - 30
quarter sec. cor.

80.04 The cor. to sec. 11. 12. 13. and 14 - 30

Land: surface nearly level
soil along line good 2nd rate
excellent - grass

Sec. 13 is mostly broken
About 200 acres in the N.E.
corner is nearly level and
good wheat land. Rem-
ainder 2nd and 3rd rate

71

74

FINAL AFFIDAVIT OF ASSISTANTS.

We hereby certify that we assisted George
S. Pershin Deputy Surveyor, in surveying
 the Sub division lines of Township
2 S. Range 30 East Willamette Meridian, Oregon,
 and that said lines have been in all respects, to the best of our knowledge and
 belief, well and faithfully surveyed and the boundary monuments planted ac-
 cording to the instructions furnished by the Surveyor-General; and we do
 further swear that we each of us performed the work assigned us, faithfully to
 the best of our ability, in the capacity hereby indicated by our signatures.

Frank H. Barney Chainman.

Robert Alexander Chainman.

Thomas D. Grady Axeman.

..... Axeman.

..... Compassman.

STATE OF OREGON, }
 County of Umatilla }

Subscribed and sworn to before me, this 11 day
 of September ~~August~~ 1878

J. W. Salisbury, J. P.

I, George S. Pershin

Deputy Surveyor, do solemnly swear that in pursuance of
a contract with James C. Tolman

U. S. Surveyor-General of the State of Oregon, bearing
date the 12th day of August 1878,

and in strict conformity with the Printed Manual of In-
structions, and the instructions given me by the Surveyor-
General, I have faithfully surveyed the Subdivision

lines of Township 2 South Range 30 East

aforsaid, and do further solemnly swear that the forego-
ing are the true and original field notes of such survey.

George S. Pershin
Deputy Surveyor.

STATE OF OREGON,
County of Multnomah }

Subscribed and sworn to before me, a Notary

Public in and for the said County and

State, this 1st day of September 1878

D. W. Wakefield
Notary Public in
& for Oregon

73

75

Office U. S. Surveyor General,

Portland, Oregon, *Sept 20,* 1878

The foregoing Field Notes of the survey of
the subdivisional lines of T. 2 S. R. 30 E. Mill Mev
executed by *George S. Pershir* U. S. Dept. Surv.
under his contract No. *293* dated *August 12th*
1878, having been critically examined, the necessary
corrections and explanations made, the said field notes
and the survey they describe, are hereby approved.

James C. Tolman
Surveyor-General.

