

1 /

Field Notes of the Survey of
the Exterior Boundaries of
Townships number 1 and 2
South of Ranges number 28,
29 and 30 East of the Will-
amette Meridian, in the
State of Oregon, by George
Willidms and George S.
Pershin, deputy surveyors,
under their contract
No. 154 bearing date the
6th day of June 1871,
commenced on the
7th day of August 1871
and finished on the 25th
day of October 1871.

2

The names of the persons,
employed as assistants in the
survey of the Exterior Bound-
aries of Townships number
1 and 2 South, of Ranges
number 28, 29 and 30 East
of the Willamette Meridian
in the State of Oregon were
as follows:

Wilbur G. Kerns	Chairman
Lewis R. Smith	Chairman
William J. Cox	Flagman
Frank Ramps	Axeman
George S. Pershon (deputy)	Compassman

3A

We hereby certify that we assisted *George S. Pershin*, Deputy Surveyor, in surveying the

Exterior Boundaries of

Township number *1 and 2 South* ~~North~~ of the base line of Range number *28 29 and 30 East* of the Willamette meridian, and that said Township, ^{Exterior} have been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

Wilbur G. Kern Chairman
Lewis R. Smith Chairman
William J. Cox Flagman
Frank Camp Axeman

Subscribed and sworn to by the above named persons, before me, a *Notary Public* for the county of *Multnomah* in the State of *Oregon* this *14th* day of *November*, 18 *71*

J. A. McCreisen
Notary Public
for Oregon

30

I Frank Ramp do solemnly swear that I will well and truly perform the duties of Axeman according to instructions given me, and to the best of my skill and ability.

Frank Ramp.

Subscribed by the said Frank Ramp

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

July 1871
Chas E. Hsley
Notary Public

30

I William J. Cox

do solemnly swear that I will well and truly perform the duties of flagman according to instructions given me, and to the best of my skill and ability.

Wm J. Cox

Subscribed by the said Wm J. Cox

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

1877
Chas E. Husby
Notary Public



South Boundary T. 2 S. R. 30 E. Willamette Meridian

Chs. East on a true line along the Feet
South Boundary of Sec. 36.

Pa. $20^{\circ} 42'$ East-

^{3.00} 3.00 A ravine bears S. W. - 10

^{35.00} 35.00 Top of bluff a table land + 350

^{40.00} 40.00 Set a stone $22 \times 10 \times 6$ for
 $\frac{1}{4}$ Sec. cor.

Pa. $20^{\circ} 12'$ East-

^{80.00} 80.00 To a point for corner to - 8

Townships 2 and 3 South
Ranges 30 and 31 East-

Set a stone $20 \times 8 \times 7$ and
raised a mound of stone
as per instructions.

Land Western part broken
Eastern part level.

2d and 3d rate

October 20th 1871

Between Ranges 30 and 31 E. of 2 S. Willamette Meridian
 Chs From the corner to Townships Twp
 2 and 3 S. Ranges 30 and 31
 East - 1 run
 North along the East Bound-
 ary of Sec. 36
 Va. $20^{\circ} 55'$ East

35.00 A road from Settlements ⁻⁸⁰ -80
 to timber bears N.W. and S.E.

37.00 A canyon bears N.W. ⁻¹⁰ -10

40.00 Set a stone $18 \times 18 \times 4$ on N. ⁺¹⁵ +15
 hillside for $\frac{1}{4}$ Sec. cor
 Va. $18^{\circ} 45'$ East

80.00 Set a stone $24 \times 8 \times 6$ on N. ⁺³⁰ +30
 hillside for corner to Sec
 25.36. 30 and 31
 Land. rolling 2d and
 3d rate

Between Ranges 30 and 31 E. T. 28 Willamette Meridian

Chs North on the East Bound - Boundary of Sec 25.

Pa. 22° 51' East

^{37.00} 37.00 A road bears N. E and S. W. -160

^{40.00} 40.00 Set a stone 22 x 12 x 3 on S. E hillside for 1/4 Sec Cor +20

Pa. 19° 18' East

^{80.00} 80.00 Set a stone 20 x 7 x 5 on E hillside for corner to Sec 24, 25, 29 and 30 +60

Land. hilly and somewhat broken, 2d and 3d rate

82
Between Ranges 30 and 31 E. T. 2 S. Willamette Meridian

Chs North on the East Boundary of Sec. 24

Co 20° 04' East,

40.00 Set a stone 16 x 8 x 6 on E. side near top of hill for 1/4 Sec. cor

Co. 19° 48' East

74.50 A road bears N. W. and S. E. Canyon bears N. W.

80.00 Set a stone 22 x 7 x 5 on S. W. hillside for corner to Sec 13, 24, 18 and 19. Land hilly and broken. 2d and 3d rate

Between Ranges 30 and 31 E. of S. Willamette Meridian

Chs North on the East Bound-
dary of Sec. 13.

Wa. $21^{\circ} 20'$ East

^{25.00}
25.00 Top of hill +160

^{40.00}
40.00 Set a stone $16 \times 8 \times 6$ for
 $\frac{1}{4}$ Sec. cor. -10

Wa. $21^{\circ} 46'$ East

Gradually descending

^{80.00}
80.00 Set a stone $24 \times 8 \times 3$ for
corner to Sec. 12, 13, 7
and 18 -40

Land. South part broken
N. 53- chains a plain inclin-
ed to the N.

Land 2d and 3d rate

Between Ranges 30 and 31 6th 2^d Willame the Meridian

Chs North on the East Boundary
of Sec. 12.

Pa. 21° 02' East,

40.00 Set a stone 18 x 9 x 4 for ⁻⁸⁰
1/4 Sec. Cor -80

Pa. 21° 28' East

53.00 A canyon bears W. -30 -30

75.00 A Tolle land +120 +120

80.00 Set a stone 18 x 8 x 5
for corner to Sec. 1, 12,
7 and 8.

Land, rolling hills
2d and 3d rate.

Between Ranges 30 and 31 E. T. 2 S. Willamette Meridian

Chain North on the East Boundary Feet
of Sec. 1.

Be. $22^{\circ} 10'$ East

^{40.00} 40.00 Set a stone $18 \times 9 \times 4$ for
 $\frac{1}{4}$ Sec. Cor. -30

Be. $21^{\circ} 43'$ East =

^{80.00} 80.00 Set a stone $26 \times 8 \times 7$ for
corner to Townships
1 and 2 S. Ranges 30 and
31 East; raised a mound
of stone as per instruc-
tions -20

Land on a plane slight-
ly inclined North
excellent 2d rate

October 21st 1871

102

Blank

I, ... *George S. Pershin* ..., Deputy Surveyor,
do solemnly swear that, in pursuance of a contract with
William H. Odell Surveyor of the public
lands of the United States in the State of ... *Oregon* ...
bearing date the ... *6th* day of ... *June* ...
1871, and in strict conformity to the laws of the United States
and the instructions furnished by the said Surveyor General, I
have faithfully surveyed the

Exterior Boundaries

of Townships number *1 and 2 South* ~~North~~ of the base
line, of Ranges number *28, 29 and 30 East* of the Willamette
meridian, in the ... *State* aforesaid, and do further
solemnly swear that the foregoing are the true and original field
notes of such survey.

George S. Pershin
Deputy Surveyor.

Subscribed by said *George S. Pershin*
Deputy Surveyor, and sworn to before me, a ... *Notary* ...
... *Public* ... for ... *Marion* ... county, in
the State of ... *Oregon* ... this ... *8th* day of
... *December* ..., 1871

J. M. Patterson
Notary Public

U. S. Surveyor General's Office

Eugene City - April 6th 1892

The foregoing field notes of the Survey of
the Exterior lines of Townships 192 South
Ranges 28, 29 & 30 East Will, Mer, Or, are
executed by George William & George S.
Peshier Deputy Surveyors under contract
No 154 bearing date June 6th 1891, having
been critically examined the necessary cor-
rections and explanations made to said
field notes and their surveys they describe
are hereby approved -

W. H. Odell

Sur Genl Or