

1 /

Field Notes of the Survey of
the Exterior Boundaries of
Townships number 1 and 2
South of Ranges number 28,
29 and 30 East of the Will-
amette Meridian, in the
State of Oregon, by George
Willidms and George S.
Perskin, deputy surveyors,
under their contract
No. 154 bearing date the
6th day of June 1871,
commenced on the
7th day of August 1871
and finished on the 25th
day of October 1871.

2

The names of the persons,
employed as assistants in the
survey of the Exterior Bound-
aries of Townships number
1 and 2 South, of Ranges
number 28, 29 and 30 East
of the Willamette Meridian
in the State of Oregon were
as follows:

Wilbur G. Kerns	Chairman
Lewis R. Smith	Chairman
William J. Cox	Flagman
Frank Ramps	Axeman
George S. Pershon (deputy)	Compassman

3A

We hereby certify that we assisted *George S. Pershin*, Deputy Surveyor, in surveying the

Exterior Boundaries of

Township number *1 and 2 South* ~~North~~ of the base line of Range number *28 29 and 30 East* of the Willamette meridian, and that said Township, ^{Exterior} have been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

Wilbur G. Kern Chairman
Lewis R. Smith Chairman
William J. Cox Flagman
Frank Camp Axeman

Subscribed and sworn to by the above named persons, before me, a *Notary Public* for the county of *Multnomah* in the State of *Oregon* this *14th* day of *November*, 18*71*

J. A. McCreisen
Notary Public
for Oregon

30

I Frank Ramp do
solemnly swear that I will well and
truly perform the duties of Axeman
according to instructions given me, and
to the best of my skill and ability.

Frank Ramp.

Subscribed by the said Frank
Ramp

and sworn to before me, a Notary Public
for the County of Multnomah in the
State of Oregon, this 25th day

July 187
Chas E. Hsley
Notary Public

30

I William J. Cox

do solemnly swear that I will well and truly perform the duties of flagman according to instructions given me, and to the best of my skill and ability.

Wm J. Cox

Subscribed by the said Wm J. Cox

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

1877
Chas E. Husby
Notary Public



Between Ranges 29 and 30 E. T. 2 S. Willamette Meridian

Chs. North on the East Bound-ary
dary of Sec. 1

va. $22^{\circ} 06'$ East-

40.00 Set a stone $20 \times 10 \times 8$ on N. -2.80

W. hillside for $\frac{1}{4}$ Sec cor

va. $21^{\circ} 38'$ East-

77.50 County road from Butter
Creek to little Butter Creek
bears N. E. and S. W.

80.00 Set a stone $24 \times 10 \times 8$ in -60

middle of canyon for
corner to Townships
1 and 2 S. Ranges 29 and
30 East, raised a mound
of stone, as per instruc-
tions

Canyon bears N. E.

Land, hilly, 2d rate

September 7th 1871

Between Ranges 30 and 31 E. T² S. Willamette Meridian

Chain North on the East Boundary Feet
of Sec. 1.

Be. $22^{\circ} 10'$ East

^{40.00} 40.00 Set a stone $18 \times 9 \times 4$ for
 $\frac{1}{4}$ Sec. Cor. -30

Be. $21^{\circ} 43'$ East =

^{80.00} 80.00 Set a stone $26 \times 8 \times 7$ for
corner to Townships
1 and 2 S. Ranges 30 and
31 East; raised a mound
of stone as per instruc-
tions -20

Land on a plane slight-
ly inclined North
excellent 2d rate

October 21st 1871

Between Townships 1 and 2 S. R. 30 E Willamette Meridian.

Chains From the Corner to Townships Ties
1 and 2 S. Ranges 30 and 31
East, I run

West - on a random line
between said Townships
Bearing $21^{\circ} 45'$ East -

I set temporary half
mile and mile posts
at every 40 and 80 chains
and at 5 miles 78 chains
and 47 links. to a point
1 chain and 6 links South
of the corner to Town-
ships 1 and 2 S. Ranges 29
and 30 East. Therefore
the correction will be $17\frac{2}{3}$
links South per mile.

From the corner to
Townships 1 and 2 South
Ranges 29 and 30 East,
I run

Between Townships 1 and 2 S. R. 3 E. Willamette Meridian.

Chain South $89^{\circ} 53'$ East on a true line Feet
between Sec. 6 and 31

Wa. $20^{\circ} 21'$ East

^{2.00}
2.00 County road bears N. E. and S. W.

Foot of hill bears N. E. and S. W.

^{38.47}
38.47 Set a stone $20 \times 8 \times 4$ on top of hill for $\frac{1}{4}$ Sec. cor +260

Wa. $21^{\circ} 33'$ East

A small table land

^{78.47}
78.47 Set a stone $20 \times 7 \times 5$ for corner to Sec. 5, 6, 31 and 32.

Land first half mile broken hillside, last half mile level table land.

2d and 3d rate

South $89^{\circ} 53'$ East on a true line between Sec. 5 and 32

^{5.00}
5.00 ^{Wa. $21'$ East} Begin descent

^{25.00}
25.00 A ravine bears N. E. -200

Between Townships 1 and 2 S Range 30 E Willamette Mend.

38.00 Foot of hill bears N and S-100 Feet -100

40.00 Set a stone 20x8x4 in canyon for 1/4 Sec cor Va. 22° 28' East

65.00 Top of hill +290 +290

75.00 Begin to descend

80.00 Set a stone 24x7x5 on S.E. hillside for corner to sec. 4, 5, 32 and 33. -15 -15

Land high hills and broken 2d and 3d rate

South 29° 53' East on a true line between Sec. 4 and 33

Va. 21° 40' East -250

40.00 Set a stone 20x6x5 on S.E. hillside for 1/4 Sec. cor. -250

Va. 19° 47' East

49.75 A ravine bears N.E. -80 -80

61.00 On spur extending N.E. +60 +60

68.00 Foot of hill bears -120 -120

Between Townships 1 and 2 S. R. 30 E. Willamette Meridian

Chs.

Feet

- 13.60 N and S.
- 73.60 Butter Creek 30 lks wide
runs N.
- 76.50 Foot of a ledge of Basalt-
Rock 25 ft. high bears
N and S.
- 80.00 Set a stone 18 x 8 x 6 on
a bench for corner to
Sec. 3, 4, 33, and 34
Land very hilly and
broken. 2d and 3d rate
Small part on the creek
is level and first rate
and is good for farming
-
- South $29^{\circ}53'$ East on a true
line between Sec. 3 and 34
Bearing $22^{\circ}16'$ East.
- 100 Creek road bears N and S.
- 40.00 Set a Stone 20 x 10 x 3 on top
of hill for $\frac{1}{4}$ Sec cor.

+30

+450

Between Townships 1 and 2 S. R. 30 E. Willamette Meridian

Chs	Va. 22° 28' East -	Feet
-----	--------------------	------

79.00	A ravine bears N. -70	-70
-------	-----------------------	-----

80.00	Set a stone 24 x 6 x 5 on E. side of ravine for corner to Sec. 2, 3, 34 and 35 Land high broken bluffs 3d rate part worthless	
-------	---	--

South 89° 53' East on a true line between Sec. 2 and 35

Va. 26° 26' East

5.00	On spur, bears N. E. +50	+50
------	--------------------------	-----

34.50	A ravine bears N. E. -250	-250
-------	---------------------------	------

40.00	Set a stone 18 x 8 x 6 on N. ⁺⁶⁰	+60
-------	---	-----

point of spur for 1/4 Sec. cor

Va. 23° 14' East

50.00	A canyon bears N. -80	-80
-------	-----------------------	-----

80.00	Set a stone 16 x 9 x 6 on N. ⁺²⁸⁰	+280
-------	--	------

side of hill for corner to Sec. 1, 2, 35 and 36

Land high broken bluffs

Between Townships 1 and 2 S. R. 30 E. Willamette Meridian.

Chain	2d and 3d rate	Feet
-------	----------------	------

South $89^{\circ} 53'$ East on a true
line between Sec. 1 and 36

5.00	On table land $20^{\circ} 18' E$	+ 30
------	----------------------------------	------

40.00	Set a stone $18 \times 7 \times 5$ for $\frac{1}{4}$ Sec. cor.	+ 10
-------	--	------

Pa. $20^{\circ} 18'$ East

80.00	The corner to Townships	+ 20
-------	-------------------------	------

1 and 2 S. Ranges 30 and 31
East

Land, nearly level, 2d and
3d rate

October 24th 1871

General Descriptions

This Township is very hilly and broken except a small part on the east side, which is more nearly level. The principal part of the land is second rate there is much third rate, and some worthless, also a small part along the creek is first rate and good for farming.

There are a few Cotton wood trees and a thick growth of Willow and Alder under-bush along the creeks, no other timber.

The second and third rate land produces abundance of Bunch Grass making it valuable for grazing purposes.

There are already many places occupied by settlers. The Township should therefore be subdivided.

102

Blank

I, ... *George S. Pershin* ..., Deputy Surveyor,
do solemnly swear that, in pursuance of a contract with
William H. Odell Surveyor of the public
lands of the United States in the State of ... *Oregon* ...
bearing date the ... *6th* day of ... *June* ...
1871, and in strict conformity to the laws of the United States
and the instructions furnished by the said Surveyor General, I
have faithfully surveyed the

Exterior Boundaries

of Townships number *1 and 2 South* ~~North~~ of the base
line, of Ranges number *28, 29 and 30 East* of the Willamette
meridian, in the ... *State* aforesaid, and do further
solemnly swear that the foregoing are the true and original field
notes of such survey.

George S. Pershin
Deputy Surveyor.

Subscribed by said *George S. Pershin*
Deputy Surveyor, and sworn to before me, a ... *Notary* ...
... *Public* ... for ... *Marion* ... county, in
the State of ... *Oregon* ... this ... *8th* day of
... *December*, 1871

J. M. Patterson
Notary Public

U. S. Surveyor General's Office

Eugene City - April 6th 1892

The foregoing field notes of the Survey of
the Exterior lines of Townships 192 South
Ranges 28, 29 & 30 East Will, Mer, Oregon
executed by George William & George S.
Peshier Deputy Surveyors under contract
No 154 bearing date June 6th 1891, having
been critically examined the necessary cor-
rections and explanations made to said
field notes and their surveys they describe
are hereby approved -

W. H. Odell

Sur Genl Ore