

1 /

Field Notes of the Survey of  
the Exterior Boundaries of  
Townships number 1 and 2  
South of Ranges number 28,  
29 and 30 East of the Will-  
amette Meridian, in the  
State of Oregon, by George  
Willidms and George S.  
Pershin, deputy surveyors,  
under their contract  
No. 154 bearing date the  
6<sup>th</sup> day of June 1871,  
commenced on the  
7<sup>th</sup> day of August 1871  
and finished on the 25<sup>th</sup>  
day of October 1871.



2

The names of the persons,  
employed as assistants in the  
survey of the Exterior Bound-  
aries of Townships number  
1 and 2 South, of Ranges  
number 28, 29 and 30 East  
of the Willamette Meridian  
in the State of Oregon were  
as follows:

Wilbur G. Kerns	Chairman
Lewis R. Smith	Chairman
William J. Cox	Flagman
Frank Ramps	Axeman
George S. Pershon (deputy)	Compassman



3A

We hereby certify that we assisted *George S. Pershin*, Deputy Surveyor, in surveying the

*Exterior Boundaries of*

Township number *1 and 2 South* ~~North~~ of the base line of Range number *28 29 and 30 East* of the Willamette meridian, and that said Township, <sup>Exterior</sup> have been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

*Wilbur G. Kern* Chairman  
*Lewis R. Smith* Chairman  
*William J. Cox* Flagman  
*Frank Camp* Axeman

Subscribed and sworn to by the above named persons, before me, a *Notary Public* for the county of *Multnomah* in the State of *Oregon* this *14<sup>th</sup>* day of *November*, 18 *71*

*J. A. McCreisen*  
*Notary Public*  
*for Oregon*



30

I Frank Ramp do solemnly swear that I will well and truly perform the duties of Axeman according to instructions given me, and to the best of my skill and ability.

Frank Ramp.

Subscribed by the said Frank Ramp

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

July 1871  
Chas E. Husley  
Notary Public



30

I William J. Cox

do solemnly swear that I will well and truly perform the duties of flagman according to instructions given me, and to the best of my skill and ability.

Wm J. Cox

Subscribed by the said Wm J. Cox

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

1877  
Chas E. Husby  
Notary Public





South Boundary T. 2 Range 29 E Willamette Meridian  
 Chs. East on a true line along the South Boundary of Sec. 36.

Pa.  $21^{\circ} 05'$  East-

450 A ravine bears N. -60

40.00 Set a stone  $18 \times 12 \times 4$  on S.W. hillside for  $\frac{1}{4}$  Sec. cor +360

Pa.  $21^{\circ} 00'$  East-

43.00 Top of hill +10

80.00 Set a stone,  $20 \times 8 \times 7$ , on E. hillside, near foot of hill, -240

for corner to Townships, 2 and 3 South Ranges  
 $29$  and  $30$  East and raised a mound of stone as per instructions

Land high hills, 2d and 3d rate.

September 6<sup>th</sup> 1871



South Boundary. T. 2 S. R. 30 & Willamette Meridian

Chs From the corner to Townships 2 and 3 South, Ranges 29 and 30 East - A run.

East on a random line along the South Boundary of Townships 2 S. Range 30 East

Dir. 20° 35' East -

I set temporary half mile and mile posts at every 40 and 80 chains, and at 6 miles I make diligent search for the corner to Townships 2 and 3 S. Ranges 30 and 31 East, but can find no trace thereof.

I now commence at the corner to Townships 1 and 2 South Ranges 29 and 30 East and run East on a random line between said Townships



South Boundary T. 2 S. R. 30 E. Willamette Meridian

Chs.

Co. 20° 21' East

ft

I set temporary half mile and mile posts at every 40 and 80 chains and at 6 miles I make diligent search, but cannot find any trace of corner to Townships 1 and 2 S. Ranges 30 and 31 East

I now proceed to the corner to Townships 1 S. Ranges 29 and 30 East at the Base Line and trace the Base Line East 7 miles which is more than one mile East of the place where the closing corner of Townships 1 S. Ranges 30 and 31 should be, but I can find no trace of any closing corners



Boundary To S R 30 E Willamette Meridian  
 Chs from surveys on the south of #1-  
 the Base Line; but in several  
 places I find two corners from  
 two to six chains apart marked  
 alike and for the same sections  
 which shows that there has  
 been some irregularity in  
 marking the corners on the  
 Base line

I now begin at the corner  
 to sections 35 and 36 (on the  
 Base Line) in Township 1 N,  
 Range 30 East near which  
 corner, the corner of Townships  
 1 S. Ranges 30 and 31 should be  
 and I run

South 12 miles making  
 diligent search at every mile  
 but cannot find any trace  
 of any corners or surveys



South Boundary T. S. R. 30 E. Willamette Meridian

Rehs I therefore send a messenger, Peet  
with a statement of the above  
named facts, to the Surveyor  
General William H. Odell  
and receive instructions  
to establish corners for the  
afore-said Townships.

+

From the corner to Townships  
2 and 3 S. Ranges 29 and 30 East  
I run

East on a true line along  
the South Boundary of Sec. 31

ba.  $20^{\circ} 35'$  East -

21.00 A canyon bears N. E. - 80

37.75 Set a stone  $20 \times 8 \times 7$  on N. W.  
hillside for  $\frac{1}{4}$  Sec. Cor. +100



South Boundary of S. 30 E. Willamette Meridian

Chs.	Pa. 21° 16' East-	Set
70.00	A spring branch runs N.	-160
77.75	Set a stone 30x10x4 on N. hillside for corner to sec 31, 32. 5 and 6.	+50
	Land rolling hills 2d and 3d rate.	

East on a true line along the South Boundary of sec. 32.

Pa. 21° 28' East-

14.00	Top of ridge bears N. and S.	+120
30.50	A ravine bears N.E.	-150
40.00	Set a stone 18x6x4 on N.W. hillside for 1/4 Sec. cor.	+120

Pa. 21° 14' East-

42.00	Top of hill	+ 8
53.75	A road from the Settlements below to the timber in Blue Mts. bears N.W. and S.E.	-130
80.00	Set a stone 18x6x4 on W. side	+150



South Boundary T. 2 S. R. 30 E. Willamette Meridian

Chs. near top of ridge for corner Feet,  
to sec. 4, 5, 32 and 33.

Land, high broken ridges,  
2d rate

East on a true line along the  
South Boundary of sec. 33.

Pa.  $20^{\circ} 42'$  East.

4.00	Top of ridge bears N. and S.	+10	+10
35.00	A spring branch runs N.	-150	-150
40.00	Set a stone 20x10x4 on N.	+50	+50

hillside for  $\frac{1}{4}$  Sec. cor.

Pa.  $20^{\circ} 12'$  East

57.75	A canyon bears N.W.	-50	-50
80.00	Set a stone 22x8x6 on S.W.	+320	+320

hillside for corner to sec.  
3, 4, 33 and 34.

Land, hilly and broken  
2d and 3d rate



South Boundary of Sec 30 & Willamette Meridian

Chs East on a true line along the South Boundary of Sec. 34.

Pa.  $21^{\circ} 03'$  East:

6.00	Top of hill	+50
18.00	A ravine bears N.	-120
39.50	A brook 5 lks wide runs N.	-300
40.00	Set a stone $22 \times 10 \times 5$ on E bank of brook for $\frac{1}{4}$ Sec. Cor	

Pa.  $19^{\circ} 42'$  East

80.00	Set a stone $24 \times 6 \times 5$ on top of hill for corner to Sec. 2, 3, 34 and 35	+500
-------	--------------------------------------------------------------------------------------	------

Land high, steep, broken hills. 2d and 3d rate, part worthless



South Boundary of Range 30 E. Willamette Meridian

Chs East on a true line along the South Boundary of Sec. 35.

Va. 21° 50' East-

32.50 A ravine bears N. -450 -450

40.00 Set a stone 18x10x8 on W. hillside for 1/4 Sec. cor +250 +250

Va. 21° 55' East-

48.00 Top of hill +50 +150

69.25 Butter Creek 20 lks wide -450 -450 runs N. W

80.00 Set a stone 18x8x7 on S point of Spur for corner to Sec. 1, 2, 35 and 36 +125 +125

Land high broken bluffs 3 a rate large part worthless



South Boundary T. 2 S. R. 30 E. Willamette Meridian

Chs. East on a true line along the Feet  
South Boundary of Sec. 36.

Pa.  $20^{\circ} 42'$  East-

<sup>3.00</sup> 3.00 A ravine bears S. W. - 10

<sup>35.00</sup> 35.00 Top of bluff a table land + 350

<sup>40.00</sup> 40.00 Set a stone  $22 \times 10 \times 6$  for  
 $\frac{1}{4}$  Sec. cor.

Pa.  $20^{\circ} 12'$  East-

<sup>80.00</sup> 80.00 To a point for corner to - 8

Townships 2 and 3 South  
Ranges 30 and 31 East-

Set a stone  $20 \times 8 \times 7$  and  
raised a mound of stone  
as per instructions.

Land Western part broken  
Eastern part level.

2d and 3d rate

October 20<sup>th</sup> 1871



102

Blank

I, ... *George S. Pershin* ..., Deputy Surveyor,  
do solemnly swear that, in pursuance of a contract with .....  
*William H. Odell* ..... Surveyor of the public  
lands of the United States in the State of ... *Oregon* ...  
bearing date the ... *6<sup>th</sup>* ... day of ... *June* ...  
1871, and in strict conformity to the laws of the United States  
and the instructions furnished by the said Surveyor General, I  
have faithfully surveyed the .....

*Exterior Boundaries*

of Townships number *1 and 2 South* ~~North~~ of the base  
line, of Ranges number *28, 29 and 30 East* of the Willamette  
meridian, in the ... *State* ... aforesaid, and do further  
solemnly swear that the foregoing are the true and original field  
notes of such survey.

*George S. Pershin*  
Deputy Surveyor.

Subscribed by said *George S. Pershin* .....  
Deputy Surveyor, and sworn to before me, a ... *Notary* ...  
... *Public* ... for ... *Marion* ... county, in  
the State of ... *Oregon* ... this ... *8<sup>th</sup>* ... day of  
... *December*, 1871

*J. M. Patterson*  
Notary Public



U. S. Surveyor Genl's Office

Eugene City - April 6<sup>th</sup> 1892

The foregoing field notes of the Survey of  
the Exterior lines of Townships 192 South  
Ranges 28, 29 & 30 East Will, Mer, Or, are  
executed by George William & George S.  
Peshier Deputy Surveyors under contract  
No 154 bearing date June 6<sup>th</sup> 1891, having  
been critically examined the necessary cor-  
rections and explanations made to said  
field notes and then surveyed they describe  
are hereby approved -

W. H. Odell

Sur Genl Ore