

1 /

Field Notes of the Survey of  
the Exterior Boundaries of  
Townships number 1 and 2  
South of Ranges number 28,  
29 and 30 East of the Will-  
amette Meridian, in the  
State of Oregon, by George  
Willidms and George S.  
Perskin, deputy surveyors,  
under their contract  
No. 154 bearing date the  
6<sup>th</sup> day of June 1871,  
commenced on the  
7<sup>th</sup> day of August 1871  
and finished on the 25<sup>th</sup>  
day of October 1871.

2

The names of the persons,  
employed as assistants in the  
survey of the Exterior Bound-  
aries of Townships number  
1 and 2 South, of Ranges  
number 28, 29 and 30 East  
of the Willamette Meridian  
in the State of Oregon were  
as follows:

Wilbur G. Kerns	Chairman
Lewis R. Smith	Chairman
William J. Cox	Flagman
Frank Ramps	Axeman
George S. Pershon (deputy)	Compassman

3A

We hereby certify that we assisted *George S. Pershin*, Deputy Surveyor, in surveying the

*Exterior Boundaries of*

Township number *1 and 2 South* ~~North~~ of the base line of Range number *28 29 and 30 East* of the Willamette meridian, and that said Township, <sup>Exterior</sup> have been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

*Wilbur G. Kern* Chairman  
*Lewis R. Smith* Chairman  
*William J. Cox* Flagman  
*Frank Camp* Axeman

Subscribed and sworn to by the above named persons, before me, a *Notary Public* for the county of *Multnomah* in the State of *Oregon* this *14<sup>th</sup>* day of *November*, 18 *71*

*J. A. McCreisen*  
Notary Public  
for Oregon

30

I Frank Ramp do  
solemnly swear that I will well and  
truly perform the duties of Axeman  
according to instructions given me, and  
to the best of my skill and ability.

Frank Ramp.

Subscribed by the said Frank  
Ramp

and sworn to before me, a Notary Public  
for the County of Multnomah in the  
State of Oregon, this 25th day

July 1871  
Chas E. Husley  
Notary Public

30

I William J. Cox

do solemnly swear that I will well and truly perform the duties of flagman according to instructions given me, and to the best of my skill and ability.

Wm J. Cox

Subscribed by the said Wm J. Cox

and sworn to before me, a Notary Public for the County of Multnomah in the State of Oregon, this 25th day

1877  
Chas E. Husby  
Notary Public



South Boundary T. 2 Range 29 E Willamette Meridian  
 Chs. East on a true line along the South Boundary of Sec. 36.

Pa.  $21^{\circ} 05'$  East-

450 A ravine bears N. -60

40.00 Set a stone  $18 \times 12 \times 4$  on S.W. hillside for  $\frac{1}{4}$  Sec. cor +360

Pa.  $21^{\circ} 00'$  East-

43.00 Top of hill +10

80.00 Set a stone,  $20 \times 8 \times 7$ , on E. hillside, near foot of hill, -240

for corner to Townships, 2 and 3 South Ranges 29 and 30 East and raised a mound of stone as per instructions

Land high hills, 2d and 3d rate.

September 6<sup>th</sup> 1871

45

Between Ranges 29 and 30 E. T. S. Willamette Meridian  
Chs From the corner to Townships Feet  
2 and 3 S. Ranges 29 and 30 East  
A run

North along the East-Boun-  
dary of sec. 36

Pa.  $20^{\circ} 35'$  East-

3.50	A ravine bears E.	-10
25.00	Top of hill	+220
40.00	Set a stone $18 \times 8 \times 4$ on E	-30

hillside for  $\frac{1}{4}$  sec. Cor

Sec. 25, Pa.  $21^{\circ} 00'$  East:

59.25	A ravine bears N.E.	-150
-------	---------------------	------

76.00	A ravine bears S.E.	+40
-------	---------------------	-----

80.00	Set a stone $18 \times 8 \times 6$ on S.W.	+60
-------	--	-----

hillside for corner to  
Sec. 25, 36, 30 and 31.

Land high rolling  
hills, 2d and 3d rate

Between Ranges 29 and 30 E. T. 2 S. Willamette Meridian

Chs. North on the East Boundary Feet  
of Sec. 25

Pa.  $21^{\circ} 35'$  East -

4.00	Top of hill	+ 15
16.00	A wide ravine bears N.E.	- 80
24.00	Top of hill	+ 80
40.00	Set a stone $20 \times 14 \times 5$ on N. hillside for $\frac{1}{4}$ Sec. cor	- 50

Pa.  $21^{\circ} 50'$  East -

80.00	Set a stone $20 \times 8 \times 5$ at foot of hill for corner to Sec. 24, 25, 19, and 30.	- 450
-------	---	-------

Land, high broken bluffs,  
2d and 3d rate, part-  
worthless



Between Ranges 29 and 30 E. 2<sup>d</sup> S Willamette Meridian  
Chs. North on the East Boundary of  
of Sec. 24.

Pa. 20° 15' East-

33.75 Johnson Creek 25 lks wide -25-  
runs N. E.  
7.25 Foot of hill bears N. E. and S. W.  
25.00 On Spur bears S. E. +280  
40.00 Set a stone 24x12x3 on E,  
hillside for 1/4 Sec. cor -60

Pa. 20° 30' East-

46.25 A ravine bears S. E. -20  
80.00 Set a stone 24x8x5-on S. W.  
hillside for corner to  
Sec. 13, 24, 18 and 19 +250  
Land, high broken bluffs  
2<sup>d</sup> and 3<sup>d</sup> rate, large  
part-worthless

Between Ranges 29 and 30. E. T. S. Willamette Meridian

Chs North on the East Bound-  
ary of Sec. 13.

Wa.  $21^{\circ}46'$  East-

4.00 Top of hill +15-

A gradual descent-

40.00 Set a stone  $18 \times 7 \times 6$  for  
1/4 Sec. cor. -40

Wa.  $20^{\circ}35'$  East-

65.50 A ravine bears N.E. -90

80.00 Set a stone  $22 \times 12 \times 4$  on S.E. +50  
hillside for corner to Sec.  
12. 13. 7 and 18

Land, high somewhat  
broken. 2d rate

Between Ranges 29 and 30 E. T. 2 S. Willamette Meridian  
Chs North on the East Boundary of Sec  
of Sec 12.

Pa. 19° 40' East

Gradual descent

40.00 Set a stone 28 x 10 x 5  
for 1/4 Sec. cor. -40

Pa. 19° 25' East

45.75 A ravine bears N. E. -20

80.00 Set a stone 26 x 8 x 6 for -20  
corner to Sec. 1, 12, 6,

and 7  
Land high, somewhat-  
broke slopes North.  
2d part

Between Ranges 29 and 30 E. T. 2 S. Willamette Meridian

Chs. North on the East Bound-ary  
dary of Sec. 1

va.  $22^{\circ} 06'$  East-

40.00 Set a stone  $20 \times 10 \times 8$  on N. -2.80  
W. hillside for  $\frac{1}{4}$  Sec cor

va.  $21^{\circ} 38'$  East-

77.50 County road from Butter  
Creek to little Butter Creek  
bears N. E. and S. W.

80.00 Set a stone  $24 \times 10 \times 8$  in -60  
middle of canyon for

corner to Townships  
1 and 2 S. Ranges 29 and  
30 East, raised a mound  
of stone, as per instruc-  
tions

Canyon bears N. E.

Land, hilly, 2d rate

September 7<sup>th</sup> 1871