

FIELD NOTES

Of the survey of the *Subdivisional*
 Lines of Township *2 South Range 30 1/2 East,*
Willamette Meridian, Oregon.

Executed by *George S. Pershin*

U. S. Deputy Surveyor, under his Contract

No. *313* dated *Dec 7* 1878

List of the names of the persons employed to assist in running, measuring and marking the lines of the foregoing survey.

George H. Piper Chainman.

John M^r Donald Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

..... Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

We, George H Piper and
John M^c Donald

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain upon uneven ground, and plumb the tally pins, whether by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines, that we assist in measuring, to the best of our skill and ability.

George H Piper Chainman.
John M^c Donald Chainman.
..... Chainman.

Subscribed and sworn to before me, this 26th

day of December 1878
George S. Perkins

no account
We George H Piper and
John M^c Donald

do solemnly swear that we will well and truly perform the duties for which we have been severally employed according to instructions and to the best of our skill and ability.

A Notarial Instrument
George H Piper
John M^c Donald
Bond

Subscribed and sworn to before me, this

day of January 1879
A J. Stewart
Notary Public

INDEX.

Referring the lines to the pages of the field notes.

Town. *2 South* Range *30 1/2 East* Willamette Meridian.

6	5	4	3	2 <i>18</i> 1
				<i>17</i> <i>16</i>
7	8	9	10	11 <i>15</i> 12
				<i>14</i> <i>13</i>
18	17	16	15	14 <i>12</i> 13
				<i>11</i> <i>10</i>
19	20	21	22	23 <i>9</i> 24 <i>19</i>
				<i>8</i> <i>7</i>
30	20	28	27	26 <i>6</i> 25
				<i>5</i> <i>4</i>
31	32	33	34	35 <i>2</i> 36

5
540

Subdivisions of Township No. 2 South Range 30 1/2
East Willamette Meridian, Oregon.

West on a random line
between Sections 26 and 35—
Va 20° 45' East

11.60 Intersected west Boundary
22 lbs North of stone cor
to Fractional Sections
26 and 35 from which
corner. I run

N 88° 54' East on a true line
between Sec. 26 and 35—

Va. 22° 50' East

11.60 The corner to Sections 25—
26. 35 and 36

Land: Surface west slope
of hill. Soil 2nd rate
good grass.

North between Sections 25 and 26

Bear. 20° 45' East

40.00 Set Stone 17 x 14 x 4 on N. W. - 50

slope of hill for 1/4 Sec. cor.

65.00 George H Piper's house bears

N. 83° W. 3.50 chains dist

66.00 Fence & field bears. E and W.

80.00 Set Pine post 4 in. square and - 50

4 ft. long in plowed field
for corner to sections

23, 24, 25, and 26, I did

not dig pits or raise mound
as they would be entirely
useless

Land. Surface undulating
Soil. 2nd and 1st rate. good
grap. good for farming
purposes

542 Subdivisions of Township No. 2 South Range 30 1/2
East Willamette Meridian, Oregon.

East on a random line be-
tween Sections 24 and 25

Pa. 21° 30' East

40.00 Set post for temporary 1/4 Sec. cor.

79.82 Intersected East boundary
82 lbs South of Stone corner
to Sections 24 and 25 from
which corner I run

S 89° 25' West on a true line
between Sections 24 and 25

Pa. 19° 15' East

32.50 Ravine opens North - 60

39.96 Set Stone 15 x 8 x 5 on N. E
Slope for 1/4 Sec. cor.

55.00 On table land + 60

60.00 Fence & field course N. T. S.

79.82 The corner to Sections 23, 24, 25
and 26

Land: Surface undulating,
Soil 1st and 2nd rate; good
grap: good for farming

December 11, 1879

West on a random line between
 Sections 23 and 26

Pa. 21° 30' East

11.68 Intersected West Boundary
 20 lbs North of stone corner
 to Sections 23 and 26
 from which corner I run
 N. 89° 00 East on a true line
 between Sections 23 and 26

Pa. 20° 04' East

5.50 Road & fence course N. & S.
 11.68 The corner to Sections 23,
 24, 25, and 26

Land: Surface rolling
 soil 1st and 2nd rate
 good gras. well adapted
 to farming.

December 26th 1878

West on a random line be
tween Sections 14 and 23
Pa. 20° East

11.70 Intersected West Boundary 18 chs
North of stone corner to Sec.
14 & 23 from which cor. I run
N. 89° 06' East on a true line
between Sections 14 and 23
Pa. 21° 20' East

11.70 The corner to Sec. 13. 14. 23 and
24

Sand: Surface rolling.
Soil 2^d rate good for
good for grazing

Subdivisions of Township No. 2 South Range 30 1/2
East Willamette Meridian, Oregon.

North between Sec. 13 and 14
Poa. 20° East-

10.00 On plateau + 50

40.00 Set Stone 12x10x7 on
level for 1/4 Sec. cor.

80.00 Set Stone 15x10x7 on north-50
slope in mound of stone
and drove stake in pit
for cor to sections 11, 12
13, and 14

Land: Surface undulating;
Soil 2nd rate; good
grass;

548 Subdivisions of Township No. 2 South Range 30 1/2
East Willamette Meridian, Oregon.

East on a random line between Sec. 12 and 13

Pa. $20^{\circ} 15'$ East

- 40.00 Set post for temporary $\frac{1}{4}$ Sec cor.
79.10 Intersected East Boundary 88 lbs
South of post corner to sections
12 and 13 from which cor. I run
 $S. 89^{\circ} 22'$ West on a true line
between sections 12 and 13

Pa $19^{\circ} 45'$ East

- 39.55 Set Stone $15 \times 10 \times 7$ in mound
of stone, on level for $\frac{1}{4}$ Sec. cor
79.10 The corner to sections 11, 12,
13 and 14

Land: Surface nearly level,
Soil, 1st and 2nd rate; good
grafs. good for farming
Most of Sec. 13 is good
wheat land

Subdivisions of Township No. 2 South Range 30 1/2 549
 East Willamette Meridian, Oregon.

7 West on a random line
 between Sec. 11 and 14
 Pa. $20^{\circ} 15'$ East.

11.56 Intersected West Boundary
 24 lks North of Stone corner
 to Sections 11 and 14 from
 which corner I run
 $N. 88^{\circ} 48'$ East on a true line
 between sections 11 and 14
 Pa. $21^{\circ} E$

11.56 The corner to sections
 11, 12, 13 and 14

Land surface nearly
 level; soil 2nd rate; good
 grass; good for grazing

December 27th 1878

17

552 Subdivisions of Township No. 2 South Range 30 1/2
East Willamette Meridian, Oregon.

West on a random line
between sections 2 & 11

Pa. 20° 30' East

11.48 Intersected West Boundary
24 lbs north of Stone corner
to sections 2 and 11 from
which corner I run
N 88° 48' East on a true line
between sections 2 and 11

Pa. 22° 10' East

11.48 The corner to sections
1. 2. 11 and 12

Land: Surface nearly
level; Soil 2nd rate;
good grass; good for
grazing

FINAL AFFIDAVIT OF ASSISTANTS.

We hereby certify that we assisted George
S. Pershin Deputy Surveyor, in surveying
the Subdivision lines of Township 2 South
Range 30 1/2 East Willamette Meridian, Oregon,
and that said lines have been in all respects, to the best of our knowledge and
belief, well and faithfully surveyed, and the boundary monuments planted ac-
cording to the instructions furnished by the Surveyor General; and we do
further swear that we each of us performed the work assigned us, faithfully to
the best of our ability, in the capacity hereby indicated by our signatures.

George H. Piser Chainman.

John Macdonald Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

STATE OF OREGON,
County of Umatilla }

Subscribed and sworn to before me, this seventh
day of January 1879

A. J. Sturtevant
Notary Public

I George S. Pershin

Deputy Surveyor, do solemnly swear that in pursuance of a contract with James C. Tolman U. S. Surveyor General of the State of Oregon, bearing date the 7th day of December 1878, and in strict conformity with the Printed Manual of Instructions, and the instructions given me by the Surveyor General, I have faithfully surveyed the Subdivision lines of Township 2 South Range 30 1/2 East aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

George S. Pershin

Deputy Surveyor.

STATE OF OREGON,

County of Multnomah

Subscribed and sworn to before me, a Notary Public in and for the said County and State, this 15th day of January 1879

E. W. Cornell
Notary Public in
for the State of Oregon

576

Office U. S. Surveyor General,

Portland, Oregon, *January 25, 1879*

The foregoing Field Notes of the survey of

Subdivisional lines of T. S. R. 30 1/2 E. 11th N.
executed by *George S. Pershin U. S. Dept. So.*
..... *under his contract No. 313*

Dated *Dec. 7* 1878, having been critically examined, the necessary corrections and explanations made, the said field notes and the survey they describe, are hereby approved.

..... *James C. Tolman*
Surveyor General.