



# INDEX DIAGRAM

Township 3 South, Range 33½ East 2 2 1

6	5	4	3	2	<u>3</u> 1
				<u>4</u>	<u>3</u>
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

## T. 3 S., R. 33½ E., Willamette Meridian, Oregon

## CHAINS

The following field notes describe the remonumentation of certain original corner points, township 3 south, range 33½ east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350 Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

East Boundary, T. 3 S., R. 33½ E.,  
Willamette Meridian, Oregon

(Remonumenting a corner established by Rufus S. Moore,  
U. S. Deputy Surveyor, in 1882,  
and remonumented by L. E. Wilkes,  
U. S. Surveyor, in 1917)

The cor. of Tps. 2 and 3 S., Rs. 33, 33½, and 34 E.,  
monumented with the original sandstone, 28 x 9 x 4 ins.,  
firmly set 24 ins. in the ground, mkd. with 6 notches on  
N., S., E., and W. edges, from which the remains of the  
original bearing trees:

A grand fir, 24 ins. diam., bears N. 60° E., 44  
lks. dist., with scribe marks R34E visible  
on partially healed blaze.

A grand fir, 37 ins. diam., bears S. 17° E., 40  
lks. dist., with fragmentary scribe marks  
visible on partially healed blaze.

A larch snag, 20 ins. diam., bears S. 42° W., 11  
lks. dist., with scribe marks T3S R33½E S31  
visible on open blaze.

A decayed pine stump, size indeterminate, bears  
N. 25° W., 36 lks. dist., with a down pine  
alongside, 12 ins. diam., with scribe marks  
T2S R33½E S36 BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins.  
in the ground, with brass cap mkd.

T 2 S
R 33 E   R 34 E
S 36   S 31
S 1   S 6
R 33½ E   R 34 E
T 3 S
1977

from which new bearing trees

A fir, 11 ins. diam., bears S. 56° W., 52 lks.  
dist., mkd. T3S R33½E S1 BT.

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

## CHAINS

A fir, 19 ins. diam., bears N. 75° W., 31½ lks.  
dist., mkd. T2S R33E S36 BT.

Deposit corner stone alongside iron post.

North Boundary, T. 3 S., R. 33½ E.,  
Willamette Meridian, Oregon

(Remonumenting a corner established by Rufus S. Moore,  
U. S. Deputy Surveyor, in 1882)

The ¼ sec. cor. of secs. 1 and 36, on the N. bdy. of the  
Tp., monumented with the original unmarked basalt stone,  
16 x 16 x 3 ins., loosely set in a mound of stone, 2 ft.  
base, 1 ft. high, from which the only remaining original  
bearing tree:

A pine, 25 ins. diam., bears S. 41° E., 202 lks.  
dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.  
in the ground, with brass cap mkd.

T 2 S R 33 E

¼ S 36  
S 1

T 3 S R 33½ E  
1977

from which a new bearing tree

A pine, 12 ins. diam., bears N. 50° E., 43 lks.  
dist., mkd. ¼ S36 BT.

Deposit corner stone alongside iron post.

(Remonumenting a corner established by Rufus S. Moore,  
U. S. Deputy Surveyor, in 1882,  
and redescribed by John C. Arnold,  
U. S. Deputy Surveyor, in 1891)

The cor. of secs. 1, 2, 35, and 36, monumented with the  
original basalt stone, 16 x 10 x 10 ins., firmly set 10  
ins. in the ground, mkd. with 1 notch on E. and 2 notches  
on W. edges, from which the remains of the original  
bearing trees:

A pine snag, 11 ins. diam., bears S. 56° W., 36  
lks. dist., with scribe marks T3S R33½E S2 BT  
visible on open blaze. (Record, S. 50° W.)

A pine snag, 24 ins. diam., bears N. 48° W., 37  
lks. dist., with scribe marks R33½E S35 visible  
on open and burned blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.  
in the ground, with brass cap mkd.



CERTIFICATE OF SURVEY

(I) (~~W~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~W~~) have remonumented certain original corner points, township 3 south, range 33½ east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~us~~) and under (my) (~~our~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 33½ east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 17 1978 (Date) Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626