

4-679

433

B

FIELD NOTES

of

RETRACEMENT PORTION EAST BOUNDARY,

RETRACEMENT AND RESURVEY PORTION SOUTH BOUNDARY,

RETRACEMENT PORTION WEST BOUNDARY

and

RETRACEMENT AND SURVEY PORTION SUBDIVISIONAL LINES

in

TOWNSHIP NO. 2 SOUTH, RANGE NO. 34 EAST

Of the

Willamette

Meridian,

In the State of

Oregon

EXECUTED BY

L. E. Wilkes

In the capacity of U. S. Surveyor, under Special Instructions dated April 18, 1917
issued by the United States Surveyor General to govern surveys included in Group
No. 38, which were approved by the Commissioner of the General Land
Office, May 10, 1917, and Assignment Instructions dated Sept. 13, 1917

Survey commenced October 10, 1917

Survey completed October 18, 1917

6-151

ACCEPTED BY THE HON. COMMISSIONER G. L. O. May 2. 1919

404


FIELD NOTES

TO THE SURVEYOR OF THE LANDS.

RECORDING THE SURVEYS.

INDEX DIAGRAM.

Township 2 South, Range 34 East



Township No. 2 South, Range No. 34 East

DATE DIAGRAM

Report of the Geological Survey of India
on Retracements, Resurveys and Surveys for Year 1917

6	7	8	9	10	11	12
18	17	16	15	14	13	
19	20	21	22	23	24	Oct. 10.
30	29	28	27	26	25	Oct. 10.
Oct. 16	Oct. 18	Oct. 18	Oct. 17	Oct. 17	Oct. 12	Oct. 11
South ³¹ Boundary ³² Umatilla ³³ Indian ³⁴ Reservation ³⁵						
Oct. 16	Oct. 18	Oct. 18	Oct. 17	Oct. 17	Oct. 12	Oct. 11

East Boundary Umatilla Indian Reservation

436

Township No. 2 South, Range No. 34 East

Chains

This survey was made simultaneously and in connection with the survey that portion of this township within the original boundaries of the Umatilla Indian Reservation. Survey commenced Oct. 10, 1917 and executed with a Young and Sons light mountain transit No. 8585, with Smith solar attachment. The horizontal limb is provided with two double verniers placed opposite to each other, reading to single minutes of arc, which is also the least count of the verniers of the latitude and declination arcs. The instrument was examined and approved by the Assistant Supervisor of Surveys for Oregon, May 3, 1917, subject to a satisfactory field test.

I examine the adjustments of the transit and find them correct; then, to test the solar apparatus by comparing its indications resulting from solar observations made during a.m. and p.m. hours with a meridian determined by observations on Polaris, I proceed as follows:

Sept. 5, 1917: At my camp near the $\frac{1}{4}$ cor. of secs. 13 and 14, lat. $45^{\circ}24'N.$, long. $118^{\circ}29'W.$, at 8h 37m p.m., l.m.t., I observe Polaris at eastern elongation in accordance with the Manual of Instructions and mark a point in the line thus determined on a peg driven in the ground, 5.00 chs. N. of my station.

Sept. 5, 1917.

Sept. 6, 1917: At 7h 0m a.m., I lay off the azimuth of Polaris $1^{\circ}37'$ to the west and mark the meridian thus determined on a peg driven in the ground, 5.00 chs. N. of my station.

Sept. 6, 1917.

Oct. 9, 1917: At 4h 0m p.m., l.m.t., I set off $45^{\circ}24'N.$ on the lat. arc; $6^{\circ}17'S.$ on the decl. arc; and determine with the solar a meridian, which falls $0^{\circ}0'30''$ west of the meridian determined by Polaris observation, Sept. 5,

Township No. 2 South, Range No. 34 East

Chains

1917.

Chains

Oct. 9, 1917.

Oct. 10, 1917: At 8h 0m a.m., l.m.t., I set off $45^{\circ}24'N.$ on the lat. arc; $6^{\circ}33'S.$ on the decl. arc; and determine with the solar a meridian, which falls $0^{\circ}0'20''$ west of the meridian determined by Polaris observation, Sept. 5, 1917.

The solar apparatus by p.m. and a.m. observations defines positions for the meridian, which vary less than $1'$ of arc from the meridian determined by Polaris observation; therefore, I conclude that the adjustments of the instrument are satisfactory.

The instrument was maintained in good adjustment throughout the survey. Latitude and meridian observations were taken daily, weather permitting. Measurements were made with a 5.00 ch. steel tape, compared with a Chesterman standard 66 ft. steel tape and found correct. All measurements were made on the slope; angles read with an Abney clinometer and all distances reduced to the horizontal, which alone appears in these notes.

Note: Several cor. herein are monumented by stones because more iron posts were required than had been anticipated, and to procure another shipment would have involved the loss of much time and materially increased the cost.

Retracement Portion East. Bdy., T. 2 S., R. 34 E.

Commence at the cor. of secs. 13, 18, 19 and 24, on the E. bdy. of the Tp., which is a cross (X) on a volcanic stone in place, 5x3x1 ft. above ground, witnessed as described by the surveyor general.

From this cor. the closing cor. of secs. 13 and 18, on the E. bdy. of the original Umatilla Indian Reservation, bears N. $0^{\circ}11'E.$, 17.08 chs. dist.

Thence

South, retracing bet. secs. 19 and 24.

Over rolling land, through heavy timber and medium under-

Retracement Portion East Bdy., T. 2 S., R. 34 E. 441

- Chains Timber, fir, pine and tamarack.
- Undergrowth, pine, willow, service berry and ninebark.
- South, retracing line bet. secs. 31 and 36.
- Over mountainous land, through heavy timber and medium undergrowth.
- 40.24 Intersect the point for $\frac{1}{4}$ sec. cor., located by reference to the bearing trees as described by the surveyor general, except that the SE. tree is now dead. I perpetuate this cor., as follows: at the exact cor. point
- Set a volcanic stone, 20x12x10 ins., 16 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ 36 on W. and 31 on E. face; from which
- A tamarack, 16 ins. diam., bears N. $66^{\circ}45'W.$, 67 lks. dist., marked $\frac{1}{4}$ S B T (Old B.T.)
- A tamarack, 6 ins. diam., bears S. $50^{\circ}E.$, 20 lks. dist., marked $\frac{1}{4}$ S 31 B T (New B.T.)
- The true course and distance of this line to the $\frac{1}{4}$ sec. cor. is South, 40.24 chs.
- From the $\frac{1}{4}$ sec. cor.
- South, continuing my measurements
- 60.74 Daly wagon road, bears NE. and SW.; this road follows the approximate summit of the Blue Mountains, which at this point is flat and not well defined.
- 80.47 Intersect the cor. of Tps. 2 and 3 S., Rs. 34 and 35 E., which is an old post, marked and witnessed as described by the surveyor general. I perpetuate this cor., as follows: at the exact cor. point
- Set a volcanic stone, 28x20x12 ins., 12 ins. in the ground to bedrock and 9 ins. in a mound of stone, for cor. of Tps. 2 and 3 S., Rs. 34 and 35 E., marked with 6 notches on each edge; from which
- A fir, 16 ins. diam., bears N. $72^{\circ}15'E.$, 72 lks. dist., marked T 2 S R 35 E S 31 B T (Old B.T.)
- A fir, 18 ins. diam., bears S. $42^{\circ}30'E.$, 50 lks. dist.,

442

Retracement Portion East Bdy., T. 2 S., R. 34 E.

Chains

marked T 3 S R 35 E S 6 B T (Old B.T.)

A fir, 20 ins. diam., bears S. $14^{\circ}30'W.$, 56 lks. dist.,

marked T 3 S R 34 E S 1 B T (Old B.T.)

A fir, 24 ins. diam., bears N. $50^{\circ}W.$, 300 lks. dist.,

marked T 2 S R 34 E S 36 B T (New B.T.)

At this cor. the lat. is $45^{\circ}21'N.$, long, $118^{\circ}28'W.$, mag.

decl. $19^{\circ}30'E.$

The true course and distance of this line from the $\frac{1}{4}$ sec.

cor. is South, 40.23 chs.

Land, rolling bench.

Soil, light shallow loam on basalt rock, 3rd rate.

Timber, fir, pine and balsam.

Undergrowth, balsam, fir and willow.

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

From the cor. of Tps. 2 and 3 S., Rs. 34 and 35 E.

West, retracing bet. secs. 1 and 36.

Over high rolling bench land, through heavy timber and medium undergrowth.

40.08 Fall 20 lks. N. of the $\frac{1}{4}$ sec. cor., which is a basalt stone, firmly set, marked and witnessed as described by the surveyor general.

The true course and distance of this line to the $\frac{1}{4}$ sec.

cor. is S. $89^{\circ}43'W.$, 40.08 chs.

From the $\frac{1}{4}$ sec. cor.

West, continuing my measurements

80.09 Fall 50 lks. N. of the cor. of secs. 1, 2, 35 and 36, which is a stake, firmly set in the ground, not marked, but witnessed as described by the surveyor general. I per-
petuate this cor., as follows: at the exact cor. point Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for cor. of secs. 1, 2, 35 and 36, with brass cap marked

T2S	R34E
S35	S36
S2	S1
T3S	R34E

1917

443

Retracement and Resurvey Portion South Bdy., T.2 S., R.34 E.

Chains

from which

A pine, 28 ins. diam., bears N. 31° E., 38 lks. dist.,
marked T 2 S R 34 E S 36 B T (Old B.T.)

A pine, 20 ins. diam., bears S. 79° E., 38 lks. dist.,
marked T 3 S R 34 E S 1 B T (Old B.T.)

A pine, 16 ins. diam., bears S. $78^{\circ}30'W.$, 27 lks. dist.,
marked T 3 S R 34 E S 2 B T (Old B.T.)

A pine, 30 ins. diam., bears N. $80^{\circ}W.$, 190 lks. dist.,
marked T 2 S R 34 E S 35 B T (Old B.T.)

The true course and distance of this line from the $\frac{1}{4}$ sec. cor. is S. $89^{\circ}17'W.$, 40.01 chs.

Land, high bench.

Soil, light shallow loam on basalt rock, 3rd rate.

Timber, pine and fir.

Undergrowth, balsam, willow and pine.

Retracement

From the cor. of secs. 3, 4, 33 and 34, West retracing bet. secs. 4 and 33; at 39.30 chs. pass 20 lks. N. of the $\frac{1}{4}$ sec. cor., and at 79.24 chs. fall 129 lks. N. of the cor. of secs. 4, 5, 32 and 33.

From the cor. of secs. 4, 5, 32 and 33, West retracing bet. secs. 5 and 32; at 39.54 chs. pass 20 lks. N. of the $\frac{1}{4}$ sec. cor., and at 79.04 chs. fall 98 lks. N. of the cor. of secs. 5, 6, 31 and 32.

From the cor. of secs. 5, 6, 31 and 32, West retracing bet. secs. 6 and 31; at 40.10 chs. pass 5 lks. N. of the $\frac{1}{4}$ sec. cor., and at 83.16 chs. fall 2 lks. N. of the cor. of Tps. 2 and 3 S., Rs. $33\frac{1}{2}$ and 34 E.

The point for cor. of Tps. 2 and 3 S., Rs. $33\frac{1}{2}$ and 34 E. is located by reference to the bearing trees as described by the surveyor general. I perpetuate this cor., as follows:
at the exact cor. point

Set a sandstone, 28x9x4 ins., 21 ins. in the ground, for cor. of Tps. 2 and 3 S., Rs. $33\frac{1}{2}$ and 34 E., marked with 6 notches on each edge; from which

A fir, 8 ins. diam., bears N. $60^{\circ}E.$, 44 lks. dist.,
marked T 2 S R 34 E S 31 B T (Old B.T.)

A fir, 16 ins. diam., bears S. $17^{\circ}E.$, 40 lks. dist.,

444

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

Chains

marked T 3 S R 34 E S 6 B T (New B.T.)

A tamarack, 28 ins. diam., bears S.42°W., 11 lks. dist.,

marked T 3 S R 33½ E S 1 B T (Old B.T.)

A lodgepole pine, 10 ins. diam., bears N.25°W., 36 lks.

dist., marked T 2 S R 33½ E S 36 B T (Old B.T.)

Thence S.89°57'E., resurveying S. bdy. of sec. 31.

Over heavily rolling bench land, through heavy timber and dense undergrowth.

Descend 100 ft. to

16.50 Brook, 2 lks. wide, course SE.; ascend 140 ft. on SW. slope to

30.00 Top of ascent, bears NW. and SE.; over rolling land.

41.46 Set a basalt stone, 14x10x10 ins., 11 ins. in the ground, for $\frac{1}{4}$ cor. of sec. 31 only, marked $\frac{1}{4}$ 31 on N. face; from which

A pine, 24 ins. diam., bears N.13°W., 27 lks. dist., marked $\frac{1}{4}$ S 31 B T.

43.06 Intersect the point for the old $\frac{1}{4}$ sec. cor., located by reference to the bearing trees as described by the surveyor general, except that the SE. bearing tree is now dead and fallen. I change this cor. to refer to sec. 6,

T. 3 S., R. 34 E. only and perpetuate it as follows: at the exact cor. point 31.00 on bearing line.

Set a basalt stone, 24x10x4 ins., 18 ins. in the ground,

for $\frac{1}{4}$ cor. of sec. 6, T. 3 S., R. 34 E. only, marked $\frac{1}{4}$ 6 on S. face; from which

A pine, 6 ins. diam., bears South, 31 lks. dist., marked $\frac{1}{4}$ S 6 B T (New B.T.)

Thence

N.89°56'E., continuing my measurements

81.46 Set a sandstone, 20x14x6 ins., 15 ins. in the ground, for cor. of secs. 31 and 32, marked 32 on NE. and 31 on NW. face, with 5 notches on E. and 1 notch on W. edge; from which

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

Chains

A pine, 20 ins. diam., bears N. $12^{\circ}30'W.$, 78 lks. dist.,
marked T 2 S R 34 E S 31 B T.

A pine, 10 ins. diam., bears N. $70^{\circ}E.$, 43 lks. dist.,
marked T 2 S R 34 E S 32 B T.

Land, high rolling bench.

Soil, light shallow loam, 2nd rate.

Timber, balsam, lodgepole pine and fir.

Undergrowth, balsam, lodgepole pine and willow.

N. $89^{\circ}56'E.$, resurveying S. bdy. of sec. 32.

Over high rolling bench.

1.70 Intersect the point for cor. of secs. 5, 6, 31 and 32,
located by reference to the bearing trees as described
by the surveyor general, except that the SE. bearing
tree is now dead. I change this cor. to refer to secs.
5 and 6 only and perpetuate it as follows: at the exact
cor. point

Set a basalt stone, 18x12x6 ins., 12 ins. in the ground,
for cor. of secs. 5 and 6, T. 3 S., R. 34 E. only, marked
with a cross (X) on top, with 5 notches on E. and 1 notch
on W. edge; from which

A forked pine, 24 ins. diam., bears S. $88^{\circ}E.$, 4 lks.
dist., marked T 3 S R 34 E S 5 B T (New B.T.)

A pine, 14 ins. diam., bears S. $39^{\circ}W.$, 40 lks. dist.,
marked T 3 S R 34 E S 6 B T (Old B.T.)

Thence

N. $88^{\circ}52'E.$, continuing my measurements

Over high rolling bench land, through heavy timber and
medium undergrowth.

17.00 Leave bench land, bears NE. and SW.; descend SE. slope,
325 ft. to

40.00 Set a basalt stone, 28x18x12 ins., 21 ins. in the ground,
for $\frac{1}{4}$ cor. of sec. 32 only, marked $\frac{1}{4}$ 32 on N. face; from
which

A pine, 14 ins. diam., bears N. $66^{\circ}W.$, 141 lks. dist.,

446

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

Chains

marked $\frac{1}{4}$ S 32 B T.

- 41.21 Intersect the point for old $\frac{1}{4}$ sec. cor., located by reference to the bearing trees as described by the surveyor general.

I change this cor. to refer to sec. 5, T. 3 S., R. 34 E. only and perpetuate it as follows: at the exact cor. point Set a basalt stone, 24x14x10 ins., 18 ins. in the ground, for $\frac{1}{4}$ cor. of sec. 5, T. 3 S., R. 34 E. only, marked $\frac{1}{4}$ 5 on S. face; from which

A pine, 36 ins. diam., bears S. $58^{\circ}E.$, 12 lks. dist., marked $\frac{1}{4}$ S 5 B T (Old B.T.)

Thence

N. $89^{\circ}43'E.$, continuing my measurements

Descend 60 ft. to

- 43.90 Dry creek bed, course N. $30^{\circ}E.$; ascend 110 ft. to

- 51.00 Top of spur, slopes NW.; descend NE. slope, 130 ft. to

- 59.44 Dry gulch, course NW.; ascend NW. slope, 350 ft. to

- 80.00 Set a basalt stone, 18x12x12 ins., 12 ins. in the ground, for cor. of secs. 32 and 33, marked 33 on NE. and 32 on NW. face; with 4 notches on E. and 2 notches on W. edge; from which

A fir, 24 ins. diam., bears N. $50^{\circ}E.$, 26 lks. dist., marked T 2 S R 34 E S 33 B T.

A fir, 5 ins. diam., bears N. $39^{\circ}30'W.$, 13 lks. dist., marked T 2 S R 34 E S 32 B T.

Land, mountainous and rolling bench.

Soil, light shallow loam, 2nd rate.

Timber, pine, fir and tamarack.

Undergrowth, pine, fir, tamarack and honey laurel.

N. $89^{\circ}43'E.$, resurveying S. bdy. of sec. 33.

Over high rolling bench land, through heavy timber and medium undergrowth.

- 100.75 Intersect the old cor. of secs. 4, 5, 32 and 33, which is the remains of a tamarack, 14 ins. diam., now dead and fallen, witnessed as described by the surveyor general,

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

Chains

except that the SW. bearing tree is now dead. I change this cor. to refer to secs. 4 and 5 only and perpetuate it as follows: at the exact cor. point

Set a basalt stone, 18x8x5 ins., 12 ins. in the ground, for cor. of secs. 4 and 5, T. 3 S., R. 34 E. only, marked with 4 notches on the E. and 2 notches on W. edge; from which

A tamarack, 18 ins. diam., bears S. $70^{\circ}30' E.$, 81 lks.

dist., marked T 3 S R 34 E S 4 B T (Old B.T.)

A fir, 8 ins. diam., bears S. $42^{\circ}45' W.$, 24 lks. dist., marked T 3 S R 34 E S 5 B T (New B.T.)

Thence

N. $88^{\circ}26' E.$, continuing my measurements

20.00 Leave bench land; descend SE. slope, 175 ft. to

40.00 Set an iron post, 3 ft. long, 1 in. diam., 12 ins. in the ground and 14 ins. in a mound of stone, for $\frac{1}{4}$ cor. of sec. 33 only, with brass cap marked

$\frac{1}{4}$
S33

1917

from which

A pine, 30 ins. diam., bears N. $38^{\circ} E.$, 198 lks. dist., marked $\frac{1}{4}$ S 33 B T.

40.70 Intersect the old $\frac{1}{4}$ sec. cor., which is a basalt stone, 18x10x6 ins., lying loose on the ground, dimly marked $\frac{1}{4}$ on top. I change this cor. to refer to sec. 4 only and perpetuate it as follows: at the exact cor. point

Reset the basalt stone, 18x10x6 ins., 12 ins. in the ground, for $\frac{1}{4}$ cor. of sec. 4, T. 3 S., R. 34 E. only, marked $\frac{1}{4}$ on S. face; from which

A pine, 18 ins. diam., bears S. $41^{\circ}45' W.$, 80 lks. dist., marked $\frac{1}{4}$ S 4 B T (Old B.T.)

Thence

N. $89^{\circ}43' E.$, continuing my measurements

Descend 355 ft. to

60.40 Dry gulch, course N.; ascend 40 ft. to

448

Retracement and Resurvey Portion South Bdy., T. 2 S., R. 34 E.

Chains Top of spur, slopes N.; descend 75 ft. to
62.25 Dry gulch, course NE.; ascend 50 ft. to
65.00 Top of spur, slopes N.; descend 112 ft. to
70.00 Intersect the old cor. of secs. 3, 4, 33 and 34, which is
80.00 a basalt stone, 8x8x7 ins. above ground, firmly set, marked
and witnessed as described by the surveyor general,
with the exception that the SW. bearing tree is now dead.
I mark a new tree, as follows: from cor.

A tamarack, 8 ins. diam., bears S. $37^{\circ}30'W.$, 29 lks.

dist., marked T 3 S. R 34 E S 4 B. T.

Land, mountainous and rolling bench.

Soil, light shallow loam, 2nd rate.

Timber, pine and fir.

Undergrowth, balsam, pine and willow.

Retracement Portion West Bdy., T. 2 S., R. 34 E.

From the cor. of Tps. 2 and 3 S., Rs. $33\frac{1}{2}$ and 34 E., previously described

North, retracing bet. secs. 31 and 36.

Over high rolling land, through heavy timber and medium undergrowth.

17.00 Road, bears NE. and SW.

32.50 Intersect the closing cor. on the S. bdy. of the original Umatilla Indian Reservation, which is an iron post, 2 ins. diam., 12 ins. above ground, marked and witnessed as described by the surveyor general.

The true course and distance of this line to the closing cor. is North, 32.50 chs.

Land, mountainous.

Soil, light shallow loam, 2nd rate.

Timber, pine, fir and tamarack.

Undergrowth, pine, fir and tamarack.

452

Survey Portion Subdivisions, T. 2 S., R. 34 E.

Chains

Undergrowth, arrowwood, willow, pine and fir.

From the cor. of secs. 13, 18, 19 and 24, on the E. bdy.

of the Tp. over rolling land, through timber and undergrowth.

West, bet. secs. 13 and 24.

Over rolling land, through timber and undergrowth.

- 5.94 Intersect the E. bdy. of the original Umatilla Indian Reservation, at the closing cor. of that portion of secs. 13 and 24 within the original Umatilla Reservation, which is an iron post, firmly set, marked and witnessed as described by the surveyor general. I change the markings on the brass cap to read as follows:

T2S R34E
S13 S13
CC S24 S24 CC
1917

and mark new bearing trees as follows:

A fir, 12 ins. diam., bears N.77°E., 59 lks. dist., marked C C T 2 S R 34 E S 13 B T.

A pine, 20 ins. diam., bears S.59°30'W., 54 lks. dist., marked C C T 2 S R 34 E U I R B T.

Land, rolling.

Soil, light scant loam, 2nd rate.

Timber, pine and fir.

Undergrowth, fir, pine and serviceberry.

Commence at the cor. of secs. 2, 3, 34 and 35, on the S.

bdy. of the Tp., which is a volcanic stone, 12x8x12 ins. above ground, firmly set, marked with 2 notches on E. and 4 notches on W. edge; from which

A pine, 36 ins. diam., bears N.72°E., 142 lks. dist., marked T 2 S R 34 E S 35 B T.

A pine, 16 ins. diam., bears S.38°E., 161 lks. dist., marked T 3 S R 34 E S 2 B T.

A tamarack, 28 ins. diam., bears S.81°30'W., 85 lks. dist., marked T 3 S R 34 E S 3 B T.

A tamarack, 28 ins. diam., bears N.64°W., 100 lks.

SRP453

Survey Portion Subdivisions, T. 2 S., R. 34 E.

Chains

- dist., marked T 2 S R 34 E S 34 B T.
- Thence North, bet. secs. 34 and 35.
- Over rolling bench land, through heavy timber.
- 29.62 Intersect the S. bdy. of the original Umatilla Indian Reservation, N. $89^{\circ}49'W.$, 4.76 chs. from the $63\frac{1}{2}$ Mile Cor. At the point of intersection Set an iron post, 3 ft. long, 2 ins. diam., 12 ins. in the ground and 12 ins. in a mound of stone, for closing cor. of secs. 34 and 35, with brass cap marked
~~T 2 S R 34 E~~
U I R
~~S 34 | S 35~~
C C
1917
from which three native shrubs were taken.
A fir, 24 ins. diam., bears S. $9^{\circ}E.$, 38 lks. dist., marked C C T 2 S R 34 E S 35 B T.
A fir, 12 ins. diam., bears S. $70^{\circ}W.$, 72 lks. dist., marked C C T 2 S R 34 E S 34 B T.
From this cor. the old closing cor. of secs. 34 and 35 within the original Umatilla Indian Reservation, bears N. $89^{\circ}49'W.$, 50 lks. dist.
Land, rolling bench. Soil, light shallow loam on basalt rock, 2nd rate.
Timber, lodgepole pine, yellow pine, fir and tamarack.
Undergrowth, none.
- Bearings
- From the cor. of secs. 3, 4, 33 and 34, on the S. bdy. of the Tp., previously described North, bet. secs. 33 and 34.
- Over mountainous land, through heavy timber.
- Descend NE. slope, 50 ft. to
- 2.56 Jennings Creek, 50 lks. wide, course SE.; the creek is practically dry at the present time; ascend 350 ft. to
- 29.66 Intersect the S. bdy. of the original Umatilla Indian Reservation, N. $89^{\circ}27'W.$, 4.04 chs. from the $64\frac{1}{2}$ Mile Cor.

General Description, T.2 S., R.34 E.

This portion of the township lies on the summit of the Blue Mountains. The soil is light volcanic ash, very shallow over basalt and is good for grazing. It is nearly all timbered with scattering yellow pine, fir, tamarack and balsam, not of commercial value. The land is principally valuable for grazing. There are no settlers.

Oct. 18, 1917.

L. E. Wilkes.
U. S. Surveyor

For Final Certificate of U. S. Surveyor, see Book "C"

APPROVAL

Office of U. S. Surveyor General,
Portland, Oregon, August 26, 1918.

The foregoing field notes of the Retracement Portion East Bdy., Retracement and Resurvey Portion South Bdy., Retracement Portion West Bdy. and Retracement and Survey Portion Subdivisional Lines in Township No. 2 South, Range No. 34 East of the Willamette Meridian, Oregon, executed by L. E. Wilkes, U. S. Surveyor, under his special instructions dated April 18, 1917, having been critically examined, and the necessary corrections and explanations made, the said field notes, and the surveys they describe, are hereby approved.

Edwin deWolfe
U. S. Surveyor General