

ORIGINAL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD NOTES
OF THE
REMONUMENTATION
OF THE CORNER OF SECTIONS 26, 27, 34, AND 35,
TOWNSHIP 2 SOUTH, RANGE 34 EAST,
OF THE WILLAMETTE MERIDIAN,
IN THE STATE OF OREGON.

EXECUTED BY

Bryan S. Seibold, Cadastral Surveyor

Under Special Instructions dated February 22, 2002,
approved February 22, 2002, which provided for the
remonumentation included under Group No. 2000,
and Assignment Instructions dated May 20, 2004.

Survey commenced May 20, 2004

Survey completed May 20, 2004

INDEX DIAGRAM

TOWNSHIP 02 SOUTH

RANGE 34 EAST

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

T. 2 S., R. 34 E., Willamette Meridian, Oregon

FEET

The following field notes describe the remonumentation of the corner of sections 26, 27, 34, and 35, township 2 south, range 34 east, of the Willamette Meridian, Oregon, as provided for in the Special Instructions dated February 22, 2002, under Group 2000, Oregon.

The remonumentation was made at the request of the Bureau of Indian Affairs, Umatilla Agency.

The new bearing tree has a 2½ inch x ¼ inch magnetic nail (Mag-Nail) driven at the base on the right side-center.

The mean magnetic declination as taken from U.S. Geological Survey 7½ minute quadrangle map "BALLY MOUNTAIN, OREG.", dated 1967, and photorevised in 1984, is 19° East.

**Remonumentation of the Corner of Sections 26, 27, 34, and 35,
T. 2 S., R. 34 E., Willamette Meridian, Oregon**

(Rehabilitating a corner established by James P. Currin and James E. Nolan, U.S. Deputy Surveyors, in 1887, and remonumented by Richard L. Johnson, Cadastral Surveyor, in 1987-89)

The cor. of secs. 26, 27, 34, and 35, monumented with a magnet in a white plastic case, firmly set, 25 ins. in the ground, from which an original bearing tree

A larch, 32 ins. diam., bears N. 62° E., 51.4 ft. dist., no marks visible on an opened blaze. (Record, N. 60¾° E., 51.8 ft.)

and the remains of bearing trees mkd. by Johnson

A fir, 23 ins. diam., bears S. 26° E., 98.8 ft. dist., with fragmentary scribe marks visible on a partially healed blaze. (Record, 99.7 ft.)

A fir, 12 ins. diam., bears S. 45° W., 69.8 ft. dist., with a healed blaze. (Record, S. 42½° W., 70.3 ft.)

A roothole, bears N. 36½° W., 13.9 ft. dist., with an uprooted fir snag alongside, 12 ins. diam., with scribe marks T2S R34E S27 BT visible on an open blaze. (Record, N. 39½° W.)

Remonumentation of the Corner of Sections 26, 27, 34, and 35,
T. 2 S., R. 34 E., Willamette Meridian, Oregon

FEET

The stainless steel post set by Johnson was found laying on top of the ground in the area.

At the corner point

Reset the stainless steel post, 28 ins. long, 2½ ins. diam., 26 ins. in the ground, directly over the magnet, with brass cap mkd.

T 2	S R	34 E
S 27		S 26
S 34		S 35
2004		
1987		

from which a new bearing tree

A larch, 9 ins. diam., bears N. 53½° W., 32.8 ft. dist.,
mkd. T2S R34E S27 BT.

Corner is located 20 ft. North of a gravel road, 15 ft. wide, bears N. 55° W. and S. 55° E.

CERTIFICATE OF SURVEY

I, Bryan S. Seibold, Cadastral Surveyor, HEREBY CERTIFY upon honor, that in pursuance of special instructions bearing date of the 22nd day of February, 2002, I have remonumented the corner of sections 26, 27, 34, and 35, township 2 south, range 34 east, of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by me and under my direction. Said remonumentation has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

OCTOBER 17, 2004
(Date)

Bryan S. Seibold
(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
Portland, Oregon

The foregoing field notes of the remonumentation of the corner of sections 26, 27, 34, and 35, township 2 south, range 34 east, Willamette Meridian, Oregon, executed by Bryan S. Seibold, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

October 19, 2004
(Date)

Mary J. M. Hartel
(Chief Cadastral Surveyor of Oregon)