

FIELD NOTES

Of the survey of the Subdivisional
 Lines of Township 2 South Range
34 East Willamette Meridian, Oregon,
 as surveyed by Jas. P. Currier & Jas. E. Roland
 U. S. Deputy Surveyor, under his Contract No. _____
 dated May 4th, 1887.

Survey commenced, July 16th, 1887
 Survey completed, July 21st, 1887

NAMES AND DUTIES OF ASSISTANTS.

L. F. Hooley, Compassman.
J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Belshaw, Chainman.
Guy Davis, Chainman.
B. B. Browner, Axman.
A. V. Veatch, Axman.
 _____, Flagman.

4 PRELIMINARY OATHS OF ASSISTANTS.

We, J. S. Medley, W. H. Medley, Frank Belshaw, Guy Davis

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the Subdivisional lines of T 2 S, Range 34 E Willamette Meridian, Oregon.

J. S. Medley, Chainman.
W. H. Medley, Chainman.
Frank Belshaw, Chainman.
Guy Davis, Chainman.

Subscribed and sworn to before me this 16th day of July, 1887

[SEAL.] James P. Plurrien, U.S. Deputy Surveyor

We, B. B. Crown, H. Beach, and do solemnly

swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Subdivisional lines of T 2 S, R 34 E, Willamette Meridian, Oregon.

B. B. Crown, Axman.
H. Beach, Axman.

Subscribed and sworn to before me this 16th day of July, 1887

[SEAL.] James P. Plurrien, U.S. Deputy Surveyor

INDEX

411

Referring the Lines to the Pages of the Field Notes.

T. 2 South R. 34 East Will. Mer.

6	65	5	43	4	28	3		2		1
64	65	62		41						
7	61	8	40	9	27	10		11		12
60		58		39	38					
18	57	17	38	16	25	15		14		13
55		54	37	37		24				
19	53	20	35	21	22	22	74	23		24
51	52	50	34	34		21	20	13		6
30	49	29	32	28	19	27	77	26	4	25
47	48	44		29	28	16		8		3
31	46	32	31	33	18	34	10	35		36

Meanders of _____, Pages _____ to _____

Meanders of _____, Pages _____ to _____

Subdivisions of T. 2 South R. 34 East.
Willamette Meridian, Oregon.

N. 45° E. 121 kcs. dist. marked

D. 2. S. R. 34. E. S. 3. 2. C. C. B. D.

A pine 8 ins. diam. bears. N 57° W.

77 kcs. dist. marked

D. 2. S. R. 34. E. S. 3. 1. C. C. B. D.

Land rolling Good timber. Pine
Samarack and fir.

Soil 3rd rate + Rocky.

West on true line bet. Secs. 30 + 31

va. 19° 15' East.

508 Wagon Road N.E.

40.00 Det. post 3 ft long + 3 ins square

24 ins in the ground for 1/4 sec.

Cor. marked 1/4 S. on N. face

from which A pine 6 ins.

diam. bears. N 43° W. 22 kcs.

dist. marked 1/4 S. B. D. and

A pine 8 ins. diam. bears. S.

13 kcs. dist. marked 1/4 S. B. D.

Subdivision of T. 2 South R. 34 East.
Willamette Meridian, Oregon.

(8093-10 M.)

42.20

Wagon Road N.W.

45.00

Creek 10 lks. wide N.E.

66.50

" " " S.E.

75.00

Wagon Road N.E. + S.W.

79.20

Intersect West bdy. 294 chs.

N. of cor. to Secs. 25 + 36 @ 2 S.

R. 33. E. and

Set a post 4 ft. long + 4 ins.

square 24 ins. in. The ground

for closing cor. to Secs. 30 + 31

marked C.C. @ 2 S. R. 34 E

on N.

S. 30. on N and

S. 31 on S. faces with

5 notches on N. and 1 on S. edges

from which a fir 20 ins.

diam. bears N. 30° W. 21 lks. dist.

marked C.C. B.D. and

A fir 36 ins. diam. bears S. 57° E.

42 lks. dist marked C.C. @ 2 S.

R. 34. E. S. 31. B.D.

Subdivisions of T. 2 South R. 34 East
Willamette Meridian, Oregon.

Land rolling. Pine and fir
timber Some grass. Soil 3rd rate

North bet. Secs. 29 + 30
Wa. $19^{\circ} 15'$ East.

- 20.22 Wagon Road N. E.
34.00 Enter timber E + W.
40.00 Set a post 3 ft. long + 3 ins.
square 24 ins. in the ground for
 $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. on N. face
from which a line 8 ins.
diam. bears N. 79° W. 19 lks dist.
marked $\frac{1}{4}$ S. B. D. and
a line 8 ins. diam. bears S. 30° E.
11 lks. dist. marked $\frac{1}{4}$ S. B. D.
40.75 Spring flows. W.
45.50 Wagon Road E + W.
47.00 Spring Branch 5 lks. wide E,
53.65 Road N. E.
65.25 Wagon Road E + W.

50

470

Subdivisions of T. 2 South R. 34 East.
Willamette Meridian, Oregon.

(8093-10 M.)

- 73.50 Birch Creek Road E & W.
- 74.15 Daly Wagon " on ridge E & W.
- 80.00 Set Stone 6x10x12 ins. 8 ins. in
the ground for cor. to secs.
19-20-29 & 30 marked with
5 notches on E. and 2 on S. edges
over which I raised a mound
of stone 2 ft. high with
4½ ft. base.
Land rolling Pine fir and
Tamarack timber and under-
brush with small openings
Soil 3rd Rate
- East On Random Bet. secs. 20 & 29
Pa. 19°30' East.
- 40.00 Set temp. ¼ Sec. cor.
- 79.35 Intersect N. & S line at cor. to secs.
20-21-28 & 29.
Thence N. on true line
- 2.80 Jennings Creek N. E.

Subdivisions of T. 2 South R. 34 East.
Willamette Meridian, Oregon.

7.50	Wagon Road N.E.		
39.67	Set Basalt Stone 6x12x18 ins. 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ on N. face Over which I raised a mound of Stone 18 ins. high with $3\frac{1}{2}$ ft. base.		
68.50	Ravine	S.	20
72.50	"	"	30
79.35	To Cor. to Secs. 19-20-29 & 30 Land rolling. Scattering pine timber. Soil Rocky & 3rd rate		
	West on line bet. Secs. 19 & 30 Pa. 20° East		
35.70	Wagon Road to Pilot Rock N.W.		
36.00	Gulch	S.W.	
38.00	"	"	
40.00	Set Basalt Stone 7x8x10 ins.		

52472

Subdivisions of T. 2 South R. 34 East.

Willamette Meridian, Oregon.

(8093-10 M.)

6 ins in the ground for $\frac{1}{4}$ Sec.
Cor. marked $\frac{1}{4}$ on N. face
Over which I raised a mound
of Stone 1.8 ins. high with $3\frac{1}{2}$ ft.
base.

44.75 Pilot Rock Wagon Road S. W.
Ascend hill

79.25 Intersect Township Line and
M. R. by 3.65 chs. N. of cor.
to Secs. 24 + 25 T. 2 S. R. 33 E.
Set a Stone 7x9x12 ins. 8 ins. in
the ground for closing cor. to
Secs. 19 + 30 marked M. R. C. C.
on E. face with 4 notches on the
N. and 2 on S. edges. Around
which I erected a mound of
Stone 2 ft. high with $4\frac{1}{2}$ ft. base.
Land rolling ^{and} broken
Pine & fir timber first $\frac{1}{2}$ mile
Soil Rocky and 3rd rate.

Subdivisions of T. 2 South R. 34 East.
Willamette Meridian, Oregon.

North on @rue Line Bet. Secs. 19 + 20

Na. $19^{\circ} 30'$ East.

13.00 Gulch E — 100

40.00 Set Stone $6 \times 10 \times 12$ ins. 8 ins. in
the ground for $\frac{1}{4}$ Sec. cor. marked
 $\frac{1}{4}$ on N. face. Around
which I raised a mound of
Stone 18 ins. high with $3\frac{1}{2}$ ft.
base.

51.60 Wagon Road E + W.

55.20 Gulch E — 30.

71.50 Road E + W.

80.00 Set. Post 4 ft. long 4 ins.
square 24 ins. in the ground for
cor. to Secs. 17-18-19 + 20 marked
D. 2. S. S. 17 on N. E.

R. 34. E. S. 20 on S. E.

S. 19. on S. W. and

S. 18. on N. W. faces with
5 notches on E and 3 on S. edges.
From which a line 10 ins.

Subdivisions of T. 2 South R. 34 East.

Willamette Meridian, Oregon.

(8093-10 M.)

diam. bears N. 45° E. 107 lks.

dist. marked. ^{R 34 E.} T. 2 S. 17. B. D.

A pine 24 ins. diam. bears S. 67° E.

64 lks. dist. marked T. 2 S.

R. 34. E. S. 20. B. D.

A pine 20 ins. diam. bears S. 40° W.

62 lks. dist. marked ^{T. 2 S. R 34 E.} S. 19. B. D.A pine 20 ins. diam. bears N. 45° W. 110 lks. dist. marked ^{T. 2 S. R 34 E.} S. 18.

B. D.

Land mostly open prairie.

Scattering pine timber.

Bunch grass. Soil 4th rate rocky

East on Random bet. Secs. 17 & 20

Cra. 20° East.

4000 Set temp. $\frac{1}{4}$ Sec. lev.

79.25 Intersect N. S. line at lev. to sec.

16-17-20 & 21. Thence West on true line. Cra. 18° 30' East.

Subdivisions of T. 2 South R. 34 East
Willamette Meridian, Oregon.

14.50 Head of canon N. E.
 29.50 " " " "
 39.62 Set post 3 ft. long & 3 ins. square
 24 ins. in. the ground for $\frac{1}{4}$ Sec. cor.
 marked $\frac{1}{4}$ S. on N face from which
 A fir 5 ins. diam bears N. 15 lks
 dist. marked $\frac{1}{4}$ S. B. D. and
 A fir 8 ins. diam. bears S. 40° W.
 19 lks. dist. marked $\frac{1}{4}$ S. B. D.

67.50 Enter timber N. E.

79.25 Do cor. to Secs. 17-18-19 & 20
 Land rolling. Soil 3rd rate
 Pine and fir timber in canon.

July 20, 1887

West on true line bet. Secs. 18 & 19
 Va. 20° East.

40.00 Set Stone 6x8x14 ins. 8 ins. in
 the ground for $\frac{1}{4}$ Sec. cor. marked
 $\frac{1}{4}$ on N. face around
 which I erected a mound of stone 18 ins.

Subdivisions of T. 2 South R. 34 East

Willamette Meridian, Oregon.

(8093-10 M.)

- high with $3\frac{1}{2}$ ft. base along side
 51.60 gulch 2.00 chs. South of Spring ^{George J.}
 65.10 Wagon Road N.W.
 79.20 Intersect- Township line and
 M.R. Bdy. 3.83 chs. N. of cor. to
 Secs. 13 + 24 T. 2 S. R. 33 E. and
 set a stone 12 x 14 x 16 ins. 10 ins. in
 the ground for closing cor.
 to Secs. 18 + 19. marked C. O. M. R.
 on N face with 3 notches on
 N. and S. edges. Around which
 I raised a mound of stone
 2 ft. high with $4\frac{1}{2}$ ft. base
 Land rolling and mostly
 prairie.
 Some bunch grass.
 Soil 3rd Rate

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Jas. P. Currier
and Jas. E. Noland, U. S. Deputy Surveyor, to assist in
 running, measuring, and marking the lines and corners described in the
 foregoing field notes of the survey of the Subdivisional
 lines of Township 2 South
R. 34. East Willamette Meridian, Oregon,
 showing the respective capacities in which they acted:

- L. J. Wooley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Brewer , Axman.
- H. Beach , Axman.
- , Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted Jas. P. Currier and
Jas. E. Noland, U. S. Deputy Surveyor, in surveying
 all those parts or portions of the Subdivisional
Lines of Township 2
South Range 34 East Willamette Meridian, Oregon,
 as represented in the foregoing field notes as having been surveyed by
 him and under his direction; and that said survey has been in all respects,
 to the best of our knowledge and belief, well and faithfully surveyed,
 and the corner monuments established, according to the instructions
 furnished by the U. S. Surveyor General of Oregon.

- L. J. Wooley , Compassman.
- J. S. Medley , Chainman.
- W. H. Medley , Chainman.
- Frank Belshaw , Chainman.
- Guy Davis , Chainman.
- B. B. Brewer , Axman.
- H. Beach , Axman.
- , Flagman.

Subscribed and sworn to before me this 21st day of
July, 1887.

[SEAL.]

James P. Currier
 U. S. Deputy Surveyor.

FINAL OATH OF DEPUTY SURVEYOR.

I, James P. Currier & James E. Toland, United States

Deputy Surveyor, do solemnly swear that in pursuance of instructions received from Douglas W. Taylor, U. S.

Surveyor General for Oregon, bearing date of the 13th

day of May, 1887, I have well, faithfully,

and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all

those parts or portions of Townships 2 S

Range 34 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an act of Congress approved August 8, 1846.

James P. Currier & James E. Toland
U. S. Deputy Surveyors.

Subscribed and sworn to before me this Fifteenth

day of February, 1888

A. L. Woodcock
Notary Public
for Oregon

500

Office of U. S. Surveyor General,

Portland, Oregon, June 28th, 1888

The ^{foregoing} following Field Notes of the Survey of the

Subdivisional lines of Township
2 South Range 34 East
Willamette Meridian Oregon

executed by Jas. P. Carrin and Jas. E. Noland
Special Joint U. S. Deputy Surveyors.
under his Contract No. _____, dated May

4th, 1887, having been critically examined,
the necessary corrections and explanations made, the
said Field Notes and the survey they describe, are
hereby approved.

Douglas W. Taylor -
Surveyor General.