

INDEX DIAGRAM

Township 2 South, Range 36 East,

	6	5 <u>13</u> <u>18</u> <u>13</u>	4 <u>11</u> <u>10</u>	3 <u>10</u>	2 <u>6</u>	1
	7	8 <u>17</u> <u>12</u>	9 <u>9</u> <u>9</u>	10	11	12
<u>4</u>	18 <u>17</u> <u>17</u> <u>16</u>	17 <u>16</u>	16 <u>8</u>	15	14	13
	19 <u>15</u> <u>15</u>	20 <u>12</u>	21	22 <u>7</u>	23 <u>6</u>	24
<u>4</u>	30 <u>14</u>	29 <u>11</u>	28 <u>8</u>	27 <u>7</u> <u>6</u>	26 <u>5</u>	25
<u>3</u>	31	32	33	34	35	36

3 2 2 1

Remonumentation of Certain Original Corner Points,
T. 2 S., R. 36 E., Willamette Meridian, Oregon

CHAINS

A fir, 8 ins. diam., bears S. 62° W., $35\frac{1}{2}$ lks. dist., mkd. T3S R36E S4 BT.

A fir, 10 ins. diam., bears N. $84\frac{1}{4}^{\circ}$ W., 29 lks. dist., mkd. T2S R36E S33 BT.

The cor. of secs. 4, 5, 32, and 33, on the S. bdy. of the Tp., determined at record distance from the remains of the original bearing trees:

A pine, 28 ins. diam., bears S. 42° E., 25 lks. dist., with scribe marks 3S R3 visible on partially healed blaze.

A pine, 24 ins. diam., bears S. 35° W., 86 lks. dist., with scribe marks 3S 36E S5 visible on partially healed blaze. (Record, S. 43° W.)

A root hole, bears N. 71° W., 12 lks. dist., with a down and decayed pine snag alongside, 18 ins. diam., no marks visible.

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 2 S R 36 E
S 32 S 33
S 5 S 4
T 3 S
1975

from which new bearing trees

A fir, 10 ins. diam., bears N. $54\frac{3}{4}^{\circ}$ E., 64 lks. dist., mkd. T2S R36E S33 BT.

A fir, 12 ins. diam., bears N. 8° W., 23 lks. dist., mkd. T2S R36E S32 BT.

West Boundary, T. 2 S., R. 36 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by John A. Hurlburt,
Deputy Surveyor, in 1874)

The cor. of secs. 25, 30, 31, and 36, on the W. bdy. of the Tp., monumented with a basalt stone, 18 x 12 x 8 ins. (record, 15 x 12 x 8 ins., unmarked), firmly set 8 ins. in a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, mkd. with 5 grooves on N. and 1 groove on S. face, from which the remains of the original bearing trees:

A root hole, bears N. 55° E., 60 lks. dist.

A root hole, bears N. 53° W., 57 lks. dist., with a down and decayed pine snag alongside, 20 ins. diam., with scribe mark 1 visible on decayed blaze.

At the corner point

Remonumentation of Certain Original Corner Points,
T. 2 S., R. 36 E., Willamette Meridian, Oregon

CHAINS

Set an iron post, 28 ins. long, 2½ ins. diam., 12 ins. in the ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 2 S
R 35 E R 36 E
S 25 | S 30
S 36 | S 31
1975

from which new bearing trees

A pine, 8 ins. diam., bears N. 72½° E., 31 lks. dist., mkd. T2S R36E S30 BT.

A pine, 10 ins. diam., bears S. 71½° E., 50 lks. dist., mkd. T2S R36E S31 BT.

A pine, 5 ins. diam., bears S. 55½° W., 109 lks. dist., mkd. X BT.

A pine, 18 ins. diam., bears N. 28½° W., 81½ lks. dist., mkd. T2S R35E S25 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 25 and 30, on the W. bdy. of the Tp., determined at record distance from the original bearing trees:

A fir, 24 ins. diam., bears S. 43° E., 12 lks. dist., with scribe marks ¼ S visible on partially healed blaze.

A pine, 24 ins. diam., bears N. 37° W., 31 lks. dist., with scribe marks ¼ S visible on opened blaze. (Record, N. 32° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 2 S
¼
R 35 E | R 36 E
S 25 | S 30
1975

The cor. of secs. 7, 12, 13, and 18, on the W. bdy. of the Tp., determined at record bearing and distance from the remains of the original bearing trees:

A pine, 40 ins. diam., bears N. 53° E., 20 lks. dist., with scribe marks R6 S visible on partially healed blaze.

A pine, 17 ins. diam., bears S. 7° E., 40 lks. dist., with illegible scribe marks visible on partially healed blaze.

A pine, 35 ins. diam., bears S. 43° W., 96 lks. dist., with scribe marks 2S R35E S13 visible on partially healed blaze. (Record, fir)

Remonumentation of Certain Original Corner Points,
T. 2 S., R. 36 E., Willamette Meridian, Oregon

CHAINS

A root hole, bears N. 30° W., 9 lks. dist., with
a down and decayed fir snag alongside, 18 ins.
diam., no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins.
in the ground, with brass cap mkd.

T 2 S	
R 35 E	R 36 E
S 12	S 7
S 13	S 18
1975	

from which a new bearing tree

A pine, 10 ins. diam., bears N. 65° W., 76 lks.
dist., mkd. T2S R35E S12 BT.

Subdivision, T. 2 S., R. 36 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by John A. Hurlburt,
Deputy Surveyor, in 1874)

The cor. of secs. 25, 26, 35, and 36, monumented with a
basalt stone, 15 x 12 x 9 ins., (record, 12 x 10 x 8 ins.,
unmarked) firmly set 8 ins. in the ground, mkd. with 1
groove on E. face, from which the remains of the original
bearing trees:

A root hole, bears N. 40° E., 49 lks. dist.

A root hole, bears S. 10° E., 49 lks. dist.

A fir, 27 ins. diam., bears S. 20° W., 42 lks.
dist., with scribe marks R36 S35 visible on
partially healed blaze.

A root hole, bears N. 65° W., 56 lks. dist.

and bearing trees of no record

A fir, 24 ins. diam., bears N. 57¾° E., 51½ lks.
dist., mkd. T2S R36E S25 BT.

A fir, 18 ins. diam., bears S. 36° E., 81 lks.
dist., mkd. T2S R36E S36 BT.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins.
in the ground, with brass cap mkd.

T 2 S R 36 E	
S 26	S 25
S 35	S 36
1975	

from which a new bearing tree

A fir, 6 ins. diam., bears N. 28¾° W., 19 lks.
dist., mkd. T2S R36E S26 BT.

CERTIFICATE OF SURVEY

(I) ~~KWA~~, A. Joseph Garrison, Cadastral Surveyor, HEREBY
 CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day
 of May, 19 57, (I) ~~KWA~~ have remonumented certain original corner
 points, township 2 south, range 36 east,

of the Willamette Meridian, in the State of Oregon, which
 are represented in the foregoing field notes as having been executed by (me), ~~(us)~~ and under (my)
~~(our)~~ direction; and that said survey has been made in strict conformity with said special instruc-
 tions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in
 specific manner described in the foregoing field notes.

 (Date) (Cadastral Surveyor)
 July 22, 1975
 (Date) *A. Joseph Garrison*
 (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points,
township 2 south, range 36 east, Willamette Meridian, Oregon,

executed by A. Joseph Garrison, Cadastral Surveyor,
having been critically examined and found correct, are hereby approved.

JUN 13 1977
 (Date) *Roger T. Barron*
 Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in
, is a true copy of the original field notes.

 (Date) (Chief, Division of Cadastral Survey) GPO 849-626