

Field Notes of the Subdivisions
of Township No 3 North of the base line
of Range No 27 East of the Willamette
Meridian, in the State of Oregon, by
Ebenezer E. Haft, deputy Surveyor,
under his contract No 93, bearing date
the 11th day of September 1860

Commenced the 12th day of October 1860
Completed " 27th " " October 1860

Index Diagram

6	5	4	3	2	1
30	30	22	14	11	6
7	8	9	10	11	12
29	28	21	16	10	5
18	17	16	15	14	13
27	27	20	15	9	4
19	20	21	22	23	24
26	25	19	14	8	3
30	29	28	27	26	25
24	24	18	13	7	1
31	32	33	34	35	36

(1) 147
Township 3 North Range 27 East

October 12th 1861

From the corner to Sec 1. 2. 3. 5. & 36
on South boundary of T. 3 N. R. 27 E. S. 2
North between Sec 3 5 & 36

7.00 The Trail up Butter Creek bearing S. S. W
ascend hill bearing N. E. & S. W

34.00 Top of the hill 150 ft high & descend

40.00 Set a post for gr sec corner in mound
with trench and pits and deposited
1 pins of charcoal, as per instructions

66.57 Enter rolling ground

67.00 Road from Dallas to Wallawalla bearing N. E.

80.00 Set a post for corner to Sec 25. 26. 35 & 36
in mound with trench and pits and de-
posited 1 pins of charcoal as per
instructions

Soil gray & red & white producing grass

Land hilly

Cast on a random line between Sec 25 & 36
var 19° 20' E

40.00 Set a post for temp gr sec corner

79.90 Intersect township line 21 links south
of the corner to Sec 25. 36. 30 & 31

152

(2)

Township 3 N. Range 27 East

Chains from which come I run

- S 89° 51' W on a true line between Secs 25 & 26
 22.40 Enter thick willow undergrowth
 35.00 Leave willow undergrowth, which bears N. N. E.
 36.60 Butter creek 20 lks wide bears N. N. E.
 39.95 Set a post for gr see corner in mound
 with trench and pits and deposited
 1 pint of charcoal as per instructions
 46.00 Road from the Dalles to Walla Walla
 being N. N. E. Leave bottom and ascend high ground
 79.90 The corner to sec's 35.36.25 & 26
 Soil on bottom 1st rate remainder 2nd rate
 Land principally level
 Frazer's preemption claim embraces the S. E. $\frac{1}{4}$ Sec 25
 North between Secs 25 & 26
 40.00 Set post for gr see corner in mound
 with trench and pits and deposited
 1 pint of charcoal as per instructions
 80.00 Set post for corner to Secs 23.24.25 & 26
 in mound with trench and pits and deposited
 1 pint of charcoal as per instructions
 Soil sandy, $\frac{1}{2}$ ra pits
 Sand rolling

Township 3-N Range 27 East

Chain, East end random line between Sec 25 & 24

Mar 19th 48th

40.00 Set a post for Temp gr sec corner in m

80.40 Intersect East boundary of Township

17 lks South of the corner to Sec 24, 25, 19 & 30

from which corner I run

S 89° 53' 34" E a true line between Sec 24 & 25

40.20 Set a post for gr sec corner in mound
with trench and pits and deposited

1 pint of Charcoal as per instructions

80.40 The corner to Sec 23, 24, 25 & 26

Soil sandy 3rd rate

Land rolling

North between Sec 23 & 24

40.00 Set post for gr sec corner in mound with
trench and pits and deposited 1 pint
of Charcoal as per instructions

80.00 Set post for corner to Sec 13, 14, 23 & 24

in mound with trench and pits, and
deposited 1 pint of Charcoal as per instructionsSoil sandy 3rd rate

Land rolling

154

(41)

Township 3 N. Range 27 East

Chains East on a random line between sec^s 13 & 24

Cor 19° 45' E

40.00

Set post for gr^{se} corner

79.85

Intersect East boundary of township

34 lks South of the corner to sec^s 13, 24, 18, 819

from which corner I run

S 89° 50' W on true line between sec^s 13 & 24

39.924

Set a post for gr^{se} corner in mound
with trench and pits and deposited 1 pint
of charcoal as per instructions

79.85

The corner to sec^s 13, 14, 23 & 24Soil 3rd rate producing grass

Land rolling and hilly

North between sec^s 13 & 14

40.00

Set post for gr^{se} corner in mound
with trench and pits and deposited
1 pint of charcoal as per instructions

80.00

Set post for corner to sec^s 11, 12, 13 & 14in mound with trench and pits and
deposited 1 pint of charcoal as per instructionsSoil sand 3rd rate producing some grass

Land rolling

Township 3 N Range 2 E East

Chain East on a random line between Sec 12 & 13

Var 19° 55' E

40.00 Set a post for temp gr sec corner

80.19 Intersect East boundary of township
24 links South of the corner to Sec 12, 13, 7 & 18
from which corner I run

S 89° 50' W. on true line between Sec 12 & 13

40.09 1/2 Set a post for gr sec corner in mound
with trench and pits and deposited
1 pint of charcoal as per instructions

80.19 The corner to Sec's, 11, 12, 13 & 14

Soil, light, sandy, 3rd rate

Land rolling, but little ^{undergrowth} vegetation

North between Sec 11 & 12

40.000 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint of charcoal as per instructions

80.00 ~~The corner to Sec's 11, 12, 13 & 14~~ Set post
in mound with trench and pits and
deposited 1 pint of charcoal as per instructions
for cor to sec's 1, 2, 11 & 12

Land level, Soil sandy, 3rd rate

Vegetation scarce

Township 3 N Range 27 East

Chains East On a random line between sec 14/2

Mar 20th E

40.00

Set a post for Temp gr sec corner

80.50

Intersect East boundary of the
township 59 lks South of corner to sec 1.2.6, 47from which corner I run
S 89° 35' W on a true line between sec 14/2

40.25.

Set a post for gr sec corner in ground
with trench and pits and deposited
1 pair of char coal as per instructions

80.50

The corner to sec 1.2. 114/2

Soil, sandy, 3rd rate, Land rolling

North On a random line between sec 14/2

40.00

Set a post for Temp gr sec corner

80.25

Intersect North boundary of township
46 lks West of the corner to sec 1.2.35 & 36

from which corner I run

S 0° 20' N on a true line between sec 14/2

40.25

Set a post for gr sec corner in ground
with trench and pits, and deposited
1 pair of char coal as per instructions

80.25.

The corner to sec 1.2. 114/2

Level level Soil Sand. 4 3rd rateOct. 12th / 60

Township 3 N. Range 27 E.

October 13th 1860

Chains North between Sec 34 & 35

- 40.00 Set a post for gr see corner in mound
with trench and pits and deposited
1 pint of Charcoal, as per instructions
- 80.00 Set a post for corner to Sec 34.35.26 & 27
in mound with trench and pits and
deposited 1 pint of Charcoal as per instructions
Soil 2nd & 3rd rate producing grass
Land high and rolling

East On a random line between Sec 26 & 35
Mar 19th 1857

- 40.00 Set a post for Temp gr see corner
- 79.96 Intersect N & S line 22 lks South
of the corner to Sec 25.26.35 & 36
from which corner I run
S 89° 51' W on a true line between Sec 26 & 35
- 39.98 Set a post for gr see corner in mound
with trench and pits, and deposited
1 pint of Charcoal, as per instructions
- 79.96 The corner to Sec 34.35 26 & 27
Soil 2nd rate
Land high and rolling

Township 3 N. Range 27 E

Chains North between Sec 26 & 27

- 40.00 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint of Charcoal as per instructions
- 80.00 Set a post for corner to Sec 26.27.22 & 23
in mound with trench and pits
and deposited 1 pint charcoal
as per instructions

East on a random line between Sec 23 & 26

Mar 19th 45

- 20.00 Set a post for temp gr sec corner
- 79.79 In tensor N 45° line 50 lbs South
of the corner to Sec 23.24.25 & 26
from which corner I run
S 89° 39' W center line between Sec 23 & 26
to end angular broken hill
- 39.89 1/2 Set a post for gr sec corner in mound
with trench and pits and deposited
1 pint of Charcoal as per instructions
- 44.00 Top of hill 150 ft high enter rolling ground
- 79.79 The corner to Sec 26.27.22 & 23
Sand hilly soil 2nd & 3rd pole

Township 3 N. Range 27 East

Chain North between Sec's 22 & 23

- 40.00 Set a post for gr see corner in mound with trench and pits, and deposited 1 pint of charcoal as per instructions
- 80.00 Set post for corner to Sec's 14, 15, 22 & 23 in mound with trench, and pits and deposited 1 pint of charcoal, as per instructions
Soil sandy, 3rd rate. Sterile
Sand rolling and level

East on a random line between Sec's 14 & 23

Mar 19th 35 'E

- 40.00 Set a post for temp gr see corner
- 79.82 Intersect at & S. line, 49 lbs South of the corner to Sec's 13, 14, 23 & 24 from which corner I run S 89° 39' W on a true line between Sec's 14 & 23
- 39.91 Set post for gr see corner in mound with trench and pits and deposited 1 pint of charcoal as per instructions
- 79.82 The corner to Sec's 14, 15, 22 & 23
Soil, sandy, & sterile
Sand broken

160

(10)

Township 3 N Range 2 E East

Chains North between Sec 14, & 15

40.00 Set post for corner of Sec 10, 11, 14 & 15
in mound with trench and pits and
deposited 1 pint Charcoal as per
instructions

80.00 Set post for corner to Sec 10, 11, 14 & 15
in mound with trench and pits
and deposited 1 pint of charcoal
as per instructions

Soil sandy and barren proving
richly year, & some grass. Soil level

East on Roudon between Sec 11 & 14

Mar 20th

40.00 Set post for Temp gr sec corner

79.87 In Tersect N & S. line 10 lks South
of the corner to Sec 12, 11, 14 & 18
from which corner I run

S 89° 56' W on a true line between Sec 11 & 14

39.93 1/2 Set a post for gr sec corner in mound
with trench and pits and deposited
1 pint of charcoal as per instructions

79.87. The corner 10, 11, 14 & 15, Soil 3rd rate
Soil rolling

Township 3 N Range 27 East

Chain North between Sec 10 & 11

- 40.00 Set post for gr sec corner in ground
with trench and pits and deposited
a pint of charcoal as per instructions
- 80.00 Set a post for corner to Sec 10, 11, 2 & 3
in ground with trench and pits and
deposited a pint of charcoal as per instructions
Soil sandy, 3rd rate
Land broken and rolling

East ^{line} Unrandom between Sec 2 & 11
var 19° 48' E

- 40.00 Set a post for Temp gr sec corner
- 79.70 Intense N & S line
18 lbs South of the corner to Sec 1, 2, 11 & 12
from which corner True
S 89° 52' N a true line between Sec 2 & 11
- 39.85 Set a post for gr sec corner in ground
with trench and pits and deposited
a pint of charcoal as per instructions
- 79.70 The corner to Sec 10, 11, 2 & 3
Soil sandy & barren, some grass and
mucky peat. Land level

162

(121)

Township 3 N. Range 27 E

Chain North on ^{line} Random between Sec's 2 & 3

40.00 Set a post for temp gr sec corner

80.14 Intersect North boundary of township

33 lks west of the corner to sec 2. 3. 10411

from which corner I run

S 0° 14' W on true line between Sec's 2 & 3

40.14 Set post for gr sec corner in ground

with trench and pits and deposited

1 pint Charcoal as per instructions

80.14 The corner to Secs 2. 3. 10411

Soil sandy, sterile producing meadow near

Sand level

Oct 13th 1860October 14th 1860

North between Sec's 33834

40.00 Set post for gr sec corner in ground

with trench and pits and deposited

1 pint of Charcoal as per instructions

80.00 Set post for corner to Sec's 3334. 27428

in ground with trench and pits

and deposited 1 pint of Charcoal

as per instructions

Soil 3rd rate, sandy

Sand rolling

Township 3 N Range 27 East

Chains East ^{line} ~~line~~ Random between Secs 27 & 34
 var $19^{\circ}45'E$

40.00 Set a post for temp gr sec corner

80.30 Intersect N & S line 15-les North of
 The corner to Secs 26, 27, 34 & 35

from which corner I run
 $N 89^{\circ}54'W$ an ^{exact} true line between Secs 27 & 34

40.15 Set a post ^{cut to} for gr sec ~~corner~~ in mound
 with trench, and pits and deposited
 1 pint of Charcoal as per instructions

80.30 The corner to Secs 27, 28, 33 & 34

Soil 3rd rate producing grass
 Land rolling

North between Secs 27 & 28

40.00 Set post for gr sec corner in mound
 with trench and pits and deposited
 1 pint of Charcoal as per instructions

80.00 Set post for corner to Secs 23, 24, 27 & 28
 in mound with trench and pits and
 deposited 1 pint Charcoal as per
 instructions

Soil 3rd rate Sandy
 Land rolling

164

(14)

Township 3 N. Range 27 East

Chains East ~~Qua~~ ^{line} Random between Sec 22 & 27Bear $19^{\circ} 25' E$

- 40.00 Set post for Temp gr Sec corner
- 80.24 Intersect at $45'$ line 35 lbs South
of the corner to Secs 22, 23, 26 & 27
from which corner I run
 $S 89^{\circ} 45' W$ a true line between Sec 22 & 27
- 40.12 Set post for gr Sec corner in ground
with trench and pits and deposited
1 pint of charcoal as per instructions
- 80.24 The corner to Sec's 21, 22, 27 & 28
Soil 3rd rate sandy
& sand rolling

North between Secs 21 & 22

- 40.00 Set post for gr Sec corner in ground
with trench and pits and deposited
1 pint charcoal as per instructions
- 80.00 Set post for corner to Sec's 15, 16, 21, 22
in ground with trench and pits and
deposited 1 pint charcoal as per instructions
Soil 3rd rate sandy
Soil level and rolling

Township 3 N Range 29 East

Chains East and ^{line} Random between Sec's 15 & 22
Mar 19th 55

40.00 Set post for temp gr see corner

80.11 Intersect N. & S line 13 links South
of the corner to Secs 15, 16, 21 & 22

from which corner I run

$389^{\circ}54'N$ on a true line between Secs 15 & 22

40.05 1/2 Set post for gr see corner in mound
with trench and pits and deposited
1 pint of Charcoal as per instructions

80.11 The corner to Secs 15, 16, 21 & 22

Soil 3rd rate Sandy

Level rolling

North between Sec's 15 & 16

40.00 Set post for gr see corner in mound
with trench and pits and deposited
1 pint of Charcoal as per instructions

80.00 The corner to Secs 15, 16, 21 & 19, for which

Set post in mound with trench
and pits, and deposited 1 pint Charcoal
as per instructions

Soil 3rd rate Sandy

Level level

166

(16)

Township 3 N Range 27 E

Chain East on a ^{line} random between Sec 10 & 15

Bearing 19° 50' E

Enter Columbia river bottom

- 411.111 Set post for Corp gr sec corner
 811.111 Intersect N & S line 33 lks South
 of the corner for Secs 10, 11, 14 & 15
 from which corner I run
 S 89° 46' W on a true line between sec 10 & 15
 410.000 Set post for gr sec corner in mound
 with trench and pits and deposited
 1 pint charcoal as per instructions
 80.000 The corner to Secs 9, 10, 15 & 16
 Soil sandy - 3rd rate, Sand rolling

North Between Secs 9 & 10

Enter Columbia river bottom

- 410.000 Set post for gr sec corner in mound
 with trench and pits and deposited
 1 pint of charcoal as per instructions
 80.000 Set post for corner to Secs 3, 4, 9 & 10
 in mound with trench and pits and
 deposited 1 pint charcoal as per instructions
 Soil sandy 3rd rate producing prickly
 pear. Sand level

Township 3 N. Range 27 East

Chains East on ^{line} Random between sec 8 & 10

Cor 20° E

40.00 Set post for temp gr see corner

80.21 Intersect N & S line 48 links South of the corner to sec's 2, 3, 10 & 11

from which corner I run S 89° 39' 1/2 on true line between sec 3 & 10

40.10 1/2 Set post for gr see corner in mound with trench, and pit and deposited 1 pint char coal as per instructions

80.21 The corner to sec 3, 4, 9 & 10
Sand level, Soil sterile, & sandy

North on ^{line} Random between sec 3 & 4

40.00 Set post for temp gr see corner

80.54 Intersect North boundary of Township 48 lks west of the corner to sec 3, 4, 33, & 34 from which corner I run S. 11° 21' 1/2 on true line between sec 3 & 4

40.54 Set post for gr see corner in mound with trench and pit and deposited 1 pint char coal as per instructions

80.54 The corner to sec 9, 10, 33 & 34
Soil 3rd rate Sandy Sand level, Oct 14/60

168

(18)

Townships 3 N Range 27 East

Chains, October 15th 1860

North between Sec's 32 & 33

40.00 Set post for gr see corner in mound
with trench and pits and deposited
1 pint of charcoal, as per instructions

80.00 Set post for corner to Sec's 32, 33, 28 & 29
in mound with trench and pits and
deposited 1 pint of charcoal as per instructions
Soil 2nd & 3rd rate producing grass
Land high and rolling

East ^{v line} on a random between Sec's 28 & 33Mar 19th 55th

40.00 Set post for temp gr see corner

79.50 Intersect N & S boundary 25 lbs South
of the corner to Sec's 27, 28, 33 & 34

from which corner I run
S 89° 49' W on true line between Sec's 28 & 33

39.75 Set post for gr see corner in mound
with trench and pits and deposited
1 pint of charcoal as per instructions

79.50 The corner to Sec's 32, 33, 28 & 29
Soil 3rd rate Sandy Land rolling

Township 3 N Range 27 East

Chains North between Sec's 28 & 29

40.00 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint Charcoal as per instructions

80.00 Set post for corner to Sec's 20, 21, 28 & 29
in mound with trench and pits
and deposited 1 pint Charcoal as per instructions

Soil Sandy 3rd rate

Some on South post broken, remainder rolling

East. ^{v line} ~~One~~ random between Secs 21 & 28

Bear 19° 45' E

40.00 Set post for Temp gr sec corner

79.51 Intersect N & S line 41 kts south
the corner to Secs 21, 22, 27 & 28

from which corner I run

S 89° 58' W on true line between Sec's 21 & 28

39.75 1/2 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint of Charcoal as per instruction

79.57 The corner to Secs 21, 22, 27 & 28

Soil 3rd rate sandy

Land rolling

170

(201)

Township 3 N. Range 27 East

Chains North between Secs 20 & 21

40.00 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint charcoal as per instructions

80.00 Set post for corner to Secs 17, 16, 20 & 21
in mound with trench and pits
and deposited 1 pint charcoal as per
instructions

Soil sandy 3rd rate
Land broken

East on a ^{line} Random between Sec 16 & 21
Bearing $19^{\circ}45'E$

40.00 Set post for Temp gr sec corner

79.60 Intersect N & S line 17 lks north
of the corner to Secs 15, 16, 21 & 22

from which corner I run
N $89^{\circ}53'W$ on true line between Sec 16 & 21

3980 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint charcoal as per instructions

79.60 The corner to Secs 16, 17, 20 & 21
Soil 3rd rate, sandy, Land rolling

(2nd)

Township 3 N Range 27 E

170

Chains North between sec 16 & 17

40.00 Set post for gr sec corner in mound with trench and pits and deposited 1 pint of Charcoal as per instructions

80.00 Set post corner for Secs 8, 9, 16 & 17 in mound with trench and pits and deposited 1 pint Charcoal as per instructions

Soil 3rd rate land rolling and level

East On a ^{line} random between sec 16 & 9

40.00 Mar 1945-5 E

40.00 Set post for Temp gr sec corner

80.10 Intersect N & S line 30 lks north of the corner to Sec's 9, 10, 15 & 16

from which corner I run N 89° 47' W on true line between sec 9 & 16

40.05 Set post for gr sec corner in mound with trench and pits and deposited 1 pint Charcoal as per instruction

80.10 The corner to Sec's 8, 9, 16 & 17

Soil 3rd rate sandy producing thickly near. Land level

172

{ 22 }

Township 3 N Range 27 East

Chains North between Sec 8 and 9

40.00 Set post for gr sec corner in ground with trench and pits and deposited 1 pint of Charcoal, as per instructions Enter Columbia river bottom

80.00 Set post for corner to Sec 4.5.849 in ground with trench and pits and deposited 1 pint charcoal as per instructions Soil 3rd rate sandy producing much pear, and some grass Land level

East line random ^{v line} between Sec 4 & 9

Bar 20° E

40.00 Set post for Temp gr sec corner

79.93 Intersect N & S line 22 lks North of the corner to Sec 3.4.9410

from which corner I run

N 89° 37' 34" on true line between Sec 4 & 9

39.96 1/2 Set post for gr sec corner in ground with trench and pits and deposited 1 pint of Charcoal as per instructions

79.93 The corner to Sec 4.5.849

Soil 3rd rate sandy Land level

Township 3 N Range 27 East

Chain North on a ^{line} Random between sec 4 & 5

40.00 Set post for temp gr see corner

80.39 Intersect North boundary of township

55 lks West of the Corner to see 4.5.32 & 33

from which Corner I run

S 0° 24' W true line between sec 4 & 5

40.39 Set post for gr see corner in mound

with trench and pits and deposited

a pair of char coal as per instructions

80.39 The corner to see 4.5.8 & 9

Soil 3rd rate Sandy, thick growth of pickypear. Land level and rolling ^{Oct 15th 1860.}October 15th 1860

North between sec 31 & 32

40.00 Set post for gr see corner in mound

with trench and pits, and deposited

a pair of char coal as per instructions

80.00 Set post for corner to sec 31.32, 29 & 30

in mound with trench and pits and dep-

osited a pair of char coal, as per instructions

Soil 3rd rate Sandy

Land high & rolling

174

(24)

Township 3 N Range 27 East

Chains East on a random ^{line} between sec's 29 & 32

Cor 19° 50' E

40.00 Set post for Temp gr see corner

80.41 Intersect N & S line 4000 ft South
of the corner to sec's 28, 29, 32 & 33from which corner I run
S 89° 43' 30" E on true line between sec's 29 & 3240.20 1/2. Set post for gr see corner in ground
with trench and pits and deposited
1 pint charcoal, as per instructions80.41 The corner to sec's 29, 30, 31 & 32
Soil 2nd & 3rd rate Sand well & rollingWest on a random ^{line} between sec's 30 & 31

40.00 Set post for Temp gr see corner

85.50 Intersect West boundary of township

at the corner to sec's 30, 31, 32 & 36

from which corner I run
East on true line between sec's 30 & 3145.50 Set post for gr see corner in ground
with trench and pits and deposited
1 pint of charcoal as per instructions

85.50 The corner to sec's 30, 31, 32 & 29

Soil 3rd rate Sandy Sand gently rolling

Township 3 N Range 27 East

Chains North between Sec 29 & 30

- 40.00 Set post for gr sec corner in mound
with trench, and pits, and deposited
1 pint of charcoal as per instructions
- 80.00 Set post for corner to Sec 19, 20, 29 & 30
in mound with trench and pits, and
deposited 1 pint charcoal, as per instructions
Soil 3rd rate, & sandy
Sand rolling

East on a random line between Sec 20 & 29
Cor 20° 8'

- 40.00 Set post for temp gr sec corner
- 80.10 Intersect N & S line 35 lks South of
the corner to Sec 20, 21, 28 & 29
from which corner I run
S 89° 45' 30" on true line between Sec 20 & 29
- 40.05 Set post for gr sec corner in mound
with trench and pits and deposited
1 pint of charcoal, as per instructions
- 80.10 The corner to Sec 19, 20, 29 & 30
Soil sandy 3rd rate
Sand rolling

176

(26)

Township 3 N. Range 27 East

Chain West line ^{line} between Secs 19 & 30

40.00 Set post for temp gr sec corner

85.55 Intersect West boundary of Township

29 lks South of the corner to Secs 24, 25, 19 & 30

from which corner I run

S 89° 48' E on true line between Secs 19 & 30

45.55 Set post for gr sec corner in ground
with trench, and pits and deposited
1 pint of Charcoal, as per instructions

85.55 The corner to Secs 19, 20, 29 & 30

Soil 3rd rate Sandy

Land rolling

North between Secs 19 & 20

40.00 Set post for gr sec corner in ground
with trench, and pits and deposited
1 pint Charcoal, as per instruction

80.00 Set post for corner to Secs 17, 18, 19 & 20

in ground with trench and pits and
deposited 1 pint Charcoal as per instructionSoil 3rd rate, Sandy prairie, but little
vegetation. Land rolling.

Township 3 N Range 27 East

Chains East or random ^{line} between Secs 17 & 20

Mar 19th 50th E

40.00 Set post for ^{temp} gr see corner in ground

80.55 Intersect ^{line} N & S line 30 lks South of the corner to Secs 16, 17, 20 & 21

from which corner I run S 89° 47' W. On true line between Secs 17 & 20

40.27 1/2 Set post for gr see corner in ground with trench and pits and deposited 1 pint Char coal, as per instructions

80.55 See corner to Secs 17, 18, 19 & 20

Soil 3rd rate, Sandy, Sand rolling to 18th Oct

October 16th 1860

West or random ^{line} between Secs 18 & 19

40.00 Set post for Temp gr see corner

84.85 Intersect West boundary of township 2 lks North of the corner to Secs 18, 19, 20 & 21

from which corner I run N 89° 59' E on true line between Secs 18 & 19

44.85 Set post for gr see corner in ground with trench and pits and deposited 1 pint of charcoal, as per instructions

84.85 The corner to Secs 17, 18, 19 & 20. Soil 3rd rate Sand rolling

178

(28)

Township 3 N. Range 27 East

Chains North between Secs 17 & 18

40.00 Set post for gr sec corner in mound
with trench and pits, and deposited
1 pint of charcoal as per instructions

80.00 Set post for corner to sec 7.8.17 & 18
in mound with trench and pits and
deposited 1 pint charcoal as per instructions
Soil 3rd rate, sandy,
Sand level and rolling

East on a random line between Secs 8 & 17
(on $20^{\circ} 5' E$)

40.00 Set post for temp gr sec corner

80.15 Set post N & S line 22 lks south
of the corner to sec 16.17. 8 & 9
from which corner I run

S $89^{\circ} 51' W$ on true line between Secs 8 & 17

40.07 $\frac{1}{2}$ Set post for gr sec corner in mound
with trench and pits, and deposited
1 pint charcoal as per instructions

80.15 The corner to sec 7.8.17 & 18
Soil sandy 3rd rate
Sand broken and rolling

Township 3 N. Range 27 East

179

Chain West on Random between Sec 7 & 18

40.00 Set post for temp gr see corner

84.25 Intersect West boundary of township

25 lbs North of the corner to sec^s 12, 13, 7 & 18

from which corner I run

N 89° 5' 0" E on true line between sec^s 7 & 1844.25 Set post for gr see corner in ground, with
trench and pits and deposited 1 pint
of charcoal, as per instructions84.25 The corner to sec^s 7, 8, 17 & 18.Soil sandy 3rd rate producing considerable
grass. Land level & rolling

North between Secs 7 & 8

Enter Columbia river bottom

40.00 Set post for gr see corner in ground
with trench and pits and deposited
1 pint charcoal as per instruction80.00 Set post for corner to Secs 5, 6, 7 & 8 in
ground with trench and pits and
deposited 1 pint charcoal, as per instructionSoil 3rd rate sandy producing spickly
pear. Land level

180

(30)

Township 3 N Range 27 East

Chains East on ^{line} Random between Secs 5 & 8
Var 20° E

- 40.00 Set post for temp gr see corner
 79.85 Intersect N & S line 20 lks South
 of the corner to Secs 4, 5, 8 & 9
 from which corner I run
 S 89° 51' W on true line between Secs 5 & 8
 39.92½. Set post for gr see corner in mound
 with trench and pits and deposited
 1 pint of Charcoal as per instructions
 79.85. The corner to Secs 5, 6, 7 & 8
 Soil 3rd rate, Sandy proving some
 grass & prickly pear. Sand level

West end ^{line} Random between Secs 6 & 7

- 40.00 Set post for temp gr see corner
 84.15 Intersect West boundary of Township
 41 links North of the corner to Secs 6, 7, 11 & 12
 from which corner I run
 N. 89° 43' E on true line between Secs 6 & 7
 44.15 Set post for gr see corner in mound
 with trench and pits and deposited
 1 pint Charcoal as per instructions
 84.15 The corner to Secs 5, 6, 7 & 8. Soil 3rd rate Sand level

Township 3 N. Range 27 East

Chairs North ^{line} ~~arbitrary~~ ^{line} between Secs 5 & 6

40.00 Set post for Temp gr see corner

80.61 Intersect North boundary of Township

34 links West of the corner to Secs 31, 32, 5 & 6

from which corner I run

S 0° 15' W on true line between Secs 5 & 6

40.61 Set post for gr see corner in ground

with trench and pits and
deposited 1 pint of charcoal
as per instructions

80.61 The corner to Secs 5, 6, 7 & 8

Soil 3rd rate sandy

producing aundance of prickly pear and

but little grass

Land gently rolling

October 1st 1860.

182

General Description

The Soil in this township is ~~not~~
below the common average, being prin-
cipally of the 3rd rate quality, in the hills
and table land it is adapted to the growth
of bunch grass. On the ^{extreme} North part of the
Township it is composed of heavy sand pro-
ducing but little vegetation, except the
prickly pear, which grows here in abundance
The land is all open prairie, and destitute
of water, except at the S.E. corner of the
township, where Butter creek passes through
it.

List of Names

A list of the names of the individuals employed to assist in running measuring or marking the lines and corners, described in the foregoing field notes of Township 3 North of the base line of Range No 27 East of the Willamette Meridian showing the respective capacities in which they acted

Jacob McDaniel	Chairman
C H Miller	Chairman
J. M. Mansfield	Assessors

We hereby certify that we assisted
 Ebenezer E. Hoast deputy Surveyor
 in subdividing Township Number
 Three North of the Base line of
 Range No Twenty Seven East of
 the Willamette Meridian, and that
 said Township has been ^{in all respects} to the best
 of our knowledge and belief well
 and faithfully surveyed, and the
 boundary monuments planted
 according to the instructions fur-
 -nished by the Surveyor General

Jacob McDaniel Chairman
 C. H. Miller Chairman
 J. H. Mansfield Assessor

Subscribed and sworn to in
 presence of Ebenezer E. Hoast, deputy Surveyor,

before me a Justice of the Peace for Wasco
 County in the State of Oregon this
 30th day of October 1860

J. B. Hodgdon.

Justice of the Peace

O. Ebenzer, & Hoast deputy surveyor
do solemnly swear, that in pursuance
of a contract with W. W. Chapman Surveyor
of the public lands of the United States
& dated the 11th September 1860
for the State of Oregon, and in strict
conformity to the laws of the United
States, and the instructions furnished by
the said Surveyor General, I have
faithfully surveyed the subdivision
of Township No. 3 North of the base line
of Range No. 7 East of the Willamette
Meridian, in the state aforesaid, and do
further solemnly swear that the foregoing
are the true and original field notes of
such survey

Ebenzer, & Hoast

Deputy Surveyor

Subscribed, and sworn to by said Ebenzer
& Hoast, deputy surveyor, before me a Notary
Public for Lane County in the State of
Oregon this 11th day of November 1860

A. W. Patterson

Not. Pub

187

Surveyor General's Office.
Eugene City, Dec. 31st 1860.
The foregoing field notes of the
Survey of the Subdivisions of
Township No. 3 N. R. 27 East
of the Willamette Meridian
Oregon, executed by Ebenezer C.
Haft, deputy Surveyor, under his
contract of the 11th of September
1860. having been critically ex-
amined, the necessary corrections
and explanations made, the
said field notes and the sur-
veys they describe are here-
by approved.

A. W. Chapman

Sur. Genl. of Oregon